

VOLUME 2
Technical Appendixes

Removal Site
Assessment Report



Reynolds Metals Company
TROUTDALE FACILITY
OPERABLE UNIT 1

CH2M HILL

JANUARY 1995

1.4.1



33477



**Printed on
Recycled and
Recyclable
Paper**

OPE39293.B3.05

Contents

- Appendix A . Soil and Groundwater Tracking Data Tables
- Appendix B Soil and Test Pit Logs
- Appendix C Geo Recon Electrical Resistivity Survey Report
- Appendix D Monitoring Well Geologic Logs and Well Construction Diagrams
- Appendix E RMC Production Well and Sampled Offsite Well Geologic and Well Drillers' Logs
- Appendix F Quality Assurance Sampling Plan

Appendix A
Soil and Groundwater Tracking Data Tables

Soil Tracking Data Tables

Soil Tracking Data

Matrix	Sample ID	Collection Date	Add. Anal. Date	Beg depth	End depth	Lab #	Lab Results In (a)	Cyanide-Total	Fluoride	Hardness	Metals-13(PP)	Metals-23(CLP)	Metals-Dissolved	PAH	TPAH-S	PCB	PCB-S	Pesticides-Chlor.	TCLP	TOC	TPH	TPH 418_1	TPH-1l glass	TPH-S	TPH-VOA bottle	
North Landfill East Area																										
S	E-H-W1	6/20/94		0	0	94-1672	F									X			X							
S	E-H-W2	6/20/94		0	0	94-1672	F									X			X							
S	E-H-W3	6/20/94		0	0	94-1672	F									X			X							
S	E-H-W4A	6/20/94		0	0	94-1672	F														X					
S	E-H-W5	6/20/94		0	0	94-1672	F									X			X							
S	S-H-N3A	6/20/94		0	0	94-1672	F														X					
North Landfill West Area																										
S	EHW1-C	7/20/94		0	0	94-2017	F	X	X		X				X		X									
S	EHW1-C	7/20/94	8/1/94	0	0	94-2017	F									X										
S	EHW1-S	7/20/94	8/1/94	0	0	94-2017	F										X									
S	EHW1-2	7/20/94	8/1/94	2	2	94-2017	F										X									
S	EHW1-5	7/20/94	8/1/94	5	5	942017	F										X									
S	EHW2-C	7/20/94		0	0	94-2017	F	X	X		X				X		X									
S	EHW2-C	7/20/94	8/1/94	0	0	94-2017	F									X										
S	EHW2-S	7/20/94	8/1/94	0	0	94-2017	F										X									
S	EHW2-2	7/20/94	8/1/94	2	2	94-2017	F										X									
S	EHW2-5.5	7/20/94	8/1/94	5.5	5.5	94-2017	F										X									
S	EHW3-C	7/19/94		0	0	94-2007	F	X	X		X				X		X									
S	SHN1-C	7/20/94		0	0	94-2017	F	X	X		X				X		X									
S	SHN2-C	7/20/94		0	0	94-2017	F	X	X		X				X		X									
S	SHN3-C	7/20/94		0	0	94-2017	F	X	X		X				X		X									
S	SHN4-C	7/18/94		0	0	94-2007	F	X	X		X				X		X									
South Potliner																										
S	SP1-C	7/20/94	8/1/94	0	0	94-2017	F															X				
S	SP1-C	7/20/94		0	0	94-2017	F	X	X						X		X									
S	SP2-C	7/20/94	8/1/94	0	0	94-2032	F							X												
S	SP2-C	7/20/94		0	0	94-2032	F	X	X		X				X		X									
S	SP2-2.5	7/20/94	8/1/94	2.5	2.5	94-2032	F								X											
S	SP2-5.0	7/20/94	8/1/94	5	5	94-2032	F								X											
S	SP3-C	7/21/94		0	0	94-2032	F	X	X		X				X		X									
S	SP3-CD	7/21/94		0	0	94-2032	F	X	X		X				X		X									
S	SP4-C	7/21/94		0	0	94-2032	F	X	X		X				X		X									
S	SP4-C	7/21/94	8/1/94	0	0	94-2032	F							X												
S	SP4-3.0	7/21/94	8/1/94	3	3	94-2032	F								X											
S	SP5-C	7/21/94		0	0	94-2032	F	X	X		X				X		X									
S	SP5-3.0	7/21/94	8/1/94	3	3	94-2032	F								X											
S	SP6-C	7/21/94		0	0	94-2032	F	X	X		X				X		X									
S	SP6-CD	7/21/94		0	0	94-2032	F	X	X		X				X		X									
S	SP6-CD	7/21/94	8/1/94	0	0	94-2032	F							X												
S	SP6-3.0	7/21/94	8/1/94	3	3	94-2032	F								X											
S	SP7-C	7/21/94		0	0	94-2032	F	X	X		X				X		X									
S	SP7-2.5	7/21/94	8/1/94	2.5	2.5	94-2032	F								X											
S	SP8-C	7/21/94		0	0	94-2032	F	X	X		X				X		X									
S	SP8-2.5	7/21/94	8/1/94	2.5	2.5	94-2032	F								X											
S	SP9-C	7/21/94		0	0	94-2032	F	X	X		X				X		X									
S	SP9-2.5	7/21/94	8/1/94	2.5	2.5	94-2032	F								X		X									
S	SP9-5.0	7/21/94	8/1/94	5	5	94-2032	F								X		X									
S	SP10-C	7/21/94		0	0	94-2032	F	X	X		X				X		X									
S	SP10-C	7/21/94	8/1/94	0	0	94-2032	F							X		X										
S	SP10-4.0	7/21/94	8/1/94	4	4	94-2032	F								X		X									
S	SP11-C	7/21/94		0	0	94-2032	F	X	X		X				X		X									

Soil Tracking Data

Matrix	Sample ID	Collection Date	Add. Anal. Date	Beg depth	End depth	Lab #	Lab Results In (a)	Cyanide-Total	Fluoride	Hardness	Metals-13(PP)	Metals-23(CLP)	Metals-Dissolved	PAH	TPAH-S	PCB	PCB-S	Pesticides-Chlor.	TCLP	TOC	TPH	TPH 418_1	TPH-1l glass	TPH-S	TPH-VOA bottle	
Additional South Potliner																										
S	B2-2	9/13/94	9/15/94	2	2	94-2643	F							X	X											
S	B2-4	9/13/94	9/15/94	4	4	94-2643	F							X	X	X	X									
S	B2-6	9/13/94		6	6	94-2643	F							X		X										
S	B2-6	9/13/94	9/15/94	6	6	94-2643	F								X		X									
S	B2-C	9/13/94		0	0	94-2643	F	X	X		X				X		X									
S	B2-C	9/13/94	9/15/94	0	0	94-2643	F							X												
S	C1.5-C	9/13/94		0	0	94-2643	F	X	X		X				X		X									
S	C1.5-C	9/13/94	9/15/94	0	0	94-2643	F							X												
S	C1-5.6	9/13/94		6	6	94-2643	F							X		X										
S	C1-5.6	9/13/94	9/15/94	6	6	94-2643	F								X		X									
S	D4-6	9/13/94		6	6	94-2643	F							X		X										
S	D4-6	9/13/94	9/15/94	6	6	94-2643	F								X		X									
S	D4-8	9/13/94		8	8	94-2643	F							X												
S	D4-8	9/13/94		8	8	94-2643	F									X										
S	D4-8	9/13/94	9/15/94	8	8	94-2643	F									X		X								
S	D4-C	9/13/94		0	0	94-2643	F	X	X		X				X		X									
S	D4-C	9/13/94	9/15/94	0	0	94-2643	F							X												
S	E2-C	9/13/94		0	0	94-2643	F	X	X		X				X		X									
S	E2-C	9/13/94	9/15/94	0	0	94-2643	F							X												
S	E5-C	9/13/94		0	0	94-2643	F	X	X		X				X		X									
S	E5-C	9/13/94	9/15/94	0	0	94-2643	F							X												
East Potliner																										
S	EP1-S	7/22/94	9/27/94	0	0	94-2047	F										X									
S	EP2-S	7/22/94	9/27/94	0	0	94-2047	F										X									
S	EP3-S	7/22/94	9/27/94	0	0	94-2047	F										X									
S	EP4-S	7/22/94	9/27/94	0	0	94-2047	F										X									
S	EP5-S	7/22/94	9/27/94	0	0	94-2047	F										X									
S	EP6-S	7/22/94	9/27/94	0	0	94-2047	F										X									
S	EP7-S	7/22/94	9/27/94	0	0	94-2047	F										X									
S	EP8-S	7/22/94	9/27/94	0	0	94-2047	F										X									
S	EP1-C	7/22/94		0	0	94-2047	F	X	X						X											
S	EP2-C	7/22/94		0	0	94-2047	F	X	X						X											
S	EP2-CD	7/22/94		0	0	94-2047	F	X	X						X											
S	EP3-C	7/22/94		0	0	94-2047	F	X	X						X											
S	EP4-C	7/22/94		0	0	94-2047	F	X	X						X											
S	EP5-C	7/22/94		0	0	94-2047	F	X	X						X											
S	EP6-C	7/22/94		0	0	94-2047	F	X	X						X											
S	EP7-C	7/22/94		0	0	94-2047	F	X	X						X											
S	EP8-C	7/22/94		0	0	94-2047	F	X	X						X											
Cryolite Ponds																										
S	CP1-C	7/25/94		0	0	94-2060	F	X							X		X									
S	CP1-5.0	7/25/94	9/9/94	5	5	94-2060	F		X																	
S	CP1-C	7/25/94	9/9/94	0	0	94-2060	F				X															
S	CP2-C	7/25/94		0	0	94-2060	F	X							X		X									
S	CP2-C	7/25/94	9/9/94	0	0	94-2060	F				X															
S	CP2-10.5	7/25/94		10.5	10.5	94-2060	F	X							X		X									
S	CP3-S	7/25/94	8/3/94	0	0	94-2060	F	X	X						X		X									
S	CP3-S	7/25/94	9/9/94	0	0	94-2060	F		X																	
S	CP3-1.2	7/25/94	8/3/94	1.2	1.2	94-2060	F	X							X		X									
S	CP3-1.2	7/25/94	9/9/94	1.2	1.2	94-2060	F		X		X															
S	CP4-S	7/25/94	8/3/94	0	0	94-2060	F	X							X		X									
S	CP4-S	7/25/94	9/9/94	0	0	94-2060	F		X																	
S	CP4-2.5	7/25/94	8/3/94	2.5	2.5	94-2060	F	X							X		X									
S	CP4-2.5	7/25/94	9/9/94	2.5	2.5	94-2060	F		X		X															

Soil Tracking Data

Matrix	Sample ID	Collection Date	Add. Anal. Date	Beg depth	End depth	Lab #	Lab Results In (a)	Cyanide-Total	Fluoride	Hardness	Metals-13(PP)	Metals-23(CLP)	Metals-Dissolved	PAH	TPAH-S	PCB	PCB-S	Pesticides-Chlor.	TCLP	TOC	TPH	TPH 418_1	TPH-1l glass	TPH-S	TPH-VOA bottle	
S	CP5-C	7/28/94		0	0	94-2101	F	X	X						X		X									
S	CP5-C	7/28/94	9/9/94	0	0	94-2101	F				X															
S	CP5-3.0	7/28/94	9/9/94	3	3	94-2101	F		X																	
S	CP6-C	7/28/94		0	0	94-2101	F	X	X						X		X									
S	CP6-C	7/28/94	9/9/94	0	0	94-2101	F				X															
S	CP6-3.0	7/28/94	9/9/94	3	3	94-2101	F		X																	
Parking Lot																										
S	P1-1-3	7/25/94		1	3	94-2060	F	X							X		X									
S	P1-3-5	7/25/94		3	5	94-2060	F	X							X		X									
S	P1-5-7	7/25/94		5	7	94-2060	F	X							X		X									
S	P2-1-3	7/25/94		1	3	94-2060	F	X							X		X									
S	P2-3-5	7/25/94		3	5	94-2060	F	X							X		X									
S	P2-5-7	7/25/94		5	7	94-2060	F	X							X		X									
S	P3-1-3	7/25/94		1	3	94-2060	F	X							X		X									
S	P3-3-5	7/25/94		3	5	94-2060	F	X							X		X									
S	P3-5-7	7/25/94		5	7	94-2060	F	X							X		X									
S	P4-1-3	7/25/94		1	3	94-2060	F	X							X		X									
S	P4-3-5	7/25/94		3	5	94-2060	F	X							X		X									
S	P4-5-7	7/25/94		5	7	94-2060	F	X							X		X									
South Wetlands																										
S	SW1-C	7/26/94		0	0	94-2070	F	X	X						X		X	X								
S	SW1-C	7/26/94	8/1/94	0	0	94-2070	F																	X		
S	SW1-C	7/26/94	9/9/94	0	0	94-2070	F				X															
S	SW2-C	7/26/94		0	0	94-2070	F	X	X						X		X	X								
S	SW2-C	7/26/94	8/1/94	0	0	94-2070	F															X				
S	SW2-C	7/26/94	9/9/94	0	0	94-2070	F				X															
S	SW3-C	7/26/94		0	0	94-2070	F	X	X						X		X	X								
S	SW3-C	7/26/94	8/1/94	0	0	94-2070	F																	X		
S	SW3-C	7/26/94	9/9/94	0	0	94-2070	F				X															
S	SW4-C	7/25/94		0	0	94-2070	F	X	X						X		X	X								
S	SW4-C	7/25/94	8/1/94	0	0	94-2070	F																	X		
S	SW4-C	7/25/94	9/9/94	0	0	94-2070	F				X															
S	SW5-C	7/25/94		0	0	94-2070	F	X	X						X		X	X								
S	SW5-C	7/26/94	9/9/94	0	0	94-2070	F				X															
Scrap Yard																										
S	SY1-C	7/25/94		0	0	94-2060	F								X											
S	SY1-C	7/25/94	8/1/94	0	0	94-2060	F	X	X					X			X									
S	SY1-2.0	7/25/94	8/1/94	2	2	94-2060	F								X											
S	SY1-4.0	7/25/94	8/1/94	4	4	94-2060	F								X											
S	SY2-C	7/25/94		0	0	94-2060	F								X											
S	SY2-C	7/25/94	8/1/94	0	0	94-2060	F										X									
S	SY2-C	7/25/94	8/1/94	0	0	94-2060	F	X	X																	
S	SY2-2.0	7/25/94	8/1/94	2	2	94-2060	F								X											
S	SY2-4.0	7/25/94	8/1/94	4	4	94-2060	F								X											
S	SY3-C	7/25/94		0	0	94-2060	F	X	X						X		X									
S	SY3-C	7/25/94	8/1/94	0	0	94-2060	F				X															
S	SY4-C	7/26/94		0	0	94-2070	F								X											
S	SY4-C	7/26/94	8/1/94	0	0	94-2070	F	X	X								X									
S	SY5-C	7/26/94		0	0	94-2070	F				X				X											
S	SY5-C	7/26/94	8/1/94	0	0	94-2070	F	X	X								X									
S	SY6-S	7/26/94		0	0	94-2070	F								X											
S	SY6-S	7/26/94	8/1/94	0	0	94-2070	F	X	X								X									
S	SY7-S	7/26/94		0	0	94-2070	F								X											
S	SY7-S	7/26/94		0	0	94-2070	F	X	X																	
S	SY7-S	7/26/94	8/1/94	0	0	94-2070	F										X									

Soil Tracking Data

Matrix	Sample ID	Collection Date	Add. Anal. Date	Beg depth	End depth	Lab #	Lab Results In (a)	Cyanide-Total	Fluoride	Hardness	Metals-13(PP)	Metals-23(CLP)	Metals-Dissolved	PAH	TPAH-S	PCB	PCB-S	Pesticides-Chlor.	TCLP	TOC	TPH	TPH 418_1	TPH-11 glass	TPH-S	TPH-VOA bottle	
S	SY8-C	7/26/94		0	0	94-2070	F				X				X											
S	SY8-C	7/26/94	8/1/94	0	0	94-2070	F										X									
S	SY8-C	7/26/94	8/1/94	0	0	94-2070	F	X	X																	
S	SY9-C	7/26/94		0	0	94-2070	F								X											
S	SY9-C	7/26/94	8/1/94	0	0	94-2070	F	X	X								X									
S	SY10-C	7/26/94		0	0	94-2070	F								X											
S	SY10-C	7/26/94	8/1/94	0	0	94-2070	F	X	X								X									
S	SY11-C	7/26/94		0	0	94-2070	F								X											
S	SY11-C	7/26/94	8/1/94	0	0	94-2070	F	X	X								X									
S	SY12-C	7/25/94		0	0	94-2060	F								X											
S	SY12-C	7/25/94	8/1/94	0	0	94-2060	F	X	X						X		X									
S	SY13-C	7/25/94		0	0	94-2060	F								X											
S	SY13-C	7/25/94	8/1/94	0	0	94-2060	F	X	X								X									
S	SY14-C	7/25/94		0	0	94-2060	F								X											
S	SY14-C	7/25/94	8/1/94	0	0	94-2060	F	X	X					X			X									
S	SY14-2.0	7/25/94	8/1/94	2	2	94-2060	F								X											
S	SY14-4.0	7/25/94	8/1/94	4	4	94-2060	F								X											
S	SY15-C	7/25/94		0	0	94-2060	F								X											
S	SY15-C	7/25/94	8/1/94	0	0	94-2060	F	X	X								X									
Reconnaissance																										
S	ND-1-S	8/4/94		0	0	94-2178	F	X							X											
S	ND-2-S	8/4/94		0	0	94-2178	F	X							X											
S	OR-1-S	8/4/94		0	0	94-2178	F	X							X											
S	SPWP-B	8/26/94		0	0	94-2441	F	X	X		X			X	X	X	X									
S	SPWP-A	8/26/94		0	0	94-2441	F	X	X		X			X	X	X	X									
S	SW-6-S	8/4/94		0	0	94-2178	F	X	X						X											
West Field																										
S	WF1-2.0	9/23/94		2	2	94-2808	F	X	X																	
S	WF2-2.0	9/23/94		2	2	94-2808	F	X	X																	
S	WF3-2.0	9/23/94		2	2	94-2808	F	X	X																	
Sediment																										
SD	RM-SD1	8/18/94		0	0	94-2359	F	X	X			X		X		X				X				X		
SD	RM-SD2	8/18/94		0	0	94-2359	F	X	X			X		X		X				X				X		
SD	RM-SD3	8/18/94		0	0	94-2359	F	X	X			X		X		X				X				X		
SD	RM-SD4	8/18/94		0	0	94-2359	F	X	X			X		X		X				X				X		
SD	RM-SD5	8/19/94	8/19/94	0	0	94-2373	F	X	X			X		X		X				X				X		
SD	RM-SD5D	8/19/94	8/19/94	0	0	94-2373	F	X	X			X		X		X				X				X		
SD	RM-SD6	8/19/94	8/19/94	0	0	94-2373	F	X	X			X		X		X				X				X		
SD	RM-SD7	8/19/94	8/19/94	0	0	94-2373	F	X	X			X		X		X				X				X		
SD	RM-SD8	8/19/94	8/19/94	0	0	94-2373	F	X	X			X		X		X				X				X		
SD	RM-SD9	8/19/94	8/19/94	0	0	94-2373	F	X	X			X		X		X				X				X		
SD	RM-SD10	8/19/94	8/19/94	0	0	94-2373	F	X	X			X		X		X				X				X		
SD	RM-SD11	8/19/94	8/19/94	0	0	94-2373	F	X	X			X		X		X				X				X		
SD	RM-SD12	8/18/94		0	0	94-2359	F	X	X			X		X		X				X				X		
SD	RM-SD13	8/18/94		0	0	94-2359	F	X	X			X		X		X				X				X		
SD	RM-SD14	8/18/94		0	0	94-2359	F	X	X			X		X		X				X				X		
SD	RM-SD14D	8/18/94		0	0	94-2359	F	X	X			X		X		X				X				X		
SD	RM-S15	8/18/94		0	0	94-2359	F	X	X			X		X		X				X				X		
SD	RM-S16	8/18/94		0	0	94-2359	F	X	X			X		X		X				X				X		
SD	RM-S17	8/18/94		0	0	94-2359	F	X	X			X		X		X				X				X		
SD	RM-SD18	8/19/94	8/19/94	0	0	94-2373	F	X	X			X		X		X				X				X		

Soil Tracking Data

Matrix	Sample ID	Collection Date	Add. Anal. Date	Beg depth	End depth	Lab #	Lab Results In (a)	Cyanide-Total	Fluoride	Hardness	Metals-13(PP)	Metals-23(CLP)	Metals-Dissolved	PAH	TPAH-S	PCB	PCB-S	Pesticides-Chlor.	TCLP	TOC	TPH	TPH 418_1	TPH-1l glass	TPH-S	TPH-VOA bottle
	Surface Water																								
SW	RM-SW1	8/18/94		0	0	94-2360	F	X	X	X		X		X		X								X	
SW	RM-SW3	8/18/94		0	0	94-2360	F	X	X	X		X		X		X								X	
SW	RM-SW5	8/19/94		0	0	94-2374	F	X	X	X		X		X		X								X	
SW	RM-SW6	8/19/94		0	0	94-2374	F	X	X	X		X		X		X								X	
SW	RM-SW10	8/19/94		0	0	94-2374	F	X	X	X		X		X		X								X	
SW	RM-SW11	8/18/94		0	0	94-2360	F	X	X	X		X		X		X								X	
SW	RM-SW14	8/18/94		0	0	94-2360	F	X	X	X		X		X		X								X	
SW	RM-SW14D	8/18/94		0	0	94-2360	F	X	X	X		X		X		X								X	
SW	RM-SW18	8/19/94		0	0	94-2374	F	X	X	X		X		X		X								X	
	Miscellaneous Area																								
	Stressed Area																								
S	SP5-SA1-C	7/26/94	9/9/94	0	0	94-2070	F	X	X		X				X		X	X							
S	SP5-SA2-C	7/26/94		0	0	94-2070	F	X	X						X		X	X							
S	SP5-SA2-C	7/26/94	9/9/94	0	0	94-2070	F				X														
	Notes:																								
	(a) F = Final results																								

Groundwater Tracking Data Tables

Appendix B
Soil and Test Pit Logs

Groundwater Tracking Data

Matrix	Station ID	Sample ID	Collection Date	Add. Anal. Date	Beg depth	End depth	Lab #	Lab Results In (a)	Aluminum	Arsenic	Cyanide-Amen.	Cyanide-Total	Fluoride	Metals-23(CLP)	Metals-Dis.	PAH	TPAH-S	PCB	PCB-S	Pesticide-Chlor.	SVOC	TPH	TPH-S	VOC
Bake House Sump and Drill Rig Samples																								
GW	BS-11	RM-BS11	08/25/94		0	0	94-2433	F			X	X	X	X		X					X		X	
GW	BS-16	RM-BS16	08/25/94		0	0	94-2433	F	X	X		X	X			X					X		X	
GW	BS-18	RM-BS18	08/25/94		0	0	94-2433	F	X	X	X	X	X			X					X		X	
GW	BS-21	RM-BS21	08/25/94		0	0	94-2433	F	X	X		X	X			X					X		X	
GW	BW-13	RM-BWP3-82594	08/25/94		0	0	94-2433	F	X	X		X	X			X					X		X	
GW	DRILLRIG	RM-DRILLRIG	07/09/94		0	0	94-1899	F				X	X	X				X					X	
GW	DRILLRIG	RM-DRILLRIG	07/09/94		0	0	94-1899	F									X		X				X	
Offsite Wells																								
GW	FF-01	RM-FF1-9694	09/06/94		0	0	94-2541	F				X	X					X			X			
GW	GS-01	RM-GS1-9694	09/06/94		0	0	94-2541	F				X	X					X			X			
GW	SM-01	RM-SM1-9694	09/06/94		0	0	94-2541	F				X	X					X			X			
Monitoring Well Groundwater Samples																								
GW	MW-01	RM-MW-01-EB	07/12/94		0	0	94-1926	F				X	X	X			X		X				X	
GW	MW-01	RM-MW01-7-94	07/18/94		0	0	94-2000	F			X	X	X	X		X		X				X		
GW	MW-01	RM-MW01-81594	08/15/94		0	0	94-2305	F			X	X	X											
GW	MW-02	RM-MW02-7-94	07/18/94		0	0	94-2000	F				X	X	X		X		X					X	
GW	MW-02	RM-MW02-81594	08/15/94		0	0	94-2305	F				X	X			X								
GW	MW-02D	RM-MW22-7-94	07/18/94		0	0	94-2000	F				X	X	X		X		X					X	
GW	MW-02EB	RM-MW32-81594	08/15/94		0	0	94-2305	F				X	X	X		X		X		X			X	
GW	MW-02EB	RM-MW32-81594	08/15/94		0	0	94-2323	F																X
GW	MW-03	RM-MW03-7-94	07/18/94		0	0	94-2000	F			X	X	X	X		X		X				X	X	
GW	MW-03EB	RM-MW-33-7-94	07/18/94		0	0	94-2000	F				X	X	X		X		X				X	X	
GW	MW-04	RM-MW-04-81594	08/15/94		0	0	94-2305	F			X	X	X	X	X									
GW	MW-04	RM-MW-04-7/18	07/18/94				94-2000	F			X	X	X	X	X	X		X				X		
GW	MW-05	RM-MW05-7-94	07/18/94		0	0	94-2000	F				X	X	X		X		X					X	
GW	MW-05	BPA-MW5-81694	08/16/94		0	0	94-2323	F				X	X	X		X		X		X	X			X
GW	MW-06	RM-MW-06-7/18	07/18/94				94-2000	F				X	X	X		X	X	X					X	
GW	MW-07	RM-MW-07-EB	07/09/94		0	0	94-1899	F				X	X	X			X		X				X	
GW	MW-07	RM-MW-07-7/18	07/18/94				94-2000	F				X	X	X		X	X	X					X	
GW	MW-08	RM-MW08-81594	08/15/94		0	0	94-2305	F				X	X											
GW	MW-08	RM-MW-08-7/18	07/18/94				94-2000	F				X	X	X		X	X	X					X	
GW	MW-09	RM-MW09-81594	08/15/94		0	0	94-2305	F			X	X	X	X		X		X		X	X		X	

Groundwater Tracking Data

Matrix	Station ID	Sample ID	Collection Date	Add. Anal. Date	Beg depth	End depth	Lab #	Lab Results in (a)	Aluminum	Arsenic	Cyanide-Amen.	Cyanide-Total	Fluoride	Metals-23(CLP)	Metals-Dis.	PAH	TPAH-S	PCB	PCB-S	Pesticide-Chlor.	SVOC	TPH	TPH-S	VOC
GW	MW-09	RM-MW09-81594	08/15/94		0	0	94-2323	F																X
GW	MW-09D	RM-MW29-81594	08/15/94		0	0	94-2305	F			X	X	X	X		X		X		X	X		X	
GW	MW-09D	RM-MW29-81594	08/15/94		0	0	94-2323	F																X
GW	MW-10	RM-MW-10-81594	08/15/94		0	0	94-2305	F				X	X	X	X	X		X		X	X		X	
GW	MW-10	RM-MW-10-81594	08/15/94		0	0	94-2323	F																X
GW	MW-10EB	RM-MW10-2.5EB	08/05/94		2.5	2.5	94-2202	F				X	X	X			X		X				X	
GW	MW-11	RM-MW11-81594	08/15/94		0	0	94-2305	F			X	X	X	X	X	X		X		X	X		X	
GW	MW-11	RM-MW11-81594	08/15/94		0	0	94-2323	F																X
GW	MW-11EB	RM-MW11-2.5EB	08/04/94		2.5	2.5	94-2202	F				X	X	X			X		X				X	
GW	MW-12	RM-MW12-81594	08/15/94		0	0	94-2305	F				X	X	X		X		X		X	X		X	
GW	MW-12	RM-MW12-81594	08/15/94		0	0	94-2323	F																X
		Production Wells																						
GW	PW-03	RM-PW03-81694	08/16/94		0	0	94-2323	F				X	X	X		X		X		X	X		X	X
GW	PW-07	RM-PW07-81694	08/16/94		0	0	94-2323	F				X	X	X		X		X		X	X		X	X
GW	PW-08	RM-PW08-81594	08/16/94		0	0	94-2323	F				X	X	X		X		X		X	X		X	X
GW	PW-10	RM-PW10-81694	08/16/94		0	0	94-2323	F				X	X	X		X		X		X	X	X	X	X
GW	PW-18	RM-PW18-81694	08/16/94		0	0	94-2323	F			X	X	X	X		X		X		X	X		X	X
GW	PW-18	RM-PW18TB	08/16/94		0	0	94-2323	F																X
GW	PW-18D	RM-PW28-81694	08/16/94		0	0	94-2323	F			X	X	X	X		X		X		X	X		X	X
		Soil Boring Samples																						
SB	MW-01	RM-MW-01-S	07/12/94		0	0	94-1926	F				X	X	X		X	X	X	X			X	X	
SB	MW-01	RM-MW-01-2.5	07/12/94		2.5	2.5	94-1926	F				X	X	X			X		X				X	
SB	MW-01	RM-MW-01-7.5	07/12/94		7.5	7.5	94-1926	F				X	X			X	X	X	X			X	X	
SB	MW-01	RM-MW01-10	07/12/94		10	10	94-1926	F									X							
SB	MW-01	RM-MW01-12.5	07/12/94		12.5	12.5	94-1926	F									X							
SB	MW-01D	RM-MW-01-SD	07/12/94		0	0	94-1926	F				X	X	X			X		X				X	
SB	MW-02	RM-MW-02-S	07/11/94		0	0	94-1913	F				X	X	X			X		X				X	
SB	MW-02	RM-MW-02-2.5	07/11/94		2.5	2.5	94-1913	F				X	X	X			X		X				X	
SB	MW-02	RM-MW-02-7.5	07/11/94		7.5	7.5	94-1913	F				X	X				X		X				X	
SB	MW-02	RM-MW-02-12.5	07/11/94		12.5	12.5	94-1913	F				X	X				X		X				X	
SB	MW-03	RM-MW-03-S	07/09/94		0	0	94-1899	F				X	X				X		X				X	
SB	MW-03	RM-MW-03-2.5'	07/09/94		2.5	2.5	94-1899	F				X	X				X		X				X	
SB	MW-04	RM-MW-04-S	07/12/94		0	0	94-1926	F				X	X	X		X	X	X	X			X	X	

Groundwater Tracking Data

Matrix	Station ID	Sample ID	Collection Date	Add. Anal. Date	Beg depth	End depth	Lab #	Lab Results In (a)	Aluminum	Arsenic	Cyanide-Amen.	Cyanide-Total	Fluoride	Metals-23(CLP)	Metals-Dis.	PAH	TPAH-S	PCB	PCB-S	Pesticide-Chlor.	SVOC	TPH	TPH-S	VOC
SB	MW-04	RM-MW-04-2.5	07/12/94		2.5	2.5	94-1926	F				X	X	X			X		X				X	
SB	MW-04	RM-MW-04-7.5	07/12/94		7.5	7.5	94-1926	F				X	X				X		X				X	
SB	MW-04	RM-MW-04-10.0	07/12/94		10	10	94-1926	F				X	X				X		X				X	
SB	MW-05	RM-MW-05-2.5	07/08/94		2.5	2.5	94-1895	F				X	X				X		X				X	
SB	MW-06	RM-MW-06-S	07/08/94		0	0	94-1895	F				X	X	X			X		X				X	
SB	MW-06	RM-MW-06-2.5	07/08/94		2.5	2.5	94-1895	F				X	X	X			X		X				X	
SB	MW-06	RM-MW-06-7.5	07/08/94		7.5	7.5	94-1895	F				X	X				X		X				X	
SB	MW-07	RM-MW-07-S	07/09/94		0	0	94-1899	F				X	X				X		X				X	
SB	MW-07	RM-MW-07-2.5'	07/09/94		2.5	2.5	94-1899	F				X	X	X			X		X				X	
SB	MW-07	RM-MW-07-7.5'	07/09/94		7.5	7.5	94-1899	F				X	X				X		X				X	
SB	MW-07	RM-MW-07-10.0'	07/09/94		10	10	94-1899	F				X	X				X		X				X	
SB	MW-07D	RM-MW-07-2.5D	07/09/94		2.5	2.5	94-1899	F				X	X	X			X		X				X	
SB	MW-08	RM-MW-08-S	07/07/94		0	0	94-1882	F				X	X				X		X				X	
SB	MW-08	RM-MW-08-2.5	07/07/94		2.5	2.5	94-1882	F				X	X				X		X				X	
SB	MW-09	RM-MW09-S	08/04/94		0	0	94-2179	F				X	X	X		X	X	X	X				X	
SB	MW-09	RM-MW09-2.5	08/04/94	8/31/94	2.5	2.5	94-2179	F								X	X							
SB	MW-09	RM-MW09-17.5	08/04/94		17.5	17.5	94-2179	F				X	X	X			X		X				X	
SB	MW-10	RM-MW10-S	08/05/94		0	0	94-2202	F				X	X	X		X	X		X				X	
SB	MW-10	RM-MW10-2.5	08/05/94	8/31/94	2.5	2.5	94-2202	F								X								
SB	MW-10	RM-MW10-7.5	08/05/94		7.5	7.5	94-2202	F				X	X				X		X				X	
SB	MW-10	RM-MW10-10	08/05/94		10	10	94-2202	F				X	X				X		X				X	
SB	MW-11a	RM-MW11-S	08/04/94		0	0	94-2202	F				X	X	X		X	X	X	X			X	X	
SB	MW-11b	RM-MW11-2.5	08/04/94	8/31/94	2.5	2.5	94-2202	F								X								
SB	MW-11c	RM-MW11-5.0	08/04/94		5	5	94-2202	F				X	X	X			X		X				X	
SB	MW-11d	RM-MW11-7.5	08/04/94		7.5	7.5	94-2202	F				X	X	X			X		X				X	
SB	MW-12a	RM-MW12-S	08/04/94		0	0	94-2179	F				X	X	X		X	X	X	X				X	
SB	MW-12b	RM-MW12-7.5	08/04/94		7.5	7.5	94-2179	F				X	X	X			X		X				X	
Notes:																								
(a) F = Final results																								
P = Preliminary results																								
INC = Incomplete set of preliminary results, outstanding data.																								

North Landfill East Area



PROJECT NUMBER <u>07E 39285.40</u>	TEST PIT NUMBER	SHEET <u>1</u> OF <u>10</u>
---------------------------------------	-----------------	-----------------------------

TEST PIT WALL LOG


DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>BMC WILKINSON WASTE PILE</u>	LOCATION <u>EAST HENDON WEST</u>	MAP OF	WALL OF PIT	
	INTERVAL	TYPE AND NUMBER					
1			ELEVATION _____	CONTRACTOR <u>IMC</u>	DATE EXCAVATED <u>10/20/94</u>		
2			WATER LEVEL AND DATE _____	EXCAVATION METHOD <u>CAT 416B</u>	LOGGER <u>END</u>		
3			APPROXIMATE DIMENSIONS: LENGTH _____ WIDTH _____ DEPTH _____	REMARKS _____			
4			<div><u>BLACK BRICK/ REFRACTORY</u></div> <div><u>(E-H-W11)</u></div>				COMMENTS
5							
6							
7							
8							
9							
10							
LENGTH (FT)			20				



TEST PIT WALL LOG

PROJECT NUMBER <u>OPB 39285.40</u>	TEST PIT NUMBER	SHEET <u>2</u> OF <u>10</u>
---------------------------------------	-----------------	-----------------------------

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>BRD CELLULAR WASTE PILE</u>	LOCATION <u>EAST HEADWALL WEST</u>	MAP OF	WALL OF PIT	DATE EXCAVATED <u>6/24/54</u>	LOGGER <u>BRD</u>	REMARKS	COMMENTS
	INTERVAL	TYPE AND NUMBER								
1										
2										
3										
4										
5										
6										
7										
8										
9										
10										
LENGTH (FT) <u>20</u> <u>20</u>										



DEPTH BELOW SURFACE (FT)	SAMPLE	PROJECT <u>ENC. W/REINFORCED WASTE PILE</u>		LOCATION <u>EAST HEADWATER WEST</u>		MAP OF <u>WALL OF PIT</u>	
		INTERVAL	TYPE AND NUMBER	ELEVATION	CONTRACTOR <u>TRAC</u>	DATE EXCAVATED <u>6/20/94</u>	WALL OF PIT
1 -				WATER LEVEL AND DATE	EXCAVATION METHOD <u>CAT 416B</u>	LOGGER <u>RUO</u>	
2 -				APPROXIMATE DIMENSIONS: LENGTH	WIDTH	DEPTH	REMARKS
3 -							
4 -							
5 -							
6 -							
7 -							
8 -							
9 -							
10 -							
11 -							
12 -							



PROJECT NUMBER 07E 39285.A0 TEST PIT NUMBER _____ SHEET 4 OF 10

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>BMC CULTURAL WASTE PILE</u>	LOCATION <u>EAST HEADQUARTERS WEST</u>	MAP OF _____ WALL OF PIT	DATE EXCAVATED <u>6/20/84</u>	LOGGER <u>Paul</u>	COMMENTS
	INTERVAL	TYPE AND NUMBER						
1			ELEVATION _____	CONTRACTOR <u>IMC</u>	EXCAVATION METHOD <u>CAT W/BL</u>			
2			WATER LEVEL AND DATE _____					
3			APPROXIMATE DIMENSIONS: LENGTH _____ WIDTH _____ DEPTH _____					
4								
5								
6								
7								
8								
9								
10								
11								
12								
			(E-H-WZ)					
			BLUE CARBON RESIDUALITY					
			SOME DEBRIS					
			AVIDE BALS					
			FOUND IN EXCAVATION					
			LENGTH (FT) <u>70</u> <u>85</u>					



PROJECT NUMBER
07E 39285 AB

TEST PIT NUMBER

SHEET 5 OF 10

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>Bull National Waste Pile</u>	LOCATION <u>EAST HEADQUARTERS WEST</u>	MAP OF	WALL OF PIT
	INTERVAL	TYPE AND NUMBER				
1			ELEVATION	CONTRACTOR <u>EMU</u>	DATE EXCAVATED <u>6/20/54</u>	
2			WATER LEVEL AND DATE	EXCAVATION METHOD <u>CAT 916B</u>	LOGGER <u>EMU</u>	
3			APPROXIMATE DIMENSIONS:	LENGTH	WIDTH	DEPTH
4						REMARKS
5						
6						
7						
8						
9						
10						
11						
12						
No Excavation. Assume 9' Deep. Blast Chamber Destroyed and Debris.						
80 LENGTH (FT) 90 100						

PROJECT NUMBER
02E 39285.A0

TEST PIT NUMBER

SHEET **6** OF **10**

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT ENC. W/REINFORCED CONCRETE	LOCATION EAST HEADQUARTERS	MAP OF	WALL OF PIT
	INTERVAL	TYPE AND NUMBER				
1			ELEVATION	CONTRACTOR TRW	EXCAVATION METHOD CHT 416 B	DATE EXCAVATED 6/20/84
2			WATER LEVEL AND DATE	LENGTH	WIDTH	DEPTH
3			APPROXIMATE DIMENSIONS:			REMARKS
4						
5						
6						
7						
8						
9						
10						
11						
12						
100 LENGTH (FT) 120						

BLACK CARBON FERRITORY
CARBON AMOUNT OF 80000 / 100000

(E-H-W3)



PROJECT NUMBER

TEST PIT NUMBER

02E38285.40

SHEET 7 OF 10

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>RAIL WILLOWD WASTE PILE</u>	LOCATION <u>EAST HEADQUARTERS WEST</u>	MAP OF <u>WALL OF PIT</u>				
	INTERVAL	TYPE AND NUMBER				DATE EXCAVATED <u>6/10/14</u>			
1			ELEVATION _____	CONTRACTOR <u>TRW</u>	EXCAVATION METHOD <u>CH 416.3</u>	WATER LEVEL AND DATE _____	APPROXIMATE DIMENSIONS: LENGTH _____ WIDTH _____ DEPTH _____	REMARKS _____	COMMENTS <u>NO EXCAVATION!</u> <u>ASSUME SAME AS (E-H. W.3)</u>
2									
3									
4									
5									
6									
7									
8									
9									
10									
11									
12									
			LENGTH (FT) <u>130</u> <u>140</u>						



PROJECT NUMBER

OPE 39225, AD

TEST PIT NUMBER

SHEET 8 OF 10

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT	LOCATION	MAP OF	WALL OF PIT
	INTERVAL	TYPE AND NUMBER	ELEVATION	CONTRACTOR	DATE EXCAVATED	
			WML UNKNOWN WASTE PILE <td>IMW<td>6/20/84<td></td></td></td>	IMW <td>6/20/84<td></td></td>	6/20/84 <td></td>	
			WATER LEVEL AND DATE	EXCAVATION METHOD	LOGGER	
			APPROXIMATE DIMENSIONS: LENGTH	WIDTH	DEPTH	REMARKS
1						
2						
3						
4						
5						
6						
7						
8						
9						
10						
11						
12						

NO EXCAVATION!
ASSUME SAME AS
(E-H-W3)

BLACK CARBON REFRACTORY
w/ DEBRIS
BLACK OILY SILTS @ BOTTOM
OF EXCAVATION

(E-H-W4)

WASTE PILE DEPTH
EXCEEDS THE REACH
OF THE CAT 416B

DIESEL SMELL NOTED @
BOTTOM OF EXCAVATION

140 150 160
LENGTH (FT)



PROJECT NUMBER

OPE 39285.A0

TEST PIT NUMBER

SHEET 9 OF 10

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>RMC UNKNOWN WASTE PILE</u>	LOCATION <u>EAST HEADING WEST</u>	MAP OF _____	WALL OF PIT _____	
	INTERVAL	TYPE AND NUMBER					
			ELEVATION _____	CONTRACTOR <u>FMW</u>	DATE EXCAVATED <u>6/20/94</u>		
			WATER LEVEL AND DATE _____	EXCAVATION METHOD <u>CAT 4/6 B</u>	LOGGER <u>RW</u>		
			APPROXIMATE DIMENSIONS: LENGTH _____ WIDTH _____ DEPTH _____	REMARKS _____			
1			<p>NO EXCAVATION! ASSUME SAME AS (E-H-WY)</p>				COMMENTS
2							
3							
4							
5							
6							
7							
8							
9							
10							
11							
12							
			LENGTH (FT) <u>160</u> <u>170</u> <u>180</u>				



PROJECT NUMBER 07E 352285.A0 TEST PIT NUMBER 10 OF 10

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>EMC WILKINSON WASTE PILE</u>	LOCATION <u>EAST-HEADWATER WEST</u>	MAP OF <u>WALL OF PIT</u>
	INTERVAL	TYPE AND NUMBER			
1			ELEVATION _____	CONTRACTOR <u>PMU</u>	DATE EXCAVATED <u>6/6/54</u>
2			WATER LEVEL AND DATE _____	EXCAVATION METHOD <u>CAT 416B</u>	LOGGER <u>ELC</u>
3			APPROXIMATE DIMENSIONS: LENGTH _____ WIDTH _____ DEPTH _____	REMARKS _____	
4					
5					
6					
7					
8					
9					
10					
11					
12					
COMMENTS					

BLACK CARBON REMEDIATION
w/ BRICKS

WASTE PILE DEPTH
EXCEEDS THE DEPTH
OF THE CAT 416B
(E-H-W5)

NO EXCAVATION
ASSUME SAME AS
(E-H-W5)

180 LENGTH (FT) 200 @ ROAD



PROJECT NUMBER
ORE 39285. AD

TEST PIT NUMBER

SHEET *1* OF *7*

TEST PIT WALL LOG


DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <i>ARC VALLEJOUL WASTE PILE</i>	LOCATION <i>SOUTH HEADQUARTERS NORTH</i>	MAP OF	WALL OF PIT		
	INTERVAL	TYPE AND NUMBER						
1			ELEVATION _____	CONTRACTOR <i>IMU</i>	EXCAVATION METHOD <i>CAT 410 B</i>	DATE EXCAVATED <i>6/20/94</i>	LOGGER <i>AWO</i>	COMMENTS
2			WATER LEVEL AND DATE _____	LENGTH _____	WIDTH _____	DEPTH _____	REMARKS _____	
3			APPROXIMATE DIMENSIONS:					
4			<i>SOIL COVER</i>					
5			<i>Brown silt</i>					
6			<i>Black carbon Refractory</i>					
7			<i>w/brick</i>					
8			<i>(S-H-N11)</i>					
9								
10								
			<i>18</i>					
			<i>LENGTH (FT)</i>					
			<i>20</i>					



PROJECT NUMBER <u>ORE 39285 Ad</u>	TEST PIT NUMBER	SHEET <u>2</u> OF <u>7</u>
---------------------------------------	-----------------	----------------------------

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>RAIL WILLOW WASTE PILE</u>	LOCATION <u>SOUTH HEADQUARTERS</u>	MAP OF	WALL OF PIT	
	INTERVAL	TYPE AND NUMBER					
1			ELEVATION _____	CONTRACTOR <u>IMV</u>	DATE EXCAVATED <u>6/22/94</u>		
2			WATER LEVEL AND DATE _____	EXCAVATION METHOD <u>CAT 416B</u>	LOGGER <u>RAIL</u>		
3			APPROXIMATE DIMENSIONS: LENGTH _____ WIDTH _____ DEPTH _____	REMARKS _____			
4			NO EXCAVATION				COMMENTS
5			ASSUME 2' SOIL COVER				
6			ASSUME BLACK CARBON BENTON				
7			W/ BECKS				
8							
9							
10							
20			LENGTH (FT) <u>40</u>				



REV 7/86 FORM D1599



PROJECT NUMBER <i>OPE 39285.A0</i>	TEST PIT NUMBER SHEET <i>4</i> OF <i>7</i>
TEST PIT WALL LOG	

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <i>RMC UNKNOWN WASTE PILE</i>	LOCATION <i>SOUTH HEADING NORTH</i>	MAP OF _____	WALL OF PIT	
	INTERVAL	TYPE AND NUMBER	ELEVATION _____	CONTRACTOR <i>IMW</i>	DATE EXCAVATED <i>6/20/94</i>		
			WATER LEVEL AND DATE _____	EXCAVATION METHOD <i>CAT 4/6 B</i>	LOGGER <i>BUN</i>		
			APPROXIMATE DIMENSIONS: LENGTH _____ WIDTH _____ DEPTH _____	REMARKS _____			
1			<div>NO EXCAVATION ASSUME 8' DEEP BLACK CARBON REFRACTORY w/ BRICKS etc...</div>				COMMENTS
2							
3							
4							
5							
6							
7							
8							
9							
10							
			LENGTH (FT) <i>60</i> <i>70</i> <i>80</i>				



PROJECT NUMBER <u>OPE 39285.A0</u>	TEST PIT NUMBER <u>SHEET 5 OF 7</u>
TEST PIT WALL LOG	

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>RMC UNKNOWN WASTE PILE</u>	LOCATION <u>SOUTH HEADING NORTH</u>	MAP OF _____	WALL OF PIT _____
	INTERVAL	TYPE AND NUMBER				
			ELEVATION _____	CONTRACTOR <u>IMW</u>	DATE EXCAVATED <u>6/20/94</u>	
			WATER LEVEL AND DATE _____	EXCAVATION METHOD <u>CAT 4/6 B</u>	LOGGER <u>RND</u>	
			APPROXIMATE DIMENSIONS: LENGTH _____ WIDTH _____ DEPTH _____ REMARKS _____			
1			<p>BLACK CARBON REFRACTORY w/ BRICKS</p> <p>WASTE PILE DEPTH EXCEEDED THE REACH OF THE CAT 4/6 B (S-H-N3)</p> <p>NOT EXCAVATED ASSUME SAME AS (S-H-N3)</p>			
2						
3						
4						
5						
6						
7						
8						
9						
10						
11						
12						
			DECEL SMELL NOTED @ BOTTOM OF EXCAVATION			
			LENGTH (FT) <u>90</u> <u>100</u>			



PROJECT NUMBER
0PE39285.A0

TEST PIT NUMBER

SHEET 6 OF 7

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>ENC WELLHEAD WASTE PILE</u>	LOCATION <u>SOUTH HEADWALL 162TH</u>	MAP OF	WALL OF PIT
	INTERVAL	TYPE AND NUMBER				
1			ELEVATION _____	CONTRACTOR <u>EMU</u>	EXCAVATION METHOD <u>CAT 416B</u>	DATE EXCAVATED <u>6/20/94</u>
2			WATER LEVEL AND DATE _____	LENGTH _____	WIDTH _____	DEPTH _____
3			APPROXIMATE DIMENSIONS: _____	REMARKS _____		
4			<p>NOT EXCAVATED ASSUME SAME AS (S-H-N/3)</p>			
5						
6						
7						
8						
9						
10						
11						
12						
			LENGTH (FT) <u>180</u> <u>120</u>			




PROJECT NUMBER

OPE 39285.AD

TEST PIT NUMBER

SHEET 7 OF 7

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>RMC UNKNOWN WASTE PILE</u>	LOCATION <u>SOUTH HEADWALL NORTH</u>	MAP OF _____	WALL OF PIT _____
	INTERVAL	TYPE AND NUMBER				
			ELEVATION _____	CONTRACTOR <u>IMW</u>	DATE EXCAVATED <u>6/20/94</u>	
			WATER LEVEL AND DATE _____	EXCAVATION METHOD <u>CAT 416B</u>	LOGGER <u>PLD</u>	
			APPROXIMATE DIMENSIONS: LENGTH _____ WIDTH _____ DEPTH _____ REMARKS _____			
1			 <p>GRAY ASH</p>			
2						
3						
4						
5						
6						
7						
8						
9						
10						
11						
12						
			COMMENTS			

North Landfill West Area

C. M. HILL

PROJECT NUMBER

TEST PIT NUMBER


EHW3

SHEET

OF 1


TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT	LOCATION	MAP OF	WALL OF PIT
	INTERVAL	TYPE AND NUMBER				
			ELEVATION <u>unknown</u>	CONTRACTOR <u>STRANIS</u>	DATE EXCAVATED <u>7/19/94</u>	
			WATER LEVEL AND DATE <u>9' - 7/19/94</u>	EXCAVATION METHOD <u>CAT 416B Backhoe</u>	LOGGER <u>R. Johns</u>	
			APPROXIMATE DIMENSIONS: LENGTH <u>17'</u> WIDTH <u>5'</u> DEPTH <u>14.5'</u>			REMARKS <u>85°F, Sunny</u>
						EAST
1						COMMENTS
2						<p>Fill FOR ENTIRE 14.5' OF TEST PIT, Fill IS BRICK, PLASTIC, DRUMS, TRASH, WIRE CABLE, WOOD, SOIL IS SAND, BLACK,</p>
3						
4						
5						
6						
7						
8						
9						
10						
11						
12						
13						
14						
15						
			LENGTH (FT)			





PROJECT NUMBER	TEST PIT NUMBER	SHEET 1 OF 1
	EHW4	
TEST PIT WALL LOG		

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>RML</u>	LOCATION <u>NORTH LANDFILL AREA</u>	MAP OF	WALL OF PIT
	INTERVAL	TYPE AND NUMBER	ELEVATION	CONTRACTOR <u>STRATUS</u>	DATE EXCAVATED <u>7/19/94</u>	
			WATER LEVEL AND DATE	EXCAVATION METHOD <u>CAT 426</u>	LOGGER <u>puo</u>	
	APPROXIMATE DIMENSIONS:		LENGTH <u>10</u>	WIDTH <u>6'</u>	DEPTH <u>7</u>	REMARKS <u>Subj. SC</u>
1			 <p>Brick/chimney Flies</p>			
2						
3						
4						
5						
6						
7						
8						
9						
10						
11						
12						
13						
14						
15						
			LENGTH (FT)			

CRM HILL

PROJECT NUMBER

07E 39223 B0003

TEST PIT NUMBER

SHW1

SHEET 1 OF 1

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT	LOCATION	MAP OF	WALL OF PIT
	INTERVAL	TYPE AND NUMBER				
			ELEVATION	CONTRACTOR	DATE EXCAVATED	
			WATER LEVEL AND DATE	EXCAVATION METHOD	LOGGER	
			APPROXIMATE DIMENSIONS: LENGTH WIDTH DEPTH REMARKS			
1			<div style="display: flex; justify-content: space-between;"> Native Soils Brick </div>			
2						
3						
4						
5						
6						
7						
8						
9						
10						
			LENGTH (FT)			


COMMENTS

samples collected @



PROJECT NUMBER	TEST PIT NUMBER
01E 39293. Bd. 03	SHN 12
SHEET 1 OF 1	

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>RMC North Cambridge Area</u>	LOCATION <u>STATION 5</u>	MAP OF <u>W</u> WALL OF PIT
	INTERVAL	TYPE AND NUMBER			
1			ELEVATION _____	CONTRACTOR <u>STRAVIS</u>	DATE EXCAVATED _____
2			WATER LEVEL AND DATE _____	EXCAVATION METHOD <u>CAT 416B</u>	LOGGER <u>RWD</u>
3			APPROXIMATE DIMENSIONS: LENGTH <u>15</u> WIDTH <u>3</u> DEPTH <u>2</u>	REMARKS _____	
4					
5					
6					
7					
8					
LENGTH (FT)			COMMENTS <u>Samples collected @</u>		



PROJECT NUMBER
09E 39293.80.d3

TEST PIT NUMBER
SHN3

SHEET 1 OF 1

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT	LOCATION	CONTRACTOR	EXCAVATION METHOD	DATE EXCAVATED	LOGGER	MAP OF WALL OF PIT	COMMENTS
	INTERVAL	TYPE AND NUMBER								
1			PAC	Northland Ice Area	STRAVUS	CAH 41613	2/20/94	EW		Sampled e <input type="checkbox"/>
2										
3										
4										
5										
6										
<p>Backfill / Black Carbon Pellets 1' in y</p> <p>Brown Asphalts 5' ft</p> <p>Length 14 Width 3 Depth 4</p> <p>Remarks</p>										
<p>MAP OF WALL OF PIT</p> <p>Right</p> <p>SHN3</p> <p>N ←</p>										



PROJECT NUMBER	TEST PIT NUMBER SHN 4	SHEET 1 OF 1
----------------	---------------------------------	----------------------------

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT	LOCATION	MAP OF	WALL OF PIT
	INTERVAL	TYPE AND NUMBER				
			ELEVATION <u>unk</u>	CONTRACTOR <u>STRATUS</u>	DATE EXCAVATED <u>7/19/94</u>	
			WATER LEVEL AND DATE <u>none observed</u>	EXCAVATION METHOD <u>CAT 416B Backhoe</u>	LOGGER <u>R. Johns</u>	
			APPROXIMATE DIMENSIONS: LENGTH <u>15'</u> WIDTH <u>4'</u> DEPTH <u>5-6'</u>		REMARKS <u>85° F, Sunny</u>	
					<u>North</u>	
1						
2						
3						
4						
5						
6						
7						
			COMMENTS			
			FILL TO 4.0' - BRICKS, SLABS, CONCRETE, w/ SILT FILL MATERIAL			
			4.0' - 6' - NATIVE SOIL - SILT, MED. BRN, DRY, SOFT TO STIFF, (ML)			
			photo # 21 is looking east at wall - notice fill to 3.5' / native below that is silt, med brn, dry, too soft to stiff, (ML)			
			LENGTH (FT)			

CRMHILL

PROJECT NUMBER

01E-39293-191.03

TEST PIT NUMBER

FHW1

SHEET 1 OF 1

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT	LOCATION	MAP OF	WALL OF PIT
	INTERVAL	TYPE AND NUMBER	ELEVATION	CONTRACTOR	DATE EXCAVATED	LOGGER
			PMC Northwest Landfill area		7/20/74	RWD
			WATER LEVEL AND DATE	EXCAVATION METHOD	Cat 416B	
			APPROXIMATE DIMENSIONS: LENGTH 12 WIDTH 5 DEPTH 5			
			REMARKS			
1						
2						
3						
4						
5						
6						
7						
8						
9						
10						
			<p>COMMENTS</p> <p>Samples collected @ </p>			
			LENGTH (FT)			




PROJECT NUMBER	TEST PIT NUMBER <u>ETHW2</u>	SHEET <u>1</u> OF <u>1</u>
TEST PIT WALL LOG		

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>PWC Northwest Landfill</u>	LOCATION _____	MAP OF <u>S</u> WALL OF PIT
	INTERVAL	TYPE AND NUMBER	ELEVATION _____	CONTRACTOR <u>STRATUS</u>	DATE EXCAVATED <u>7/20/84</u>
			WATER LEVEL AND DATE <u>55' 7/20/84</u>	EXCAVATION METHOD <u>Cat 46B</u>	LOGGER <u>RW</u>
			APPROXIMATE DIMENSIONS: LENGTH <u>11</u> WIDTH <u>4</u> DEPTH <u>5.5</u> REMARKS <u>water @ 55'</u>		
1					
2					
3					
4					
5					
6					
7					
8					
9					
10					
			COMMENTS <u>samples collected @ 1</u> <u>oil reading 1.5 ppm</u> <u>Diesel smell coming from the pit</u>		
			LENGTH (FT)		

South Landfill Area

PDX157EB.WPS




DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT	LOCATION	MAP OF	WALL OF PIT
	INTERVAL	TYPE AND NUMBER	ELEVATION	CONTRACTOR	DATE EXCAVATED	
			REYNOLDS METALS	SOUTHERN POTLINER	S	
				STRATUS Corp	9/13/94	
			WATER LEVEL AND DATE	EXCAVATION METHOD	CAT 416 b	LOGGER
			APPROXIMATE DIMENSIONS: LENGTH 15 WIDTH 3 DEPTH 6	REMARKS		
1						
2			<p>NO DEBRIS, clean.</p>			
3			<p>pit has color</p>			
4			<p>Sample @ 1, 2, 4, 6 + composite.</p>			
5			<p>Time 1300</p>			
6						
7						
8						
			LENGTH (FT)			



PROJECT NUMBER <u>0437213.P00.03</u>	TEST PIT NUMBER <u>D4</u>	SHEET <u>1</u> OF <u>1</u>
---	------------------------------	----------------------------

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>REINFORCED METALS South pole</u>	LOCATION _____	MAP OF <u>4</u> WALL OF PIT
	INTERVAL	TYPE AND NUMBER			
			ELEVATION _____	CONTRACTOR <u>STRATUS Corp</u>	DATE EXCAVATED <u>9/13/94</u>
			WATER LEVEL AND DATE _____	EXCAVATION METHOD <u>Cat 416ch</u>	LOGGER <u>FW</u>
			APPROXIMATE DIMENSIONS: LENGTH <u>11'</u> WIDTH <u>3'</u> DEPTH <u>8'</u> REMARKS _____		
1					
2					
3					
4					
5					
6					
7					
8					
			COMMENTS <u>sampled @ 3, 2, 4, 6, 8'</u>		
			LENGTH (FT)		

CH2M HILL

PROJECT NUMBER

DPE 39293.B5.01

TEST PIT NUMBER

C1.5

SHEET 1 OF 1

TEST PIT WALL LOG


DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT	LOCATION	MAP OF	WALL OF PIT
	INTERVAL	TYPE AND NUMBER				
			ELEVATION	CONTRACTOR	DATE EXCAVATED	
			WATER LEVEL AND DATE	EXCAVATION METHOD	LOGGER	
			APPROXIMATE DIMENSIONS: LENGTH WIDTH DEPTH REMARKS			
1			<p>gray cryolite? w/ debris</p> <p>RUST colored metal debris</p> <p>metal CUTTING</p> <p>sampled @ 1, 2, 4, 6 + composite</p> <p>Sample Time 1330</p>			
2						
3						
4						
5						
6						
7						
8						
			LENGTH (FT)			


Note: The south landfill was previously termed the "south potliner area." This terminology was revised for this Removal Site Assessment (RSA) report because information available to date (including the results of the RSA) indicate that this fill does not include potliner.



PROJECT NUMBER <i>NE 3923.3 PM 13</i>	TEST PIT NUMBER <i>EL</i>	SHEET <i>1</i> OF <i>1</i>
--	------------------------------	----------------------------

TEST PIT WALL LOG


DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <i>WIL Sixth Potliner</i>	LOCATION	MAP OF <i>W</i> WALL OF PIT
	INTERVAL	TYPE AND NUMBER			
			ELEVATION	CONTRACTOR <i>STRATUS Corp</i>	DATE EXCAVATED <i>9/13/84</i>
			WATER LEVEL AND DATE	EXCAVATION METHOD <i>CH 466</i>	LOGGER <i>lu</i>
			APPROXIMATE DIMENSIONS: LENGTH <i>11'</i> WIDTH <i>3'</i> DEPTH <i>4'</i> REMARKS		
1					
2					
3					
4					
			COMMENTS <i>Sampled @ S, 4</i>		
			LENGTH (FT)		



REV 7/86 FORM D1599



PROJECT NUMBER <u>07E-39273-BD-023</u>	TEST PIT NUMBER <u>SPI</u>	SHEET <u>1</u> OF <u>1</u>
TEST PIT WALL LOG		

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>PMC Southern Potliner Area</u>	LOCATION _____	MAP OF <u>W</u> WALL OF PIT
	INTERVAL	TYPE AND NUMBER			
			ELEVATION _____	CONTRACTOR <u>STRATUS</u>	DATE EXCAVATED <u>7/20/94</u>
			WATER LEVEL AND DATE <u>07' 7/20/94</u>	EXCAVATION METHOD <u>Cat 416B</u>	LOGGER <u>flw</u>
			APPROXIMATE DIMENSIONS: LENGTH <u>12</u> WIDTH <u>4</u> DEPTH <u>7</u> REMARKS _____		
1					
2					
3					
4					
5					
6					
7					
8					
9					
10					
			LENGTH (FT)		



PROJECT NUMBER 0839293.B0.03 TEST PIT NUMBER SP2 SHEET 1 OF 1

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>RMC Southern Polymers</u>	LOCATION <u>STARS</u>	MAP OF <u>E</u> WALL OF PIT				
	INTERVAL	TYPE AND NUMBER				ELEVATION	CONTRACTOR	EXCAVATION METHOD	DATE EXCAVATED
1									<p>Very little debris Samples Collected @ surface, 2.5' and 5'</p>
2									
3									
4									
5									
6									
7									
8									
9									
10									
			<p>Hand-drawn sketch of the test pit wall showing a large, irregularly shaped area labeled "Silty claystone?" and "Silty claystone?". The area is shaded with diagonal lines. The sketch is labeled "D" in the top right corner.</p>						
			LENGTH (FT)						

CRI HILL

PROJECT NUMBER <u>OPF39293.B0.03</u>	TEST PIT NUMBER <u>SP.3</u>	SHEET <u>1</u> OF <u>1</u>
---	--------------------------------	----------------------------


TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>RMC Southern Potliner</u>	LOCATION _____	MAP OF <u>W</u> WALL OF PIT
	INTERVAL	TYPE AND NUMBER	ELEVATION _____	CONTRACTOR <u>STRATUS</u>	DATE EXCAVATED <u>7/21/94</u>
			WATER LEVEL AND DATE _____	EXCAVATION METHOD <u>CAT 4166</u>	LOGGER <u>Rmo</u>
			APPROXIMATE DIMENSIONS: LENGTH <u>10</u> WIDTH <u>3</u> DEPTH <u>2.5</u> REMARKS _____		
1					
2					
3					
4					
5					
6					
7					
8					
			LENGTH (FT)		



PROJECT NUMBER <u>OPE 39293, PLOT 3</u>	TEST PIT NUMBER <u>SP4</u>	SHEET <u>1</u> OF <u>1</u>
--	-------------------------------	----------------------------

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>RMC Southern POTLIN</u>	LOCATION _____	MAP OF <u>W</u> WALL OF PIT
	INTERVAL	TYPE AND NUMBER	ELEVATION _____	CONTRACTOR <u>STRATUS</u>	DATE EXCAVATED <u>7/21/94</u>
			WATER LEVEL AND DATE _____	EXCAVATION METHOD <u>CAT 416b</u>	LOGGER <u>Ruo</u>
			APPROXIMATE DIMENSIONS: LENGTH <u>11</u> WIDTH <u>3</u> DEPTH <u>3</u> REMARKS _____		
1					
2					
3					
4					
5					
6					
7					
8					
			LENGTH (FT)		

COMMENTS

sapled e D

CHMILL

PROJECT NUMBER <u>OPE 37293.BQ.03</u>	TEST PIT NUMBER <u>SP5</u>	SHEET <u>1</u> OF <u>1</u>
--	-------------------------------	----------------------------

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>RMC Southern Potlimer</u>	LOCATION _____	MAP OF <u>W</u>	WALL OF PIT
	INTERVAL	TYPE AND NUMBER	ELEVATION _____	CONTRACTOR <u>STRATUS</u>	DATE EXCAVATED <u>7/21/24</u>	
			WATER LEVEL AND DATE _____	EXCAVATION METHOD <u>CAT 416b</u>	LOGGER <u>RWO</u>	
			APPROXIMATE DIMENSIONS: LENGTH _____ WIDTH _____ DEPTH _____	REMARKS _____		
1			brick w/ grey crosshatch			COMMENTS Sample & surface 3'
2			brown sandy silt			
3						
4						
5						
6						
7						
8						
			LENGTH (FT)			




PROJECT NUMBER <u>OFF 39293.BA.03</u>	TEST PIT NUMBER <u>SP6</u>	SHEET <u>1</u> OF <u>1</u>
--	-------------------------------	----------------------------

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>RMC Southern Potliner</u>	LOCATION _____	MAP OF <u>E</u> WALL OF PIT
	INTERVAL	TYPE AND NUMBER	ELEVATION _____	CONTRACTOR <u>STRATUS</u>	DATE EXCAVATED <u>7/21/94</u>
			WATER LEVEL AND DATE _____	EXCAVATION METHOD <u>CAT 4166</u>	LOGGER <u>RWD</u>
			APPROXIMATE DIMENSIONS: LENGTH <u>10</u> WIDTH <u>3</u> DEPTH <u>3</u> REMARKS _____		
1					
2					
3					
4					
5					
6					
7					
8					
			LENGTH (FT)		



PROJECT NUMBER <u>0PE 39293.BD.03</u>	TEST PIT NUMBER <u>SP7</u>	SHEET <u>1</u> OF <u>1</u>
TEST PIT WALL LOG		


DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>PMC Southern Potliner</u>	LOCATION _____	MAP OF <u>N</u> WALL OF PIT
	INTERVAL	TYPE AND NUMBER			
			ELEVATION _____	CONTRACTOR <u>STRATUS</u>	DATE EXCAVATED <u>7/21/94</u>
			WATER LEVEL AND DATE _____	EXCAVATION METHOD <u>CAT 466</u>	LOGGER <u>RWO</u>
			APPROXIMATE DIMENSIONS: LENGTH <u>11</u> WIDTH <u>3</u> DEPTH <u>3.5</u> REMARKS _____		
1					
2					
3					
4					
5					
6					
7					
8					
			LENGTH (FT)		

COMMENTS
Sampled @
Surface @ 2.5'



PROJECT NUMBER <u>0PE37273. B.O. 03</u>	TEST PIT NUMBER <u>SP8</u>	SHEET <u>1</u> OF <u>1</u>
--	-------------------------------	----------------------------

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>RMC Southern Potline</u>	LOCATION _____	MAP OF <u>N</u> WALL OF PIT
	INTERVAL	TYPE AND NUMBER	ELEVATION _____	CONTRACTOR <u>STRATUS</u>	DATE EXCAVATED <u>7/21/74</u>
			WATER LEVEL AND DATE _____	EXCAVATION METHOD <u>CAT 4166</u>	LOGGER <u>Rus</u>
			APPROXIMATE DIMENSIONS: LENGTH <u>11</u> WIDTH <u>3</u> DEPTH <u>3.5</u> REMARKS _____		
1					
2					
3					
			COMMENTS <u>Sample @ surface</u> <u>! 2.5'</u>		
			LENGTH (FT)		



PROJECT NUMBER 0839293.00.03 SP9 TEST PIT NUMBER SHEET 1 OF 1


TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT	LOCATION	CONTRACTOR	EXCAVATION METHOD	DATE EXCAVATED	MAP OF WALL OF PIT
	INTERVAL	TYPE AND NUMBER						
1								
2								
3								
4								
5								
6								
7								
8								
			PROJECT <u>Port Southern Bollinger</u> LOCATION <u>STRAUS</u> CONTRACTOR <u>STRAUS</u> EXCAVATION METHOD <u>CAT 416b</u> DATE EXCAVATED <u>7/21/94</u> MAP OF WALL OF PIT <u>See sketch</u>					
			ELEVATION _____ WATER LEVEL AND DATE _____ APPROXIMATE DIMENSIONS: LENGTH <u>40</u> WIDTH <u>4</u> DEPTH <u>50</u> REMARKS _____					
			Black carbon 7					
			Not live brown granular streaked sand					
			Blue material					
			Sampled surface 21, 5.0					
			LENGTH (FT)					



PROJECT NUMBER <u>0739283. BA.05</u>	TEST PIT NUMBER <u>SP10</u>	SHEET <u>1</u> OF <u>1</u>
---	--------------------------------	-------------------------------

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>ENC Southern Potliver</u>	LOCATION <u>STATUS</u>	CONTRACTOR <u>STATUS</u>	EXCAVATION METHOD <u>CAT 4166</u>	ELEVATION	WATER LEVEL AND DATE	APPROXIMATE DIMENSIONS: LENGTH <u>11</u> WIDTH <u>3</u> DEPTH <u>4</u>	REMARKS	MAP OF WALL OF PIT	DATE EXCAVATED <u>7/24/94</u>	LOGGER <u>Red</u>	COMMENTS	
	INTERVAL	TYPE AND NUMBER													
1															 <p>Black carbon?</p> <p>Black carbon?</p> <p>Brown poorly sorted sand</p> <p>Sample e Surface and bottom</p>
2															
3															
4															
5															
6															
7															
8															
LENGTH (FT)															



PROJECT NUMBER
DE 39233.80.03
TEST PIT NUMBER
SP 11
SHEET 1 OF 1


TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT	LOCATION	CONTRACTOR	ELEVATION	WATER LEVEL AND DATE	EXCAVATION METHOD	APPROXIMATE DIMENSIONS: LENGTH WIDTH DEPTH	REMARKS	MAP OF WALL OF PIT	DATE EXCAVATED	LOGGER	COMMENTS
	INTERVAL	TYPE AND NUMBER												
1														Sample @ Surface 1
2														2.5'
3														
4														
5														
6														
7														
8														

Black carbon?
Brick
Heavy clay soil
Heavy clay soil


LENGTH (FT)

East Potliner Area

REV 7/86 FORM D1599



PROJECT NUMBER <i>01E 39293 BC-03</i>	TEST PIT NUMBER <i>EP8</i>	SHEET <i>1</i> OF <i>1</i>
TEST PIT WALL LOG		

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <i>RMC EASTERN POTLIN</i>	LOCATION _____	MAP OF <i>E</i> WALL OF PIT
	INTERVAL	TYPE AND NUMBER			
			ELEVATION _____	CONTRACTOR <i>STRATUS</i>	DATE EXCAVATED <i>7/22/94</i>
			WATER LEVEL AND DATE _____	EXCAVATION METHOD <i>CAT 466</i>	LOGGER <i>RW</i>
			APPROXIMATE DIMENSIONS: LENGTH <i>22</i> WIDTH <i>3</i> DEPTH <i>10' 13.0'</i> <i>10' 12'</i>		
1			 <p>tools & organic matter</p> <p>gray crystalline</p> <p>brown poorly sorted sand</p> <p>Samples @ surface, 2', and 3'</p>		
2					
3					
4					
5					
6					
			LENGTH (FT)		



PROJECT NUMBER <u>MS 39223, P&A 03</u>	TEST PIT NUMBER <u>EP9</u>	SHEET <u>1</u> OF <u>1</u>
---	-------------------------------	----------------------------

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>BAC EASTERN POTLIVER</u>	LOCATION <u>STATUS</u>	MAP OF <u>W</u> WALL OF PIT
	INTERVAL	TYPE AND NUMBER			
1			ELEVATION _____	CONTRACTOR <u>STATUS</u>	DATE EXCAVATED <u>7/22/94</u>
2			WATER LEVEL AND DATE <u>2' @ 7/22/94</u>	EXCAVATION METHOD <u>CAT 466</u>	LOGGER <u>RMS</u>
3			APPROXIMATE DIMENSIONS: LENGTH <u>22'</u> WIDTH <u>3'</u> DEPTH <u>2'</u>	REMARKS:	
4					
5					
6					
7					
			COMMENTS <u>Soil @ 2'</u> <u>Sample @ surface : 2'</u>		
LENGTH (FT)					



PROJECT NUMBER	TEST PIT NUMBER	SHEET	OF
08239773.R.D.03	EP 4	1	1


TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>ENC EXISTING PIT</u>	LOCATION	MAP OF <u>E</u> WALL OF PIT
	INTERVAL	TYPE AND NUMBER			
1			ELEVATION	CONTRACTOR <u>STEARNS</u>	DATE EXCAVATED <u>7/12/94</u>
2			WATER LEVEL AND DATE	EXCAVATION METHOD <u>CAT 416b</u>	LOGGER <u>ENC</u>
3			APPROXIMATE DIMENSIONS: LENGTH	WIDTH	DEPTH
4			REMARKS		
5			COMMENTS		
6			<p>Dry pebbles graded sand w/ gravel</p> <p>Brown s.l.f. moist.</p> <p>soils becoming moist @ 3'</p>		
			LENGTH (FT)		



PROJECT NUMBER CPE 39773 RD. 013	TEST PIT NUMBER FP 05	SHEET 1 OF 1
-------------------------------------	--------------------------	--------------

TEST PIT WALL LOG


DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>PAIC EASTERN POTLINER</u>	LOCATION _____	MAP OF <u>W</u> WALL OF PIT
	INTERVAL	TYPE AND NUMBER			
			ELEVATION _____	CONTRACTOR <u>STRATUS</u>	DATE EXCAVATED <u>2/22/94</u>
			WATER LEVEL AND DATE _____	EXCAVATION METHOD <u>CAT 4165</u>	LOGGER <u>PLW</u>
			APPROXIMATE DIMENSIONS: LENGTH <u>11</u> WIDTH <u>3</u> DEPTH <u>4</u> REMARKS _____		
1					
2					
3					
4					
5					
6					
			LENGTH (FT)		

COMMENTS
collect samples @ surface 2, 4 feet
Tight soils to 4'



PROJECT NUMBER CP23973.00.03 TEST PIT NUMBER EP6 SHEET 1 OF 1

TEST PIT WALL LOG


DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>RMC EASTERN POLYMER</u>	LOCATION _____	MAP OF <u>E</u> WALL OF PIT
	INTERVAL	TYPE AND NUMBER			
			ELEVATION _____	CONTRACTOR <u>STRATUS</u>	DATE EXCAVATED <u>7/22/94</u>
			WATER LEVEL AND DATE _____	EXCAVATION METHOD <u>CAT 466</u>	LOGGER <u>Ruo</u>
			APPROXIMATE DIMENSIONS: LENGTH <u>11</u> WIDTH <u>3</u> DEPTH <u>4</u> REMARKS _____		
1					
2					
3					
4					
5					
6					
			LENGTH (FT)		

COMMENTS
Sand @ S. face
2' and 4'



PROJECT NUMBER <u>0P39253.Pd.03</u>	TEST PIT NUMBER <u>EP3</u>
SHEET <u>1</u> OF <u>1</u>	

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>PUC EASTERN Potliner</u>	LOCATION <u>STH 4715</u>	MAP OF <u>E</u> WALL OF PIT
	INTERVAL	TYPE AND NUMBER			
1			ELEVATION _____	CONTRACTOR <u>STH 4715</u>	DATE EXCAVATED <u>7/22/04</u>
2			WATER LEVEL AND DATE _____	EXCAVATION METHOD <u>CAT 400</u>	LOGGER <u>Kuo</u>
3			APPROXIMATE DIMENSIONS: LENGTH <u>12</u> WIDTH <u>3</u> DEPTH <u>3</u>	REMARKS _____	COMMENTS _____
4					
5					
6					
LENGTH (FT)					



Scrap Yard

PROJECT NUMBER	TEST PIT NUMBER	
0PE39273.EQ.01	SY3	SHEET 1 OF 1
TEST PIT WALL LOG		

[illegible]



PROJECT NUMBER

PR 39293 B7 (1)


TEST PIT NUMBER

SY2

SHEET

OF 1


TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT	LOCATION	MAP OF	WALL OF PIT
	INTERVAL	TYPE AND NUMBER	ELEVATION	CONTRACTOR	DATE EXCAVATED	
			PRVC SCRAP YARD <td>SHUTTL'S<td>7/25/94<td></td></td></td>	SHUTTL'S <td>7/25/94<td></td></td>	7/25/94 <td></td>	
			WATER LEVEL AND DATE	EXCAVATION METHOD	LOGGER	
			APPROXIMATE DIMENSIONS: LENGTH	WIDTH	DEPTH	REMARKS
			11	2.5	4	Looking at S. WALL
1						
2						
3						
4						
			COMMENTS			
			SAMPLE c surf, 2.5-2.0, 4, composite			
			LENGTH (FT)			



PROJECT NUMBER <u>OPE 37293-BCL & 1</u>	TEST PIT NUMBER <u>SY3</u>	SHEET <u>1</u> OF <u>1</u>
--	-------------------------------	----------------------------

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>RWC SCRAP YARD</u>	LOCATION _____	MAP OF _____	WALL OF PIT _____
	INTERVAL	TYPE AND NUMBER	ELEVATION _____	CONTRACTOR <u>STRATUS</u>	DATE EXCAVATED <u>7/25/94</u>	
			WATER LEVEL AND DATE _____	EXCAVATION METHOD <u>CAT 416b</u>	LOGGER <u>R. SFO</u>	
			APPROXIMATE DIMENSIONS: LENGTH <u>12</u> WIDTH <u>2.5</u> DEPTH <u>5</u> REMARKS <u>View of North Wall</u>			
1						
2						
3						
4						
5						
			COMMENTS <u>SAMPLES COLLECTED AT surface, 2', 5' & composited</u>			
			LENGTH (FT)			



PROJECT NUMBER CPE 39793	TEST PIT NUMBER SY4	SHEET 1 OF 1
-----------------------------	------------------------	--------------


TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>Rail Scrap Yard</u>	LOCATION _____	MAP OF: <u>E</u> WALL OF PIT
	INTERVAL	TYPE AND NUMBER			
			ELEVATION _____	CONTRACTOR <u>STREETS</u>	DATE EXCAVATED <u>7/24/94</u>
			WATER LEVEL AND DATE _____	EXCAVATION METHOD <u>Cut & Fill</u>	LOGGER <u>RLW</u>
			APPROXIMATE DIMENSIONS: LENGTH <u>12</u> WIDTH <u>4</u> DEPTH <u>4</u> REMARKS _____		
1					
2					
3					
4					
5					
			LENGTH (FT)		




PROJECT NUMBER 018-39293-127.44	TEST PIT NUMBER SYS	SHEET 1 OF 1
------------------------------------	------------------------	--------------

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>KRIC SCRAP YARD</u>	LOCATION _____	MAP OF <u>E</u> WALL OF PIT
	INTERVAL	TYPE AND NUMBER			
			ELEVATION _____	CONTRACTOR <u>SIDACE</u>	DATE EXCAVATED <u>7/24/94</u>
			WATER LEVEL AND DATE _____	EXCAVATION METHOD <u>CUT & COVER</u>	LOGGER <u>RUD</u>
			APPROXIMATE DIMENSIONS: LENGTH <u>12</u> WIDTH <u>4</u> DEPTH <u>4</u> REMARKS _____		
1					
2					
3					
4					
5					
			COMMENTS <u>Sampled E surface, 2' and 4'</u>		
			LENGTH (FT)		




PROJECT NUMBER <u>LPE 39293.B4.01</u>	TEST PIT NUMBER <u>SYL</u>	SHEET <u>1</u> OF <u>1</u>
TEST PIT WALL LOG		

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>RMC SCRAP YARD</u>	LOCATION _____	MAP OF _____	WALL OF PIT _____
	INTERVAL	TYPE AND NUMBER				
			ELEVATION _____	CONTRACTOR <u>STRATICS</u>	DATE EXCAVATED <u>7/24/94</u>	
			WATER LEVEL AND DATE _____	EXCAVATION METHOD <u>CAT 416b</u>	LOGGER <u>RWO</u>	
			APPROXIMATE DIMENSIONS: LENGTH <u>12</u> WIDTH <u>4</u> DEPTH <u>2</u> REMARKS _____			
1						
2						
3						
			LENGTH (FT)			




PROJECT NUMBER <u>CPE-37293 Bx. 01</u>	TEST PIT NUMBER <u>547</u>	SHEET <u>1</u> OF <u>1</u>
TEST PIT WALL LOG		

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>PMC SCRAP YARD</u>	LOCATION _____	MAP OF <u>E</u> WALL OF PIT
	INTERVAL	TYPE AND NUMBER			
			ELEVATION _____	CONTRACTOR <u>STRATIS</u>	DATE EXCAVATED <u>7/24/94</u>
			WATER LEVEL AND DATE _____	EXCAVATION METHOD <u>CAT 4166</u>	LOGGER <u>RWC</u>
			APPROXIMATE DIMENSIONS: LENGTH <u>6'</u> WIDTH <u>3</u> DEPTH <u>1.5'</u> REMARKS _____		
1					
2					
3					
			COMMENTS <u>polluted brick?</u> <u>found sand stone?</u>		
			LENGTH (FT)		



PROJECT NUMBER <u>01E39293-09.01</u>	TEST PIT NUMBER <u>SYE</u>	SHEET <u>1</u> OF <u>1</u>
---	-------------------------------	----------------------------


TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>KRIC SCRAP YARD</u>	LOCATION _____	MAP OF <u>E</u> WALL OF PIT
	INTERVAL	TYPE AND NUMBER			
			ELEVATION _____	CONTRACTOR <u>STRATLS</u>	DATE EXCAVATED <u>7/24/84</u>
			WATER LEVEL AND DATE _____	EXCAVATION METHOD <u>CAT 466</u>	LOGGER <u>RUC</u>
			APPROXIMATE DIMENSIONS: LENGTH <u>4</u> WIDTH <u>3</u> DEPTH <u>2</u> REMARKS _____		
1					
2					
3					
			LENGTH (FT)		

COMMENTS
Sample @ surface
and 2'



PROJECT NUMBER <u>CR 39293, Bd. 01</u>	TEST PIT NUMBER <u>519</u>	SHEET <u>1</u> OF <u>1</u>
TEST PIT WALL LOG		

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>RMC SCRAPYARD</u>	LOCATION _____	MAP OF <u>W</u> WALL OF PIT
	INTERVAL	TYPE AND NUMBER			
			ELEVATION _____	CONTRACTOR <u>STRATUS</u>	DATE EXCAVATED <u>7/24/94</u>
			WATER LEVEL AND DATE _____	EXCAVATION METHOD <u>CAT4066</u>	LOGGER <u>RWO</u>
			APPROXIMATE DIMENSIONS: LENGTH <u>17</u> WIDTH <u>3</u> DEPTH <u>4</u> REMARKS _____		
1					
2					
3					
4					
			COMMENTS <u>0-4" cryolite / pollution?</u> <u>collect samples e. surface, 2' and 4'</u>		
			LENGTH (FT)		



PROJECT NUMBER 0839293.60.02 TEST PIT NUMBER SY10 SHEET 1 OF 1

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>KAC</u>	LOCATION <u>SCRAP GRND</u>	CONTRACTOR <u>SHCHTS</u>	EXCAVATION METHOD <u>CAT 416b</u>	DATE EXCAVATED <u>7/24/94</u>	MAP OF <u>N</u> WALL OF PIT
	INTERVAL	TYPE AND NUMBER						
1								
2								
3								
4								

WATER LEVEL AND DATE	LENGTH	WIDTH	DEPTH	REMARKS	COMMENTS
	<u>12</u>	<u>3</u>	<u>4</u>		

8" red sand
brown silt
pot liner?
crystallite?
Seyla & surface
2' and 4'

LENGTH (FT)




PROJECT NUMBER <u>CVE 39293.B7-D1</u>	TEST PIT NUMBER <u>SY 11</u>	SHEET <u>1</u> OF <u>2</u>
TEST PIT WALL LOG		

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>RAIL SCRAP YARD</u>	LOCATION _____	MAP OF <u>S</u> WALL OF PIT
	INTERVAL	TYPE AND NUMBER			
			ELEVATION _____	CONTRACTOR <u>STATUS</u>	DATE EXCAVATED <u>7/26/54</u>
			WATER LEVEL AND DATE _____	EXCAVATION METHOD <u>CAT 416E</u>	LOGGER <u>RWD</u>
			APPROXIMATE DIMENSIONS: LENGTH <u>12</u> WIDTH <u>4</u> DEPTH <u>4</u> REMARKS _____		
1					
2					
3					
4					
			LENGTH (FT)		



PROJECT NUMBER 618 39293. RD. 81	TEST PIT NUMBER 5412	SHEET 1 OF 1
TEST PIT WALL LOG		

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>KWIC SCRIP YARD</u>	LOCATION _____	MAP OF _____	WALL OF PIT _____
	INTERVAL	TYPE AND NUMBER				
			ELEVATION _____	CONTRACTOR <u>SPRINTS</u>	DATE EXCAVATED <u>7/24/94</u>	
			WATER LEVEL AND DATE _____	EXCAVATION METHOD <u>CAT 1 410.6</u>	LOGGER <u>K.C.C.</u>	
			APPROXIMATE DIMENSIONS: LENGTH <u>12'</u> WIDTH <u>2.5'</u> DEPTH <u>5'</u>		REMARKS <u>LOOKING NORTH</u>	
1						
2						
3						
4						
5						
			LENGTH (FT)			



PROJECT NUMBER
CIV 39253-001.01 SY13

SHEET 1 OF 1


TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>KUC SCDP V410</u>	LOCATION <u>ST 4705</u>	MAP OF	WALL OF PIT
	INTERVAL	TYPE AND NUMBER				
1			PROJECT <u>KUC SCDP V410</u>	LOCATION <u>ST 4705</u>	MAP OF	WALL OF PIT
2			ELEVATION	CONTRACTOR	DATE EXCAVATED <u>7/25/94</u>	
3			WATER LEVEL AND DATE	EXCAVATION METHOD <u>CAT 446b</u>	LOGGER <u>Lee SFO</u>	
4			APPROXIMATE DIMENSIONS: LENGTH <u>12</u> WIDTH <u>2.5</u> DEPTH <u>4.5</u>	REMARKS <u>LOOKING WEST</u>		
5						
			COMMENTS SAMPLES TAKEN @ SURFACE, 2.0', 4.5' & COMPOSITE			
LENGTH (FT)						



PROJECT NUMBER <u>0PE 39273.00.701</u>	TEST PIT NUMBER <u>SY14</u>	SHEET <u>1</u> OF <u>1</u>
---	--------------------------------	----------------------------

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>RMC SCRAP YARD</u>	LOCATION _____	MAP OF _____	WALL OF PIT _____
	INTERVAL	TYPE AND NUMBER	ELEVATION _____	CONTRACTOR <u>STIKTUS</u>	DATE EXCAVATED <u>7/24/94</u>	
			WATER LEVEL AND DATE _____	EXCAVATION METHOD <u>CAT 46b</u>	LOGGER <u>RW</u>	
			APPROXIMATE DIMENSIONS: LENGTH <u>12</u> WIDTH <u>2.5'</u> DEPTH <u>4'</u>		REMARKS <u>SOUTH SIDE VIEW OF WALL</u>	
1						
2						
3						
4						
			COMMENTS <u>SAMPLES @ Surface, 2', 4', composite</u> <u>some leaching visible in 1-2 foot section of brown sand</u>			
			LENGTH (FT)			

C.M.HILL

PROJECT NUMBER

0PE 39293-BQ.01

TEST PIT NUMBER

SY15

SHEET 1 OF 1

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>KM1C SCRAP YARD</u>	LOCATION _____	MAP OF <u>S</u> WALL OF PIT
	INTERVAL	TYPE AND NUMBER			
			ELEVATION _____	CONTRACTOR <u>STRATUS</u>	DATE EXCAVATED <u>7/28/94</u>
			WATER LEVEL AND DATE _____	EXCAVATION METHOD <u>CAT 416b</u>	LOGGER <u>Reno</u>
			APPROXIMATE DIMENSIONS: LENGTH <u>12</u> WIDTH <u>3</u> DEPTH <u>4</u> REMARKS _____		
1					
2					
3					
4					
			LENGTH (FT)		

Miscellaneous Areas



PROJECT NUMBER 0639293.85.02 TEST PIT NUMBER NF-1 SHEET 1 OF 1

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>RM-7 Road</u>	LOCATION <u>WEST FIELD</u>	MAP OF <u>F</u> WALL OF PIT	DATE EXCAVATED <u>9/23/92</u>	REMARKS	COMMENTS
	INTERVAL	TYPE AND NUMBER						
1			ELEVATION <u>11.5</u>	CONTRACTOR <u>STRATIS CORP</u>				0-1' loamy s.h. w/ gravel
2			WATER LEVEL AND DATE	EXCAVATION METHOD <u>CAT TUBES</u>				2-3' s.h. w/ clay (mud)
3			APPROXIMATE DIMENSIONS: LENGTH <u>12'</u> WIDTH <u>3'</u> DEPTH <u>4'</u>					Brown, Fine, Dry, Fine
4								10% clay
								3-4' sand, brown
								mud-fine, dry, s.h.
								large

Sampled @ 2' (2 jars WFL-2.0)

LENGTH (FT)



TEST PIT WALL LOG


PROJECT NUMBER

TEST PIT NUMBER

WE-2

SHEET 1 OF

SAMPLE	PROJECT	RMC-T		LOCATION	WEST FIELD, Middle Pit		MAP OF	E	WALL OF PIT
	INTERVAL	ELEVATION	CONTRACTOR	EXCAVATION METHOD	DATE EXCAVATED	LOGGER			
TYPE AND NUMBER	WATER LEVEL AND DATE	APPROXIMATE DIMENSIONS:	LENGTH	WIDTH	DEPTH	REMARKS			





PROJECT NUMBER	TEST PIT NUMBER WF3	SHEET	OF
TEST PIT WALL LOG			

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT RMC-T	LOCATION WEST FIELD, EAST Pit	MAP OF E	WALL OF PIT
	INTERVAL	TYPE AND NUMBER				
			ELEVATION _____	CONTRACTOR STATUS	DATE EXCAVATED 9/23/94	
			WATER LEVEL AND DATE _____	EXCAVATION METHOD CAT B.M.	LOGGER P. Brown	
			APPROXIMATE DIMENSIONS: LENGTH 12 WIDTH 4 DEPTH 3 REMARKS _____			
1						
2						
3						
4						
			LENGTH (FT)			



PROJECT NUMBER OPE39293.	TEST PIT NUMBER UTL-S	SHEET 1 OF 1
-----------------------------	--------------------------	--------------

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>REYNOLDS METALS</u>	LOCATION <u>(UTL-S)</u>	MAP OF <u>S</u> WALL OF PIT
	INTERVAL	TYPE AND NUMBER			
			ELEVATION _____	CONTRACTOR <u>STRATUS Corp</u>	DATE EXCAVATED <u>9/13/94</u>
			WATER LEVEL AND DATE _____	EXCAVATION METHOD <u>CAT 416b</u>	LOGGER <u>Ruo</u>
			APPROXIMATE DIMENSIONS: LENGTH <u>15</u> WIDTH <u>4</u> DEPTH <u>7</u> REMARKS <u>No Caps</u>		
1			<p>silt w/ some Rock</p> <p>brick / Flt. caps</p> <p>Debris</p> <p>silty sand</p> <p>UTL-S => UNDER TRANSMISSION LINES, southern pit.</p>		
2					
3					
4					
5					
6					
7					
8					
9					
10					
11					
12					
			LENGTH (FT)		

Geoprobe Borings

3993. P. 03

P1

SOIL BORING LOG

PROJECT RMC EAST PARKING LOT

LOCATION PL

ELEVATION

DRILLING CONTRACTOR

DRILLING METHOD AND EQUIPMENT

WATER LEVELS

START 7/25/64

FINISH

LOGGER

DEPTH BELOW SURFACE (FT)	SAMPLE			STANDARD PENETRATION TEST RESULTS	SOIL DESCRIPTION	COMMENTS
	INTERVAL	NUMBER AND TYPE	RECOVERY (FT)		SOIL NAME, USCS GROUP SYMBOL, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY	DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
				6"-6'-6" (N)		
1	0'					
2	3.0'	G-1	1.1'	NA	brown silt 7", brown sand 6"	
3						
4	5.0'	G-2	1.5'	NA	brown silty sand	
5						
6	7.0'	G-3	1.5'		brown sand	
7						
8						

97-3973 B6.03

P

SOIL BORING LOG

PROJECT ENC EAST PARKING LOT

LOCATION 21

ELEVATION

DRILLING CONTRACTOR *GEO-TECH EXPLORATIONS*

DRILLING METHOD AND EQUIPMENT *Coffin Probe*

WATER LEVELS

START 7/25/94

FINISH 7/25/94

LOGGER *Lee*

DEPTH BELOW SURFACE (FT)	SAMPLE			STANDARD PENETRATION TEST RESULTS	SOIL DESCRIPTION	COMMENTS
	INTERVAL	NUMBER AND TYPE	RECOVERY (FT)			
				6"-6'-6" (N)		
1	1.0					backfilled boring
2		G-1	1.0'	NA	brown silty sand (.4"), brown sand (.6")	
3	3.0					
4		G-2	1.2'	NA	brown silty sand	
5	5.0					
6		G-	1.8'	NA	brown silt	
7	7.0					

Capacitor Search




PROJECT NUMBER <u>DPE 39293.13</u>	TEST PIT NUMBER <u>NE-CAP-SEARCH</u>
SHEET <u>1</u> OF <u>1</u>	

TEST PIT WALL LOG

DEPTH BELOW SURFACE (FT)	SAMPLE		PROJECT <u>REYNOLDS METALS</u>	LOCATION <u>NORTHEAST LANDFILL</u>	MAP OF <u>N</u> WALL OF PIT
	INTERVAL	TYPE AND NUMBER	ELEVATION _____	CONTRACTOR <u>STRATUS Corp</u>	DATE EXCAVATED <u>9/13/94</u>
			WATER LEVEL AND DATE _____	EXCAVATION METHOD <u>CAT 416b</u>	LOGGER <u>Rwo</u>
			APPROXIMATE DIMENSIONS: LENGTH <u>15</u> WIDTH <u>5</u> DEPTH <u>6</u> REMARKS <u>No Caps</u>		
1					
2					
3					
4					
5					
6					
7					
8					
9					
10					
			LENGTH (FT)		

Appendix C
Geo Recon Electrical Resistivity Survey Report

GEO RECON INTERNATIONAL



applied geophysics

December 15, 1994
J94-611

Dave Dailer
CH2M-Hill, Inc.
825 N.E. Multnomah, Suite 1300
Portland, Oregon 97232

Gentlemen:

This letter report presents the results of geophysical studies completed to assist with geo-hydrologic and environmental studies at the Reynolds Aluminum Plant near Troutdale, Oregon. The general location of the exploration sites are shown on Figure I, Vicinity Map.

Magnetic, Electromagnetic and Electrical resistivity methods are viable geophysical techniques to assist in the definition of the subsurface geologic conditions at the Reynolds site. The electromagnetic and electrical resistivity methods were used in the South landfill area. The electromagnetic and electrical resistivity data appears to indicate the spatial location of the suspected waste area. It is important to note that the VES data solution, although plotted as a point solution, is derived over a moderately large area, and as such represents a composite average of the geophysical properties of the material layering at that point; whereas a drill hole log describes a discrete sample at a discrete depth.

Test pits were subsequently excavated by CH2M-Hill at several locations to establish correlation's between the VES data and discrete samples.

The computer methodology used to reduce the field collected electrical resistivity data to solution layering is more rigorous than curve matching or other empirical techniques. We normally use these more rigorous procedures to reduce the number of possible solutions for any single set of field data and provide a more definitive description of the geophysical regime at exploration sites.

The exploration program was coordinated with Mr. Dave Dailer of CH2M-Hill, Inc. The field data were collected between August 16 and August 30, 1994. Coordinate locations were established by reference to grid lines previously established by CH2M-Hill surveyors. Vertical control was obtained from the topography, as shown on a provided map.

MAGNETIC METHOD

The purpose of the magnetometer survey was to locate potential areas where electrical capacitor cores may have been buried. The areas, which were investigated, had been previously identified by Reynolds Metals and CH2M-Hill reconnaissance activity. The sites were surveyed on lines arbitrarily established across each area after discussion with CH2M-Hill personnel.

A EDA OMNI IV Magnetic Gradiometer was used to make the magnetic readings over five selected areas. This instrument records the Total Field of the top sensor, time and date of each reading and the X-Y grid location of the reading. The Total Field reading of the top sensor has been reduced to an arbitrary base station reading of 57,000 nano-Tesla (nT) utilizing Tie-Line methods to correct for diurnal variations occurring during the measurement period. A separate base station was established for each of the 5 areas. The average magnetic field for the area was in the order of 57,000 nT. The instrument is controlled by micro-processors, and the programming includes a circuit check of the processing system when the instrument is turned on. A brief discussion of magnetic theory follows in the text below.

RESULTS

The data from the five sites are presented as magnetic profiles at each site. Site 1, the north landfill area consists of line 1 and line 2, Figures 3 and 4. Line 1 was completed East to West with station 100 equal to a survey hub placed by CH2M-Hill surveyors. The ending station of line 2 is at station 100 of line 1. The most significant feature of these two lines is the magnetic high occurring near station 75 of line 1. This may also be associated with the high shown near the end of line 2.

Line 3, Figure 5, was completed along an open area approximately 500 feet South of line 1, near the northeast corner of the company Lake. The line began at the outfall road to the island heading in a general westerly direction. No apparent anomalies are noted on this line, but proximity of power lines may have overridden any magnetic anomaly.

Line 4 and line 5, Figures 6 and 7, were completed along the top of the dike. High magnetic values observed along these lines are very likely the product of significant deposits of baked brick. Near the end of each line apparent major changes in the magnetic field are the product of power line interference.

Line 6 and line 7, Figures 8 and 9, were completed approximately 100 feet East of the power substation with approximately 50 feet separation between the lines. The lines were completed from the plant road to the dike (South to North). Again significant interference from overhead power lines was noted.

Lines 8 through 11, Figures 10, 11, 12 and 13, were completed just northeast of the Reynolds facility, near the intersection of Sundial Road and the Plant Road. Line 8, Figure 10, was positioned approximately 50 west of the plant fence. All lines were North to South and spaced approximately 100 apart. The

data from lines 8 and 9 were relatively smooth and uneventful. Lines 10 and 11, Figures 12 and 13, show a significant negative to positive dipole effect approximately mid-line. It is suggested that further direct exploration be completed near the center of line 11.

MAGNETIC THEORY

The magnetic field over the surface of the earth is affected by local concentrations of (or absence of) magnetic materials, resulting in "anomalies" in the measured magnetic field. The concentrations or magnetic sources are described as either "dipoles" or "monopoles" depending on the configuration of the magnetic source. A "dipole" is essentially a magnetic source that exhibits both north and south poles, whereas a "monopole" exhibits a single pole, with the opposing pole at a great distance or infinity. An example of a "monopole" is that anomaly created by a deep well casing, whereas a "dipole" is that anomaly created by a piece of iron lying on the surface. However, it is noted that a magnetic source may be considered either as "line of monopoles" or as "line of dipoles" depending on the configuration of the source and the direction of the earth's field. For almost all cultural magnetic features, including hearths, the magnetic response is that of a dipole (Linington, 1964).

A material may have two magnetic fields; (1) an induced magnetization and (2) a remnant magnetization. Induced magnetization results from the ambient magnetic field, or the magnetic field of the earth. Remnant magnetization is that magnetic component which has a fixed direction relative to the rock and is independent of the earth's magnetic field.

The magnetic susceptibility (a measure of the degree to which a substance exhibits magnetization by an external field) increases when soil containing ferromagnetic material is heated and then cooled. That is, the magnetic susceptibility of the soil increases due to an increase in remnant magnetism (i.e. magnetism remaining in the absence of a magnetic field) as the temperature increases and is (or falls) below the Curie point (the Curie point of most rocks is 550 C.). The Curie point is the temperature above which thermal agitation prevents spontaneous magnetic ordering.

The strength of a "dipole" anomaly is inversely proportional to the cube of the distance between the source and the point of measurement. The magnetic strength of a "monopole" is inversely proportional to the square of the distance between the source and the point of measurement. The function describing a source magnetic strength is a function of the magnetic moment of the source, the distance from the source to the point of measurement, and a trigonometric relationship to the angle of inclination of the magnetic field. To define the fall off from the "peak" of the anomaly, the simple dipole function can become a complex equation.

ELECTROMAGNETIC METHODS

The electromagnetic data was collected with a Geonics EM-31. The data was collected by recording both the inphase and out-of-phase (quadrature) components, which were converted into apparent conductivity in milli-Siemens

per metre (milli-mhos per metre) for the conductivity and to parts per thousand (ppt) for the inphase response. The depth penetration of the EM-31 is approximately 18 to 19 feet (in the vertical dipole mode) depending on the height the instrument is carried off the ground, and the conductivity of the material measured.

The EM data points were collected at 25 foot intervals along the grid lines.

The EM-31 is a frequency domain electromagnetic device. The device transmits a 9.8 kHz electromagnetic signal. The resulting electromagnetic signal is received at another coil, spaced 3.66 metres from the transmitting coil. As the electromagnetic wave encounters a conducting medium (the ground), it sets up an alternating flow of current, which in turn radiates a wave at an equivalent frequency. This secondary wave interacts with the primary wave (transmitted through the air), creating distortion of the transmitted wave at the receiving coil. The amount of distortion is a function of the ability of the current to flow in the second medium (the ground), or the ground conductivity. The current flow through the ground is a function of two variables, (1) the inphase portion and (2) the out-of-phase portion. The out-of-phase portion acts at ninety degrees to the inphase portion.

When the transmitted wave interacts with a conductive material the distortion is dominated by the out-of-phase portion of the re-radiated wave. As a result the "computed" ground conductivity goes to zero (the inphase and out-of-phase voltages reverse polarity). The decrease in conductivity is preceded and followed by an increase in apparent conductivity.

The electromagnetic data was used as a guide along with the electrical resistivity data to determine the landfill boundary shown on Figure 2, Electrical Resistivity Studies. The electrical resistivity data was used as a guide for further direct exploration. Based upon our understanding of the local geology of the Reynolds site, we believe the near surface materials should exhibit a relatively high electrical resistivity, except in the materials below the water table where a reduction of the overall resistivity should occur. We believe the landfill materials should conversely demonstrate a low resistivity. Based upon the above, we have constructed an interpreted outline of the area believed to contain landfill materials. Variations, of the resistivity, within this area may represent changes in the percentage of landfill materials present. Of particular note are the very low resistivity zones shown near grid points E-500, D-400, C-150 and A-250. These areas show an extremely low resistivity which may indicate very high percentages of landfill materials. A general interpreted depth of the waste fill, based upon the electrical resistivity data, is approximately 6 to 8 feet. However, the highly variable nature of the fill material do not produce a uniform resistivity by which to establish a definite boundary.

The density of electrical data along line D is much more sparse than along other lines. Much of the data along this line was not interpretable due to interfering noise. The noise may be produced by unknown subsurface features, such as pipes and large deposits of metallic debris which produce huge lateral changes along the sounding array.

THE ELECTRICAL RESISTIVITY METHOD

The electrical resistivity method may be utilized to determine the configuration of subsurface materials based upon differences in their electrical properties (i.e., electrical resistivity).

C. and M. Schlumberger during the early 1900's were the primary developers of electrical prospecting methods, as we know them today. Utilizing resistivity mapping and electrical soundings they revolutionized the field of geophysical exploration. Initially, electrical methods were applied to Tectonic mining surveys of sedimentary deposits, each formation being characterized by its resistivity. Since the position and material properties of the strata, together with the amount of water contained in the strata, affects the electrical properties of the strata, it rapidly became evident that formations could be followed, their thickness determined and permeable areas located. Analogous to the location of permeable areas, Barnes in the 1950's proposed the use of electrical methods for the delineation of sand and gravel deposits. The basis for this proposal was the significant increase in resistivity to be expected by the increase in the granular nature of underlying deposits. These increases in resistivity would thus equate permeability and granularity.

In 1974 the U.S. Geological Survey published a text entitled, "The Application of Surface Geophysics to Groundwater Investigations". This text was instrumental in establishing a basis for the use of electrical resistivity methods in groundwater exploration. The field of electrical techniques has rapidly progressed in recent years by notable advances in field instrumentation and interpretive methods.

Advances in instrumentation has lead to the development of solid state circuitry for power supplies and signal amplification in the receiver. These advances have resulted in lower weight for power capabilities and greater sensitivity. The primary result of increased sensitivity is that the sensitivity may only be limited by internal instrumentation electrical noise. Electrical noise originating from industrial currents or natural earth currents have been significantly reduced by the use of synchronous detection systems, in which the transmitter current and receiver polarity are reversed periodically at a frequency of less than one Hertz. Noise which is asynchronous with the switching frequency is then averaged out.

Theoretical Background

The resistivity of a geologic unit is a function which is determined by the amount of contained water; the quantity of total dissolved salts in the water and the distribution of the water within the unit, that is the amount of void space which may contain water. Thus, the resistivity of most granular soils and rocks is controlled more by porosity, water content and water quality than by the conductivity of matrix materials.

The capacity of a strata to conduct electricity is affected by the number of interconnected spaces (permeability) and the water content. Void spaces must be interconnected and filled with water in order to conduct electricity. The pore volumes may consist of two parts; larger voids which serve as storage locations and finer interconnecting zones. Much of the resistance to current flow is due to the connecting of small sized pores because of their smaller cross section. Thus, a rock with a higher ratio of storage pore volume to connecting pore volume will have a higher resistivity.

Clay minerals such as kaolinite, halloysite, montmorillonite, etc., have the property of absorbing ions in an exchangeable state. Thus, when clay is mixed with water, the exchangeable ions may separate from the clay minerals in a process resembling ionization. These ions render the water in a pore structure conductive, even when the water has no salinity. Most earth materials possess some exchange capacity, therefore, the conductivity of an electrolyte in a pore structure will always be increased by ions supplied by desorption.

The pore structure of a geologic material need not necessarily be filled with an electrolyte as is usually found in strata lying above the regional groundwater table. Most of the pore space is generally filled with air with only the granular surfaces coated with water, termed pellicular water. The resistivity of a material containing only a partial fraction of saturation will generally exhibit a resistivity much higher than the same material fully saturated. Studies of the effect desaturation has on the resistivity of various types of oil reservoir rocks containing saline water have led to recognition of an empirical expression termed Archie's Law:

$$\rho_a = \rho_w \psi^m$$

where ρ_a is the bulk resistivity of the geologic unit, ρ_w is the resistivity of the water contained in the pore structure, and ψ is the porosity expressed as a fraction per unit volume of rock. The terms "a" and "m" are parameters whose values are assigned to allow the equation to fit practical field measurements.

Generally it has been found that "a" is slightly greater than one, and "m" is slightly less than two for granular materials. Thus, as the above equation indicates, the resistivity increases as (approximately) the square of the reduction in water content. It therefore is suggestive that resistivity measurements should be an effective method to determine the degree of saturation and porosity (i.e., grain size distribution).

Field and Interpretive Methods

Vertical electrical soundings (VES) are accomplished by applying a direct current or very low frequency synchronous alternating current to the ground through a pair of electrodes (A & B) and measuring the resulting potential established by this current across a second set of electrodes (M & N). The corresponding resistivity may be calculated according to Ohm's Law as follows:

$$R = K(E/I)$$

Where K is a geometric factor depending only upon the relative position of the four electrodes.

In order to study the variation of resistivity with depth, the spacing between the various electrodes is gradually increased. The effect of materials at depth becomes more pronounced with the increased electrode spacing and corresponding set of potential measurements. The relationship of electrode spacing to potential distribution is shown in Figure 2R for a uniform homogeneous half space.

Interpretation of the corresponding data obtained during an electrical resistivity study has evolved tremendously since the work of the Schlumberger brothers in the 1900's. This evolution has followed a sequence consisting of solution by empirical techniques (circa 1940-1960 to present). The empirical methods involved the assumption of a direct relationship of depth to electrode spacing and in many instances, appeared to produce reasonable results, when the underlying substratum was non-conductive. Curve matching techniques achieved much better results but were however rather limited by the number of published theoretical curves and the complexity of the field curve. Generally, the analysis of a field curve was limited to no more than four layers. There were additional techniques by which a curve could be matched to allow five or more layers, although due to the tedium and inaccuracies introduced by these solutions, such solutions were utilized very infrequently with less than desirable results. During the early to mid-1970's, several investigators began to use high speed digital computers for the analysis of electrical resistivity data. Probably the most predominant interpretive method which has evolved consists of the convolution of the field curve by the application of a series of filter coefficients which are applied for the direct solution of the integral defining the resistivity of a solid earth. Thus, it is possible to develop an electrical model from the field curve with no further input. Currently, it is possible by utilization of computer techniques to easily solve field curves in excess of five layer electrical models.

Dependent upon site conditions and the electrical "target", we may use one or more electrode arrays. In these arrays the current is applied across the outer electrodes. The potential change is measured between two inner electrodes.

ELECTRICAL RESISTIVITY DATA

The interpreted thickness, depths and resistivity values for each sounding are computed as (1) the Dar Zarrouk Reduction of the Detailed Solution and (2) the Detailed Solution to Smoothed VES Curve. The Detailed Solution is the interpreted resistivity solution for an initial estimation of 1 layer per data point. After the initial program pass, this estimation is reduced in the Dar Zarrouk domain, and the remaining layers are resolved until the curve fitting criteria is satisfied. The input data is projected to the preceding decade (in this case 0.1 to 1 metre, AB/2) to resolve the top most layers. The reduced

data is based upon the Dar Zarrouk reduction of the detailed solution. The Dar Zarrouk reduction is generally that which we select for the final interpretation. It is noted, however, that the Dar Zarrouk reduction may eliminate some thin layers that may be significant. Both solutions should be inspected to determine layer continuity between adjacent soundings.

ELECTRICAL RESISTIVITY METHODS AND INTERPRETATION

1. EQUIPMENT

A. An AGI Sting R1 electrical resistivity system was used for this study with associated interconnect cables and stainless steel electrodes.

2. ELECTRICAL RESISTIVITY FIELD METHODS

The vertical electrical soundings (VES) were accomplished by applying a D. C. current to the ground through a pair of electrodes and measuring the potential established by this current across a second set of electrodes. In order to study the variation of resistivity with depth, the spacing between the various electrodes was gradually increased. The effect of materials at depth becomes more pronounced with the increased electrode spacing and corresponding potential.

We trust the above will complete your requirements for this project. If you need further clarification or additional information please let us know.

For: Geo Recon International Ltd.


Clyde A. Ringstad
Principal Geophysicist

Line 11



CH2M-HILL

REYNOLDS ALUMINUM PROJECT
TROUTDALE - OREGON

MAGNETOMETER SURVEY


SEPTEMBER 1984

GEO-RECON INTERNATIONAL LTD.

J24-011

FIG. 13

Line 10



CH2M-HILL
REYNOLDS ALUMINUM PROJECT
TROUTDALE - OREGON

MAGNETOMETER SURVEY


SEPTEMBER 1994

GEO-RECON INTERNATIONAL LTD.

JS4-511

FIG. 12

Line 9



CH2M-HILL
REYNOLDS ALUMINUM PROJECT
TROUTDALE - OREGON

MAGNETOMETER SURVEY


SEPTEMBER 1984

J94-811

GEO-RECON INTERNATIONAL LTD.

FIG. 11

Line 8



CH2M-HILL

REYNOLDS ALUMINUM PROJECT
TROUTDALE - OREGON

MAGNETOMETER SURVEY


SEPTEMBER 1994

484-611

GEO-RECON INTERNATIONAL LTD.

FIG. 10

Line 7



CH2M-HILL

REYNOLDS ALUMINUM PROJECT
TROUTDALE - OREGON

MAGNETOMETER SURVEY


SEPTEMBER 1994

JD4-611

GEO-RECON INTERNATIONAL LTD.

FIG. 9

Line 6



CH2M-HILL

REYNOLDS ALUMINUM PROJECT
TROUTDALE - OREGON

MAGNETOMETER SURVEY


SEPTEMBER 1994

GEO-RECON INTERNATIONAL LTD.

JB4-611

FIG. 8

Line 5



CH2M-HILL

REYNOLDS ALUMINUM PROJECT
TROUTDALE - OREGON

MAGNETOMETER SURVEY


SEPTEMBER 1984

GEO-RECON INTERNATIONAL LTD.

J84-811

FIG. 7

Line 4



CH2M-HILL

REYNOLDS ALUMINUM PROJECT
TROUTDALE - OREGON

MAGNETOMETER SURVEY


SEPTEMBER 1984

GEO-RECON INTERNATIONAL LTD.

JS4-011

FIG. 6

Line 3



CH2M-HILL

REYNOLDS ALUMINUM PROJECT
TROUTDALE - OREGON

MAGNETOMETER SURVEY


SEPTEMBER 1994

JD4-B11

GEO-RECON INTERNATIONAL LTD.

FIG. 5

Line 2



CH2M-HILL

REYNOLDS ALUMINUM PROJECT
TROUTDALE - OREGON

MAGNETOMETER SURVEY


SEPTEMBER 1994

GEO-RECON INTERNATIONAL LTD.

J94-011

FIG. 4

Line 1



CH2M-HILL

REYNOLDS ALUMINUM PROJECT
TROUTDALE - OREGON


MAGNETOMETER SURVEY

SEPTEMBER 1994


J94-611

GEO-RECON INTERNATIONAL LTD.

FIG. 3



CH2M HILL, INC.	
REYNOLDS ALUMINUM COMPANY	
TROUTDALE, OREGON	
ELECTRICAL RESISTIVITY STUDIES	
GEO. RECON INTERNATIONAL	
APPLIED GEOPHYSICS	
J94-611	SEPTEMBER 1994
FIG.2	



CH2M-HILL INC.
REYNOLDS ALUMINUM COMPANY
TROUTDALE - OREGON

LOCATION PLAN MAP

SEPTEMBER 1984

JS4-611

GEO-RECON INTERNATIONAL LTD.

FIG. 1

Appendix D
Monitoring Well Geologic Logs
and Well Construction Diagrams

WELL NUMBER

OPE39293.B1.01

MW-01

SHEET 1 OF 1

MONITORING WELL GEOLOGIC AND CONSTRUCTION LOG

PROJECT Reynolds Metals

LOCATION Old Cryolite Plant

MEASURING POINT ELEV (NGVD) 28.25

DRILLING CONTRACTOR GeoTech-Mickey

DRILLING METHOD AND EQUIPMENT HSA 8-1/4" Augers, Canterra 250

WATER LEVEL ELEV/DATE 10.56 7-18-94

START 7-12-94

FINISH 7-12-94

LOGGER Heidi Hoffmann

DEPTH BELOW SURFACE (FT)	SAMPLE			STANDARD PENETRATION TEST RESULTS 6" - 6" - 6" (N)	SOIL DESCRIPTION	USCS DESCRIPTION	WELL COMPLETION DIAGRAM	
	INTERVAL	TYPE AND NUMBER	RECOVERY FEET		SOIL NAME, USCS GROUP SYMBOL, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY		Locking Cap	Blank PVC Casing
5.0	2.5				SILTY SANDY GRAVEL, GM, brown, angular gravel, dry, fill.	GM/FS		
	4.0	S-1	1.5	12-13-20 (33)	SILT, ML, v. dk gray, (10YR 3/1), dry, hard, wood pieces, OVM=0.0, HCN=0.0.	ML	PVC Stickup = 3.0 ft	
	5.0						Concrete Pad	
	6.5	S-2	1.5	10-22-23 (45)	SAND, SP, dk grayish brown, (10YR 4/2), moist, medium sand, 5% silt, dense, Fe-oxide staining. OVM=0.0, HCN=0.0.		Volclay Coarse Bentonite Chips	
	7.5							
10.0	9.0	S-3	1.5	8-20-23 (43)	SAND, SP, dk grayish brown, (10YR 4/2), coarse sand, 5-10% silt, dense, moist-wet. OVM=0.0, HCN=0.0.	SP		
	10.0							
	11.5	S-4	0.6	7-8-6 (14)	SAND, SP, dk grayish brown, (10YR 4/2), wet, coarse sand, 5% silt. At 11.2' SILT, ML, grayish brown, wet, stiff. OVM=0.0, HCN=0.0.		Stainless Steel Centralizer	
	12.5							
	14.0	S-5	1.0	2-3-1 (4)	SILT, ML, v. dk gray, (2.5YN 3), wet, soft, plastic. OVM=0.0, HCN=0.0.			
15.0	15.0							
	16.5	S-6	0.8	2-2-3 (5)	SILT, ML, v. dk gray, (2.5YN 3), wet, firm, plastic. OVM=0.0, HCN=0.0. Drillers smell NH3 downhole.	ML	20x40 Colorado Silica Sand	
	17.5							
	19.0	S-7	0.6	3-4-3 (7)	SILT, ML, v. dk gray, wet, plastic, firm, lense of brown plastic, silt, 3" thick. OVM=0.0, HCN=0.0.			
	20.0							
20.0	20.0							
	21.5	S-8	1.3	2-3-5 (8)	SILT, ML, black, (5Y 2.5/1), wet, firm, plastic. OVM=0.0, HCN=0.0.		Stainless Steel Centralizer	
25.0								
					BOH=20'			

4" diameter V-wire wrapped 10 slot Schedule 40 PVC Screen flush-threaded

Endcap

4" Diameter Schedule 40 Flush Treaded PCV

Locking Protective Casing-6" w/ 3 Protective Bullards



PROJECT NUMBER OPE39293.B1.01	WELL NUMBER MW-02
SHEET 1 OF 1	
MONITORING WELL GEOLOGIC AND CONSTRUCTION LOG	

PROJECT Reynolds Metals LOCATION Between Scrap Area & Former Mercury Spill
 MEASURING POINT ELEV (NGVD) 31.65 DRILLING CONTRACTOR GeoTech-Mickey
 DRILLING METHOD AND EQUIPMENT HSA 8-1/4" Augers, Canterra 250
 WATER LEVEL ELEV/DATE 21.0 7-18-94 START 7-11-94 FINISH 7-11-94 LOGGER Heidi Hoffmann

DEPTH BELOW SURFACE (FT)	SAMPLE			STANDARD PENETRATION TEST RESULTS 6" -6" -6" (N)	SOIL DESCRIPTION SOIL NAME, USCS GROUP SYMBOL, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY	USCS DESCRIPTION	WELL COMPLETION DIAGRAM	
	INTERVAL	TYPE AND NUMBER	RECOVERY FEET					
5.0	2.5				SILT, ML, v. dk gray, (7.5YR 3/1), dry.	ML	<p> Locking Cap PVC Stickup = 2.67 ft Concrete Pad Volclay Coarse Bentonite Chips Blank PVC Casing Locking Protective Casing - 6" w/ 3 Protective Bullards 4" diameter 10 slot Schedule 40 PVC Screen 4" High Treated End Cap Schedule 40 PCV </p>	
	4.0	S-1	1.5	3-8-17 (25)	SILTY SAND, SM, brown, (10YR 4/3), dry, slightly moist at top of fine sand, medium. OVM=0.0, HCN=0.0.	SM		
	5.0							
	6.5	S-2	0.8		SAND, SP, brown, (10YR 4/3), v. sl. moist, fine sand, well-sorted. OVM=0.0, HCN=0.0.	SP		
	7.5							
10.0	9.0	S-3	1.5	7-9-10 (19)	SAND, SP, brown, wet, medium, fine sand. At 8": SILTY SAND, SM, brown, wet. OVM=1.0, HCN=0.0.	SM		
	10.0							
	11.5	S-4	1.5	1-2-3 (5)	SILT, ML, grayish brown, wet, soft. At 10.5": CLAY, CL, v. dk (7.5YR 3/1), wet, plastic, firm, Fe-oxide staining. OVM=0.5, HCN=0.0.	ML		
	12.5							
	14.0	S-5	1.5	3-3-4 (7)	SILTY CLAY, CL, v. dk gray, Fe-oxide staining, wet, firm.	CL		
15.0	15.0				SILTY SAND, SM, brown w/gray mottled, wet. OVM=0.0, HCN=0.0.	SM		
	16.5	S-6	1.5	3-4-6 (10)	SANDY SILT, ML, dk gray, wet, loose, fine sand, 20-30% sand, Fe-oxide staining. OVM=0.0, HCN=0.0.	ML		
	17.5							
	19.0	S-7	1.5	3-3-4 (7)	SAND, SP, gray, (7.5YR 4/N3), fine sand. Middle 6": SILTY SAND, SM, wet, loose. OVM=0.0, HCN=0.0.	SP		
	20.0							
20.0	21.5	S-8	1.5	4-4-5 (9)	SILT SAND, SM, dk gray, (7.5YR 4/N3), wet, lenses of fine sand, loose. OVM=0.0, HCN=0.0.	SM		
	22.5							
	24.0	S-9	1.5	4-4-6 (10)	SILTY SAND, SM, dk gray, (5YR 4/1), wet, loose, Fe-oxide.	SM		
25.0					Bottom 6": SAND, SP, dk gray, wet, medium sand, well-sorted. OVM=0.0, HCN=0.0.	SP		
					BOH-24'			



PROJECT NUMBER
OPE39293.B1.01

WELL NUMBER
MW-03

SHEET 1 OF 1

MONITORING WELL GEOLOGIC AND CONSTRUCTION LOG

PROJECT Reynolds Metals

LOCATION Graham Road

MEASURING POINT ELEV (NGVD) 29.69

DRILLING CONTRACTOR GeoTech-Mickey


DRILLING METHOD AND EQUIPMENT HSA 6 1/4" Augers Canterra 250

WATER LEVEL ELEV/DATE 7.19

START 7-9-94

FINISH 7-9-94

LOGGER Heidi Hoffmann

DEPTH BELOW SURFACE (FT)	SAMPLE			STANDARD PENETRATION TEST RESULTS 6" -6" -6" (N)	SOIL DESCRIPTION SOIL NAME, USCS GROUP SYMBOL, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY	USCS DESCRIPTION	WELL COMPLETION DIAGRAM	
	INTERVAL	TYPE AND NUMBER	RECOVERY FEET					
5.0	2.5				<u>SILTY</u> , ML, dk brown, dry.	ML		
	4.0	S-1	0.6	17-18-16 (34)	<u>SAND</u> , SP, strong brown, (7.5YR 4/6), wet, fine, dense. At 3.5' <u>SILT</u> , ML, v. dk gray, (10YR 3/1), wet. OVM=0.0, HCN=0.0.	SP		
	5.0					ML		
	6.5	S-2	1.5	8-9-17 (26)	<u>SAND</u> , SP, v. dk gray, (10YR 3/1), wet, medium, fining downward from medium to fine sand. OVM=0.0, HCN=0.0.			
	7.5							
10.0	9.0	S-3	1.5	6-8-12 (20)	<u>SAND</u> , SP, v. dk gray, (10YR 3/1), wet, medium, fine sand, ~10% silt, Fe-oxide in top of spoon. OVM=0.0, HCN=0.0.	SP		
	10.0							
	11.5	S-4	1.5	7-12-14 (26)	<u>SAND</u> , SP, v. dk gray, (10YR 3/1), wet, medium v. fine sand, well-sorted. OVM=0.0, HCN=0.0.			
	12.5							
	14.0	S-5	1.5	6-12-6 (18)	<u>SAND</u> , SP, v. dk grayish brown, (10YR 3/2), wet, medium, v. fine sand, well-sorted. OVM=0.0, HCN=0.0.			
15.0	15.0							
	16.5	S-6	0.6	1-2-3 (5)	<u>SILTY SAND</u> , SM, dk grayish brown, (10YR 3/2), wet, loose, wood chunks. OVM=0.0, HCN=0.0.	SM		
	17.5							
	19.0	S-7	1.5	1-3-2 (5)	<u>SILTY SAND</u> , SM, v. dk grayish brown, (10YR 3/2), wet, loose. OVM=0.0, HCN=0.0.			
20.0					BOH=18'			
25.0								



PROJECT NUMBER

OPE39293.B1.01

WELL NUMBER

MW-04

SHEET 1 OF 1

MONITORING WELL GEOLOGIC AND CONSTRUCTION LOG

PROJECT Reynolds Metals

LOCATION Near drainage ditch SW portion of site

MEASURING POINT ELEV (NGVD) 26.91

DRILLING CONTRACTOR GeoTech-Stan

DRILLING METHOD AND EQUIPMENT HSA 8 1/4" Augers Conterra 250


WATER LEVEL ELEV/DATE 16.45 7-15-94

START 7-12-94

FINISH 7-12-94

LOGGER Heidi Hoffmann

DEPTH BELOW SURFACE (FT)	SAMPLE			STANDARD PENETRATION TEST RESULTS 6" -6" -6" (N)	SOIL DESCRIPTION SOIL NAME, USCS GROUP SYMBOL, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY	USCS DESCRIPTION	WELL COMPLETION DIAGRAM	
	INTERVAL	TYPE AND NUMBER	RECOVERY FEET					
2.5							Locking Cap	
4.0	S-1	1.2		7-7-10 (17)	SILT, ML, grayish brown, (10YR 5/2), dry, black carbon staining plus black carbon pieces, stiff. OVM=0.0, HCN=0.0.			
5.0							Volclay Coarse Bentonite Chips	
6.5	S-2	1.5		5-6-7 (13)	SILT, ML, grayish brown, (10YR 5/2), sl. moist, black carbon staining, stiff, Fe-oxide. OVM=0.0, HCN=0.0.			
7.5							Stainless Steel Centralizer	
9.0	S-3	1.5		4-5-6 (11)	SILT, ML, black, moist, stiff, abundant roots and wood, appears to be a recent surface. OVM=0.0, HCN=0.0.			
10.0							Stainless Steel Centralizer	
11.5	S-4	1.2		7-13-14 (27)	SILT, ML, dk gray, (10YR 4/1), wet, v. stiff, well-graded. OVM=0.0, HCN=0.0.			
12.5							20x40 Colorado Silica Sand	
14.0	S-5	0		5/1.5'	No recovery.			
15.0							Stainless Steel Centralizer	
16.5	S-6	1.5		7-8-7 (15)	CLAY, CL, v. dk gray, wet, stiff, plastic. OVM=0.0, HCN=0.0			
17.5							Stainless Steel Centralizer	
19.0	S-7	1.5		5-6-7 (13)	CLAY, CL, v. dk gray, (10YR 4/1), wet, stiff, plastic. OVM=0.0, HCN=0.0.			
20.0							Stainless Steel Centralizer	
21.5	S-8	1.5		5-6-9 (15)	CLAY, CL, v. dk gray, (10YR 4/1), wet, stiff, plastic, siltier at bottom.			
25.0					BOH=20'			





PROJECT NUMBER
OPE39293.B1.01

WELL NUMBER
MW-05

SHEET 1 OF 1

MONITORING WELL GEOLOGIC AND CONSTRUCTION LOG

PROJECT Reynolds Metals

LOCATION Near Sandy River

MEASURING POINT ELEV (NGVD) 33.99

DRILLING CONTRACTOR GeoTech-Mickey


DRILLING METHOD AND EQUIPMENT HSA 6 1/4" Augers Canterra 250

WATER LEVEL ELEV/DATE 12.65 7-18-94

START 7-8-94

FINISH 7-8-94

LOGGER Heidi Hoffmann

DEPTH BELOW SURFACE (FT)	SAMPLE			STANDARD PENETRATION TEST RESULTS 6" - 6" - 6" (N)	SOIL DESCRIPTION SOIL NAME, USCS GROUP SYMBOL, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY	USCS DESCRIPTION	WELL COMPLETION DIAGRAM	
	INTERVAL	TYPE AND NUMBER	RECOVERY - FEET					
5.0	2.5	S-1	1.5	7-8-14 (22)	SAND, SP, dk grayish brown, (10YR 4/2), dry, medium, medium-coarse, sandy, loose. OVM=0.0, HCN=0.0.	SP		
	4.0							
	5.0	S-2	1.5	7-10-9 (19)	SAND, SP, dk grayish brown, (10YR 4/2), v. sl. moist, loose. OVM=0.0, HCN=0.0. At 6': SILT, ML, gray and Fe-stained, mottled, v. moist.			
	6.5							
	7.5	S-3	1.5	5-6-5 (11)	SILT, ML, gray and Fe-oxidized staining, mottled, v. moist to wet, plastic, stiff. OVM=0.0, HCN=0.0.			
9.0								
10.0	10.0	S-4	1.5	3-9-3 (12)	SILTY CLAY, ML/CL, dk brown w/gray and Fe-oxide staining, mottled, plastic, wet, stiff. OVM=0.0, HCN=0.0.	ML		
	11.5							
	12.5	S-5	1.5	2-1-2 (3)	SILT, ML, dk grayish brown, wet, soft, Fe-oxide and gray mottled vertical streaks. OVM=0.0, HCN=0.0.			
	14.0							
	15.0	15.0	S-6	1.5	3-4-7 (11)	SILT, ML, dk grayish brown, wet, stiff, 10-20% fine sand, less Fe-oxide. OVM=0.0, HCN=0.0.		
16.5								
17.5		S-7	1.5	7-2-8 (10)	SILT, ML, dk grayish brown, wet, stiff, plastic, stringers of SILTY SAND, SM, fine-medium sand.	SM ML		
19.0								
20.0		20.0	S-8	1.5	4-5-4 (9)	SANDY SILT, SM, dk grayish brown, orange, Fe-oxide and gray reduction staining, wet.		
	21.5							
	22.5	S-9	1.5	5-6-6 (12)	SILTY SAND, SM, dk grayish brown, wet, medium, fine-medium sand.	SM		
	24.0							
	25.0				BOH=25.2'			



PROJECT NUMBER
OPE39293.B1.01

WELL NUMBER
MW-06

SHEET 1 OF 1

MONITORING WELL GEOLOGIC AND CONSTRUCTION LOG

PROJECT Reynolds Metals

LOCATION Field on NE corner of Sundial & Reynolds Plants

MEASURING POINT ELEV (NGVD) 26.81

DRILLING CONTRACTOR GeoTech-Mickey

DRILLING METHOD AND EQUIPMENT HSA 6 1/4" Augers Conterra 250

WATER LEVEL ELEV/DATE 11.79 7-13-94

START 7-8-94

FINISH 7-8-94

LOGGER Heidi Hoffmann

DEPTH BELOW SURFACE (FT)	SAMPLE			STANDARD PENETRATION TEST RESULTS	SOIL DESCRIPTION	USCS DESCRIPTION	WELL COMPLETION DIAGRAM	
	INTERVAL	TYPE AND NUMBER	RECOVERY FEET	6" - 6" - 6" (N)	SOIL NAME, USCS GROUP SYMBOL, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY		Locking Cap	Blank PVC Casing
5.0	2.5				SAND, SP, dk grayish brown, (2.5Y 4/2), dry, medium, fine-medium sand, lenses of <u>SILTY SAND</u> , SM. OVM=0.0, HCN=0.0	SP	PVC Stickup = 2.7 ft	Concrete Pad
	4.0	S-1	1.5	5-7-8 (15)		SM		
	5.0							
6.5	6.5	S-2	1.5	1-4-2 (6)	<u>SILTY SAND</u> , SM, dk brown, (10YR 3/3), wet. At 6": <u>SILT</u> , ML, dk grayish brown, (10YR 4/2), v. moist, Fe-oxide staining, stiff. OVM=0.0, HCN=0.0.	SM	Volclay Coarse Bentonite Chips	
	7.5							
	9.0	S-3	1.5	3-4-5 (9)				
10.0	10.0				<u>SILT</u> , ML, dk grayish brown, (10YR 4/2), v. moist, Fe-staining, root casts, plastic, stiff. OVM=0.0, HCN=0.0.			
	11.5	S-4	1.5	3-3-3 (6)				
	12.5							
14.0	14.0	S-5	1.5	2-5-6 (1)	<u>SILT</u> , ML same as above.	ML	Stainless Steel Centralizer	
	15.0							
	16.5	S-6	1.5	4-4-5 (9)				
17.5	17.5				<u>SILT</u> , ML, same as above.		20x40 Colorado Silica Sand	
	19.0	S-7	1.5	3-3-4 (7)				
	20.0							
21.5	21.5	S-8	1.5	4-4-9 (13)	SAND, SP, v. dk grayish brown, (2.5YR 3/2), wet, medium sand.	SP	Stainless Steel Centralizer	
	22.5					SM		
	24.0	S-9	1.5	2-3-3 (6)		<u>SILTY SAND</u> , SM, center of spoon.		
25.0					SAND, SP, v. dk grayish brown, (2.5YR 3/2), wet, medium sand, loose, 10-15% silt.			
					BOH=25'			

6" Diameter Locking Mild Steel Protective Casing w/ 3 Bullards

2" diameter 10 slot Schedule 40 PVC Screen Flush-threaded

End Cap, Schedule 40 PVC 2" Diameter Flush-threaded



PROJECT NUMBER
OPE39293.B1.01

WELL NUMBER
MW-07

SHEET 1 OF 1

MONITORING WELL GEOLOGIC AND CONSTRUCTION LOG

PROJECT Reynolds Metals

LOCATION North Parking Lot

MEASURING POINT ELEV (NGVD) 28.38

DRILLING CONTRACTOR GeoTech-Mickey


DRILLING METHOD AND EQUIPMENT HSA 8 1/4" Augers Conterra 250

WATER LEVEL ELEV/DATE 13.13 7-14-94

START 7-9-94

FINISH 7-9-94

LOGGER Heidi Hoffmann

DEPTH BELOW SURFACE (FT)	SAMPLE			STANDARD PENETRATION TEST RESULTS 6" - 6" - 6" (N)	SOIL DESCRIPTION SOIL NAME, USCS GROUP SYMBOL, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY	USCS DESCRIPTION	WELL COMPLETION DIAGRAM	
	INTERVAL	TYPE AND NUMBER	RECOVERY FEET					
5.0	2.5				Asphalt	ASPHALT		
	4.0	S-1	0.8	9-9-6 (15)	SILTY SANDY GRAVEL, GM, v. dk brown, dry.	GM		
	5.0				SILTY SAND, SM, v. dk grayish brown, (10YR 3/2), wet at bottom of ss, medium. OVM=0.0, HCN=0.0. Collect duplicate sample.	SM		
	6.5	S-2	1.0	4-6-11 (17)	SILT W/SAND, ML, v. dk grayish brown, (10YR 3/1), moist-wet in sand stringers, medium, sand is fine, silt is plastic. OVM=0.0, HCN=0.0.	ML		
	7.5				SILTY SAND, SM, v. dk grayish brown, (10YR 3/2), v. sl. moist sand is fine, medium, mica flakes. OVM=0.0, HCN=0.0.			
10.0	9.0	S-3	1.4	5-9-9 (18)				
	10.0				SILTY SAND, SM, brown, (10YR 3/3), moist, wet at bottom of ss, medium, mica. OVM=0.0, HCN=0.0.	SM		
	11.5	S-4	1.3	4-5-6 (11)				
	12.5				SILTY SAND, SM, brown, (10YR 3/3), wet, loose, mica. OVM=0.0, HCN=0.0.			
	14.0	S-5	1.5	2-2-6 (8)				
15.0	15.0				SILTY SAND, SM, brown, mottled with brown gray reduced areas, wet, loose. OVM=0.0, HCN=0.0.			
	16.5	S-6	1.5	2-3-5 (8)				
	17.5				SILT W/SAND, ML, dk. grayish brown, (10YR 3/2), wet, firm, mottled gray. ~10% Fe-oxide staining. OVM=0.0, HCN=0.0.			
	19.0	S-7	1.5	4-3-3 (6)				
	20.0				SILT, ML, mottled gray and rust (Fe-oxide), wet, firm, interbedded with thin layers of fine silty sand and sandy silt, silt is stiff. OVM=0.0, HCN=0.0.			
20.0	21.5	S-8	1.5	2-2-6 (8)				
	22.5				SANDY SILT, ML, mottled as above, wet, firm, sand is fine.			
	24.0	S-9	1.5	3-3-5 (8)				
25.0					BOH=25'			



PROJECT NUMBER
OPE39293.B1.01

WELL NUMBER
MW-08

SHEET 1 OF 1

MONITORING WELL GEOLOGIC AND CONSTRUCTION LOG

PROJECT Reynolds Metals

LOCATION Near Columbia River by Outlet of Company Lake

MEASURING POINT ELEV (NGVD) 25.32

DRILLING CONTRACTOR GeoTech-Mickey

DRILLING METHOD AND EQUIPMENT HSA 6 1/4" Augers Canterra 250

WATER LEVEL ELEV/DATE 17.24 7-12-94

START 7-7-94

FINISH 7-7-94

LOGGER Heidi Hoffmann

DEPTH BELOW SURFACE (FT)	SAMPLE			STANDARD PENETRATION TEST RESULTS 6" - 6" - 6" (N)	SOIL DESCRIPTION SOIL NAME, USCS GROUP SYMBOL, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY	USCS DESCRIPTION	WELL COMPLETION DIAGRAM
	INTERVAL	TYPE AND NUMBER	RECOVERY FEET				
5.0	2.5						
	4.0	S-1	1.5	Spoon broke	SILTY SAND, SM, dk brown, (10YR 3/3), v. sl. moist. OVM=0.0.	SM	
	5.0						
	6.5	S-2	1.5	7-8-12 (20)	SILTY SAND, SM, dk brown, (10YR 3/3), sl. moist, medium. At 6.2' SAND, SP, salt & pepper, sl. moist, medium-coarse sand. OVM=0.0.		
	7.5						
	9.0	S-3	1.2	7-6-9 (15)	SAND, SP, salt & pepper, v. sl. moist, medium-coarse, medium. OVM=0.0.	SP	
10.0	10.0						
	11.5	S-4	1.3	4-5-5 (10)	SAND, SP, salt & pepper w/red, v. sl. moist, loose. OVM=0.0.		
	12.5						
	14.0	S-5	1.3	5-7-8 (15)	SAND, SP, salt & pepper, moist-wet, medium, 6" of SM/ML, dk brown, (10YR 4/3), wet. OVM=0.0.	SM/ML	
15.0	15.0						
	16.5	S-6	1.3	6-6-14 (20)	SAND, SP, salt & pepper, wet, medium, ~5% silt. OVM=0.0.		
	17.5						
	19.0	S-7	1.2	5-6-6 (12)	SAND, SP, salt & pepper, wet, medium, medium-coarse, loose. OVM=0.0.		
20.0	20.0						
	21.5	S-8	1.2	4-6-5 (11)	SAND, SP, same as above. OVM=0.0.	SP	
	22.5						
	24.0	S-9	1.2	5-5-6 (11)	SAND, SP, same as above. OVM=1.1.		
25.0	25.0						
	26.5	S-10	1.1	7-7-14 (21)	SAND, SP, salt & pepper, wet, medium, ~5% subrounded pebbles. OVM=0.0.		
					BOH=28'		

The Well Completion Diagram illustrates the well's construction. It shows a 6" Diameter Locking Mild Steel Protective Casing with 3 Bullards. The casing is equipped with a Locking Cap at the top and a PVC Stickup (2.4 ft) and Concrete Pad. The well is filled with Volclay Coarse Bentonite Chips. A 2" diameter 10 slot Schedule 40 PVC Screen is installed at the bottom, with a 2" diameter 40 PVC 2" Diameter Flush-threaded End Cap. The casing is labeled as Blank PVC Casing. The diagram also shows the location of the 20x40 Colorado Silica Sand and Supreme Sand 20x40 layers.



PROJECT NUMBER

OPE39293.B1.01

WELL NUMBER

MW-09

SHEET 1 OF 1

MONITORING WELL GEOLOGIC AND CONSTRUCTION LOG

PROJECT RMC Troutdale

LOCATION N. Landfill

MEASURING POINT ELEV (NGVD) 29.27

DRILLING CONTRACTOR GeoTech Exploration

DRILLING METHOD AND EQUIPMENT 6 3/4" ID HSA

WATER LEVEL ELEV/DATE

START 8/4/94 8:30 AM

FINISH

LOGGER Phil Brown

DEPTH BELOW SURFACE (FT)	SAMPLE			STANDARD PENETRATION TEST RESULTS	SOIL DESCRIPTION	USCS DESCRIPTION	WELL COMPLETION DIAGRAM
	INTERVAL	TYPE AND NUMBER	RECOVERY FEET				
				6" - 6" - 6" (N)	SOIL NAME, USCS GROUP SYMBOL, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY		
	2.5				SANDY SILT W/GRAVEL, SM, loamy. 5% gravel to 1" angular, basaltic, dry, lt. gray/brown, firm.		
5.0	5.0			5-6-7 (13)	SILTY SAND, SM, lt. brown, damp, medium fine, some minor coarse salt and pepper sand.	SM	
	7.5			5-10-10 (20)	As above 6"; then coarser to med. Less silt, SM/SP, mottled reduction at base, some clay nodules (5%).		
10.0	10.0			4-5-7 (12)	4" SM as above, then SAND, SP, medium, lt. brown, damp, loose.		
	12.5			8-12-10 (22)	4" SM, brown/gray, mottled, damp firm. Then SAND, SP, salt & pepper, s. moist, medium-coarse, loose.	SP	
15.0	15.0			4-6-8 (14)	As above; moist to wet.		
	17.5			9-9-8 (17)	SAND, SP, darker, coarser salt and pepper, more angular. Columbia River sand (?), v. moist.		
20.0	20.0			6-8-9 (17)	As above. Wet at base, minor fine layer at 19.5'.		
	22.5			3-6-7 (13)	As above, wet.		
25.0	25.0			4-9-11 (20)	As above. 0.5" silt layer at 24', red staining below silt.		
	27.5			3-4-5 (9)	As above. Silty clay layer=1.5' thick.		
30.0					SP as above. 6" recovery.		



PROJECT NUMBER

OPE39293.B1.01

WELL NUMBER

MW-10

SHEET 1 OF 1

MONITORING WELL GEOLOGIC AND CONSTRUCTION LOG

PROJECT RMC Troutdale

LOCATION Tank Area

MEASURING POINT ELEV (NGVD) 30.28

DRILLING CONTRACTOR GeoTech Exploration

DRILLING METHOD AND EQUIPMENT 6 3/4" ID HSA

WATER LEVEL ELEV/DATE

START 8/5/94 8:30 AM

FINISH

LOGGER Phil Brown

DEPTH BELOW SURFACE (FT)	SAMPLE			STANDARD PENETRATION TEST RESULTS 6" - 6" - 6" (N)	SOIL DESCRIPTION SOIL NAME, USCS GROUP SYMBOL, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY	USCS DESCRIPTION	WELL COMPLETION DIAGRAM
	INTERVAL	TYPE AND NUMBER	RECOVERY FEET				
2.5					Silty loam gray, dry, firm, roots and organic matter.	ML	<p>Locking Cap</p> <p>Concrete Pad</p> <p>Volclay 3/4" Chips</p> <p>4" Diameter, Schedule 40 Flush-threaded PVC Casing</p> <p>6" Diameter Locking Mild Steel Protective Casing w/3 Bullards</p> <p>4" Diameter Schedule 40 Flush-threaded PVC Screen</p> <p>4" Diameter Schedule 40 PVC Silt Trap w/Secured Bottom Plug</p> <p>CSSI 20x40 Colorado Silica Sand</p>
5.0	2.5			5-5-5 (10)	SILT W/SAND, ML, brown w/gray mottling, dry to damp, medium, roots, 30-40% very fine sand.	ML	
7.5	5.0			3-7-5 (12)	SAND, SP, brown w/gray mottling, damp, loose, very fine, 30% silt.	SP	
10.0	7.5			4-3-3 (6)	SILT W/SAND, ML, brown w/gray mottling, moist, medium, increasing fine and plastic at 9'.		
12.5	10.0			1-3-2 (5)	SILT, ML, brown, moist to wet, medium, plastic, 10% very fine sand, 10% CL.		
15.0	12.5			1-1-1 (3)	Same as above, wet, plastic, 10-20% CL.		
17.5	15.0			1-1-2 (3)	SILT, ML, as above, grayer, <5% sand, 10% clay.	ML	
20.0	17.5			0-0-2 (2)	SILT, ML, as above, some macro-pores, very wet.		
22.5	20.0			0-0-3 (3)	SILT, ML, as above.		
25.0	22.5			1-2-3 (5)	SILT, ML, as above, gray w/brown mottling, 20% v. fine sand.		
27.5	25.0			1-2-4 (6)	SILT, ML, grading to sand (SP) at base, gray, wet, loose, sand very fine, 20% silt.	SP	
	27.5						



PROJECT NUMBER
OPE39293.B1.01

WELL NUMBER
MW-11

SHEET 1 OF 1

MONITORING WELL GEOLOGIC AND CONSTRUCTION LOG

PROJECT RMC Troutdale

LOCATION East Gate

MEASURING POINT ELEV (NGVD) 31.61

DRILLING CONTRACTOR GeoTech Exploration




DRILLING METHOD AND EQUIPMENT 6 3/4" ID HSA

WATER LEVEL ELEV/DATE

START 8/4/94

FINISH 8/5/94

LOGGER Phil Brown

DEPTH BELOW SURFACE (FT)	SAMPLE			STANDARD PENETRATION TEST RESULTS 6" -6" -6" (N)	SOIL DESCRIPTION SOIL NAME, USCS GROUP SYMBOL, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY	USCS DESCRIPTION	WELL COMPLETION DIAGRAM	
	INTERVAL	TYPE AND NUMBER	RECOVERY FEET					
5.0	2.5				SAND W/SILT AND GRAVEL, ML/SP/GW, fill, lt. gray to tan, dry, loose.	ML		Locking Cap Concrete Pad Volclay 3/4" Chips Stainless Steel Centralizer CSSI 20x40 Colorado Silica Sand Stainless Steel Centralizer
					SAND, SP, brown damp, loose, no layering, medium-loose (fill).	SP		
	5.0			7-7-8 (15)	SILT CLAY/CLAYEY SILT, ML/CL, brown w/red mottling, damp, dense. 5% fine sand.	ML/CL		
	7.5			3-4-4 (8)	SAND W/SILT, SP, brown, wet, medium. 25% silt.			
10.0				2-3-4 (7)	SAND W/SILT, SP, as above; finer, closer to SP-ML.			2" Diameter, Schedule 40 Flush-threaded PVC Casing 6" Diameter Locking Mild Steel Protective Casing w/3 Bullards 2" Diameter Schedule 40 Flush-threaded PVC Screen 2" Diameter Schedule 40 PVC Silt Trap w/Secured Bottom Plug
	10.0			2-2-2 (4)	SAND W/SILT, SP, brown to gray, variable silt layering soft to medium gray.	SP/ML		
	12.5			1-2-3 (5)	Same as above.			
	15.0			2-2-2 (4)	Same as above. Last 6"=ML.			
20.0	17.5			1-2-3 (5)	Same as above; 1st 6" ML.	ML		2" Diameter Schedule 40 Flush-threaded PVC Screen 2" Diameter Schedule 40 PVC Silt Trap w/Secured Bottom Plug
	20.0			2-4-3 (7)		SP/ML		
	22.5							
25.0								



PROJECT NUMBER OPE39293.B1.01	WELL NUMBER MW-12
SHEET 1 OF 1	
MONITORING WELL GEOLOGIC AND CONSTRUCTION LOG	

PROJECT RMC Troutdale LOCATION SW Field
 MEASURING POINT ELEV (NGVD) 22.53 DRILLING CONTRACTOR GeoTech Exploration
 DRILLING METHOD AND EQUIPMENT 6 3/4" ID HSA
 WATER LEVEL ELEV/DATE _____ START 8/4/94 FINISH _____ LOGGER Phil Brown

DEPTH BELOW SURFACE (FT)	SAMPLE			STANDARD PENETRATION TEST RESULTS 6" - 6" - 6" (N)	SOIL DESCRIPTION SOIL NAME, USCS GROUP SYMBOL, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY	USCS DESCRIPTION	WELL COMPLETION DIAGRAM
	INTERVAL	TYPE AND NUMBER	RECOVERY FEET				
5.0	2.5				LOAMY SILT W/GRAVEL, ML, dry, lt. gray/brown, firm. <5% gravel. Angular basalt to 3/4" diameter.		<p> Locking Cap Concrete Pad Volclay 3/4" Chips 2" Diameter, Schedule 40 Flush-threaded PVC Casing 6" Diameter Locking Mild Steel Protective Casing w/ 3 Bullards 2" Diameter Schedule 40 Flush-threaded PVC Screen 2" Diameter Schedule 40 PVC Silt Trap w/ Secured Bottom Plug Backfilled to 23' with 3/4" Volclay Bentonite Chips </p>
					SILT, ML, dk. gray to lt. gray/brown, dry to damp, firm. Some red staining, roots and organic debris. 5% very fine sand.		
	5.0			4-7-9 (16)	Top 6": SAND, SP, fine to medium, lt. gray, moist, loose. Bottom 6": SILT, ML, gray, v. fine, wet, firm.	SP	
					SILT, ML, gray, wet, soft, some root debris, 10-20% clay.		
10.0	7.5			6-6-3 (9)			
					SILT, ML, gray, wet, soft, some root debris, 10-20% clay.		
	10.0			1-2-1 (3)		ML	
					SILT W/SAND, ML, gray, wet, soft. 20% v. fine black sand.		
15.0	12.5			1-2-1 (3)			
					SILT, ML, as above. 20-25% clay, firmer.		
	15.0			1-1-2 (3)			
					SAND W/SILT, SP, dk. gray, wet, soft to medium, v. fine sand, 30% silt (coarser).		
20.0	17.5			0-1-2 (3)		SP	
					1' same as above. Bottom 6": SAND, SP, medium to coarse, dk. gray, wet, soft, interlayered w/silt.		
	20.0			1-2-2 (4)			
					SILT, ML, dk. gray, wet, firm, 15% v. fine sand, slightly plastic at base.		
25.0	22.5			1-1-2 (3)		ML	
					CLAYEY SILT, ML/CL, gray w/lt. green mottling, wet, soft to medium, much root debris and vegetation.		
	25.0			1-3-2 (5)		ML/CL	
					1' same as above. Bottom 6": SAND W/SILT, SP, dk. gray, wet, soft, medium to fine.	SP	

Appendix E
RMC Production Well and Sampled
Offsite Well Geologic and Well Drillers' Logs

STATE ENGINEER
Salem, Oregon

MULT
001308

Well Record

STATE WELL NO. 1N/3-23E(1)
COUNTY Multnomah
APPLICATION NO. GR-462

OWNER: Reynolds Metals Co.

MAILING ADDRESS: Sundial Rd.


LOCATION OF WELL: Owner's No. 1

CITY AND STATE: Troutdale, Oregon

SE 1/4 NW 1/4 Sec. 23 T. 1 N. R. 3 E. W.M.

Bearing and distance from section or subdivision

corner N. 37°09'W. 2732' from SE cor. of sec. 23



Altitude at well 26'

TYPE OF WELL: Drilled Date Constructed May 1942

Depth drilled 282' Depth cased 282'

Section 23

CASING RECORD:

12 inch

FINISH:

AQUIFERS:

WATER LEVEL:

85 feet

PUMPING EQUIPMENT: Type Pamona 7 stage turbine H.P. 50
Capacity 735 G.P.M.

WELL TESTS:

Drawdown ft. after hours G.P.M.

Drawdown ft. after hours G.P.M.

USE OF WATER Industrial Temp. °F. 19

SOURCE OF INFORMATION GR-445

DRILLER or DIGGER

ADDITIONAL DATA:

Log X Water Level Measurements Chemical Analysis Aquifer Test

REMARKS:

State Well No. 1N/3-2360
County Mult.
Application No. GR-462

Owner: Reynolds Metals Co. Owner's No. #1

[illegible]

STATE ENGINEER
Salem, Oregon

MULT Well Record

STATE WELL NO. 1N/3-23G(1)
COUNTY Multnomah
APPLICATION NO. GR-1162

001322

OWNER: Reynolds Metals Co.


MAILING
ADDRESS: Sundial Rd.

LOCATION OF WELL: Owner's No. 2

CITY AND
STATE: Troutdale, Oregon

SW 1/4 NE 1/4 Sec. 23 T. 1 N. 3 E. W.M.

Bearing and distance from section or subdivision
corner N. 3749', W. 1950' from SE cor. of sec. 23



Altitude at well 26'

TYPE OF WELL: Drilled Date Constructed 2/23/42

Depth drilled 268' Depth cased 268'

Section 23

CASING RECORD:
10 inch

FINISH:

AQUIFERS:

WATER LEVEL:
78 feet

PUMPING EQUIPMENT: Type Pamona, 7 stage turbine H.P. 40
Capacity 530 G.P.M.

WELL TESTS:
Drawdown 22 ft. after 530 G.P.M.
Drawdown ft. after hours G.P.M.

USE OF WATER Industrial Temp. °F. 19

SOURCE OF INFORMATION GR-1145

DRILLER or DIGGER

ADDITIONAL DATA:

Log X Water Level Measurements Chemical Analysis Aquifer Test

REMARKS:

State Well No. IN/S-2760
County MI 17
Application No. GR-462

Owner: Reynolds ^{Metals} Metals Co. Owner's No. #2

[illegible]

STATE ENGINEER
Salem, Oregon

MULT Well Record

001323

STATE WELL NO. 1N/3-23G(2)
COUNTY Multnomah
APPLICATION NO. GR-462

OWNER: Reynolds Metals Co.

MAILING ADDRESS: Sundial Rd.


LOCATION OF WELL: Owner's No. 3

CITY AND STATE: Troutdale, Oregon

SW 1/4 NE 1/4 Sec. 23 T. 1 N. 3 E. W.M.

Bearing and distance from section or subdivision

corner 367 1/2' N. & 153 1/2' W. from SE cor. of sec. 23



Section 23

Altitude at well 28.5'

TYPE OF WELL: Drilled Date Constructed June '42

Depth drilled 281' Depth cased 281'

CASING RECORD:

12 inch

FINISH:

AQUIFERS:

WATER LEVEL:

72 feet

PUMPING EQUIPMENT: Type Pamona, 4 stage turbine H.P. 40
Capacity 750 G.P.M.

WELL TESTS:

Drawdown 13 ft. after 600 hours G.P.M.

Drawdown ft. after hours G.P.M.

USE OF WATER Industrial Temp. °F. 19

SOURCE OF INFORMATION GR-445

DRILLER or DIGGER

ADDITIONAL DATA:

Log X Water Level Measurements Chemical Analysis Aquifer Test

REMARKS:

STATE ENGINEER
Salem, Oregon

State Well No. 1143-2360
County Mult.
Application No. GR-462

Well Log

Owner: Reynolds ^{Metals} Metals Co. Owner's No. #3

Driller: _____ Date Drilled June '42[illegible]

STATE ENGINEER
Salem, Oregon

MULT Well Record

STATE WELL NO. 1N/3-23H(1)
COUNTY Multnomah
APPLICATION NO. GR-462

001328

OWNER: Reynolds Metals Co.

MAILING ADDRESS: Sundial Rd.


LOCATION OF WELL: Owner's No. 4

CITY AND STATE: Troutdale, Oregon

SE 1/4 NE 1/4 Sec. 23 T. 1 N. R. 3 E. W.M.

Bearing and distance from section or subdivision

corner 3540' N. & 967' W. from SE cor. sec. 23



Altitude at well 28.5'

TYPE OF WELL: Drilled Date Constructed 8/3/42

Depth drilled 190' Depth cased 190'

Section 23

CASING RECORD:
12 inch

FINISH:

AQUIFERS:

WATER LEVEL:
53 feet

PUMPING EQUIPMENT: Type F. M., 8 stage turbine H.P. 75
Capacity 980 G.P.M.

WELL TESTS:
Drawdown 22 ft. after 10.0 hours G.P.M.
Drawdown ft. after hours G.P.M.

USE OF WATER Industrial Temp. °F. 19

SOURCE OF INFORMATION GR-445

DRILLER or DIGGER

ADDITIONAL DATA:

Log X Water Level Measurements Chemical Analysis Aquifer Test

REMARKS:

State Well No. 1N/3-20 HP
County Mult.
Application No. GR-462

Owner: Reynolds Metals Co. Owner's No. # 4
Driller: _____ Date Drilled Aug. 3, '42

[illegible]

STATE ENGINEER
Salem, Oregon

MULT Well Record

STATE WELL NO. LN/3-23H(2)
COUNTY Multnomah
APPLICATION NO. GR-462

OWNER: Reynolds Metals Co. 001331

MAILING
ADDRESS: Sundial Rd.


LOCATION OF WELL: Owner's No. 5

CITY AND
STATE: Troutdale, Oregon

SE $\frac{1}{4}$ NE $\frac{1}{4}$ Sec. 23 T. 1 N. 3 E. W.

Bearing and distance from section or subdivision

corner 3740' N. & 1015' W. from SE cor. sec. 23



Altitude at well 28.5'

TYPE OF WELL: Drilled Date Constructed Apr. 1943

Depth drilled 330' Depth cased 277'

Section 23

CASING RECORD:
16 inch

FINISH:

AQUIFERS:

WATER LEVEL:
60 feet

PUMPING EQUIPMENT: Type Pamona, 7 stage turbine H.P. 150
Capacity 1500 G.P.M.

WELL TESTS:

Drawdown 20 ft. after _____ hours 1900 G.P.M.

Drawdown _____ ft. after _____ hours _____ G.P.M.

USE OF WATER Industrial Temp. _____ °F. _____, 19____

SOURCE OF INFORMATION GR-445

DRILLER or DIGGER _____

ADDITIONAL DATA:

Log X Water Level Measurements _____ Chemical Analysis _____ Aquifer Test _____

REMARKS:

Application No. GR-462

Owner's No. ~~4~~ 5

Date Drilled April 143

[illegible]

STATE ENGINEER
Salem, Oregon

MULT Well Record
001311

STATE WELL NO. 1N/3-23H(3)
COUNTY Multnomah
APPLICATION NO. GR-462

OWNER: Reynolds Metals Co.

MAILING ADDRESS: Sundial Rd.


LOCATION OF WELL: Owner's No. 6

CITY AND STATE: Troutdale, Oregon

SE 1/4 NE 1/4 Sec. 23 T. 1 N. EX R. 3 E. W.M.

Bearing and distance from section or subdivision

corner 3559' N. & 1157' W. from SE cor sec. 23



Altitude at well 28.5'

TYPE OF WELL: Drilled Date Constructed 2/27/48

Depth drilled 279' Depth cased 279'

Section 23

CASING RECORD:

18 inch from 0 to 193 feet

12 inch from 180 to 279 feet

FINISH:

AQUIFERS:

WATER LEVEL:

55 feet

PUMPING EQUIPMENT: Type F. M., 5 stage turbine H.P. 60
Capacity 1000 G.P.M.

WELL TESTS:

Drawdown ft. after hours G.P.M.

Drawdown ft. after hours G.P.M.

USE OF WATER Industrial Temp. °F., 19

SOURCE OF INFORMATION GR-445

DRILLER or DIGGER

ADDITIONAL DATA:

Log ☒ Water Level Measurements Chemical Analysis Aquifer Test

REMARKS:

State Well No. 1113-204(3)
County MIT
Application No. GR-485

Owner: Reynolds ^(metals) Metals Co. Owner's No. #6

Driller: _____ Date Drilled *Feb. 27, '48*

[illegible]

STATE ENGINEER
Salem, Oregon

MULT Well Record
061329

STATE WELL NO. 1N/3-23H(4)
COUNTY Multnomah
APPLICATION NO. GR-462

OWNER: Reynolds Metals Co. MAILING ADDRESS: Sundial Rd.
CITY AND STATE: Troutdale, Oregon


LOCATION OF WELL: Owner's No. 7
SE 1/4 NE 1/4 Sec. 23 T. 1 N. R. 3 E. W.M.

Bearing and distance from section or subdivision
corner 3404' N. & 947' W. from SE cor. sec. 23

Altitude at well 28.5'

TYPE OF WELL: Drilled Date Constructed 5/12/48

Depth drilled 254' Depth cased 254'



Section 23

CASING RECORD:

18 inch from 0 to 203 feet
12 inch from 190 to 254 feet

FINISH:

AQUIFERS:

WATER LEVEL:
70 feet

PUMPING EQUIPMENT: Type F. M., 5 stage turbine H.P. 60
Capacity 1000 G.P.M.

WELL TESTS:

Drawdown ft. after hours G.P.M.

Drawdown ft. after hours G.P.M.

USE OF WATER Industrial Temp. °F. 19
SOURCE OF INFORMATION GR-445

DRILLER or DIGGER

ADDITIONAL DATA:

Log X Water Level Measurements Chemical Analysis Aquifer Test

REMARKS:

State-Wall No. *W-22*
County *Multi*
Application No. *CR 16*

Owner: Reynolds Metals Co.

Owner's No. 72-07

Driller:

Date Drilled May 12, 1955

[illegible]

STATE ENGINEER
Salem, Oregon

MULT Well Record

STATE WELL NO. 1N/3-23H(5)
COUNTY Multnomah
APPLICATION NO. GR-462

001330

OWNER: Reynolds Metals Co.

MAILING ADDRESS: Sundial Rd.


LOCATION OF WELL: Owner's No. 8

CITY AND STATE: Troutdale, Oregon

SE $\frac{1}{4}$ NE $\frac{1}{4}$ Sec. 23 T. 1 N. 3 E. W., W.M.

Bearing and distance from section or subdivision

corner 3581' N. & 804' W. from SE cor. sec. 23



Altitude at well 28.5'

TYPE OF WELL: Drilled Date Constructed 9/21/48

Depth drilled 248' Depth cased 248'

Section 23

CASING RECORD:

18 inch from 0 to 160 feet

12 inch from 152 to 248 feet

FINISH:

AQUIFERS:

WATER LEVEL:

60 feet

PUMPING EQUIPMENT: Type F. M., 5 stage turbine H.P. 60
Capacity 1000 G.P.M.

WELL TESTS:

Drawdown _____ ft. after _____ hours _____ G.P.M.

Drawdown _____ ft. after _____ hours _____ G.P.M.

USE OF WATER Industrial Temp. _____ °F. _____, 19

SOURCE OF INFORMATION GR-445

DRILLER or DIGGER _____

ADDITIONAL DATA:

Log X Water Level Measurements _____ Chemical Analysis _____ Aquifer Test _____

REMARKS:

State Well No. *1N/3-23H*
County *Mult.*
Application No. *68-462*

Owner: Reynolds Metals Co.

Owner's No. 78

Driller:

Date Drilled Sept. 21, '48

[illegible]

STATE ENGINEER
Salem, Oregon

MULT Well Record
001324

STATE WELL NO. 1N/3-23G(3)
COUNTY Multnomah
APPLICATION NO. GR- 462

OWNER: Reynolds Metals Co.

MAILING
ADDRESS: Sundial Rd.


LOCATION OF WELL: Owner's No. 9

CITY AND
STATE: Troutdale, Oregon

SW 1/4 NE 1/4 Sec. 23 T. 1 N. R. 3 E. W.M.

Bearing and distance from section or subdivision

corner 3459' N. & 1744' W. from SE cor. sec. 23



Altitude at well 28.5'

TYPE OF WELL: Drilled Date Constructed 7/23/49

Depth drilled 295' Depth cased 295'

Section 23

CASING RECORD:

20 inch from 0 to 136 1/2 feet

12 inch from 128 to 295 feet

FINISH:

AQUIFERS:

WATER LEVEL:

105 feet

PUMPING EQUIPMENT: Type Peerless, 2 stage turbine H.P. 40
Capacity 1200 G.P.M.

WELL TESTS:

Drawdown ft. after hours G.P.M.

Drawdown ft. after hours G.P.M.

USE OF WATER Industrial Temp. °F. 19

SOURCE OF INFORMATION GR- 445

DRILLER or DIGGER

ADDITIONAL DATA:

Log X Water Level Measurements Chemical Analysis Aquifer Test

REMARKS:

After development of well at 295' silt condition could not be remedied.
Well was back filled to 180' before pump test.

State Wall No. 1113-236
County Molt
Application No. 6 P 13 2

Owner: Reynolds Metals Co.

Owner's No. 22-27

Driller:

Date Drilled July 23 '49[illegible]

STATE ENGINEER
Salem, Oregon

MULT Well Record
001320

STATE WELL NO. 1N/3-23G(4)
COUNTY Multnomah
APPLICATION NO. GR-462

OWNER: Reynolds Metals Co.

MAILING ADDRESS: Sundial Rd.


LOCATION OF WELL: Owner's No. 10

CITY AND STATE: Troutdale, Oregon

SW $\frac{1}{4}$ NE $\frac{1}{4}$ Sec. 23 T. 1 N. 3 R. 3 E. W.M.

Bearing and distance from section or subdivision

corner 3198' N. & 1754' W. from SE cor. sec. 23



Altitude at well 28.5'

TYPE OF WELL: Drilled Date Constructed 8/17/49

Depth drilled 625' Depth cased 625'

Section 23

CASING RECORD:

20 inch from 0 to 140 feet

12 inch from 0 to 625 feet

FINISH:

Perforated from 144 to 185 feet - shut off when well was redrilled to 625'

AQUIFERS:

WATER LEVEL:

78 feet (1955)

PUMPING EQUIPMENT: Type Peerless, 3 stage turbine H.P. 60
Capacity 1180 G.P.M.

WELL TESTS:

Drawdown 40 ft. after _____ hours 900 G.P.M.

Drawdown 48 ft. after _____ hours 1100 G.P.M.

USE OF WATER Industrial Temp. _____ °F. _____, 19

SOURCE OF INFORMATION GR-445

DRILLER or DIGGER _____

ADDITIONAL DATA:

Log X Water Level Measurements _____ Chemical Analysis _____ Aquifer Test _____

REMARKS:

STATE ENGINEER
Salem, Oregon

State Well No. IN/2-2266
County Mult.
Application No. GR-962

Well Log

Owner: Reynolds Metals Co. Owner's No. #10

Driller: — Date Drilled Aug. 17, 49

CHARACTER OF MATERIAL	(Feet below 'and surface)		Thickness (feet)
	From	To	
Dredge sand from river	0	6	6
Brown sand	6	16	10
Blue clay	16	19	3
Brown sand	19	42	23
Gray sandy clay	42	62	20
Cemented gravel, gray binder	62	81	19
Gray silt & sand-water bearing	81	144	63
Gray sand-water bearing	144	165	21
Cemented gravel	165	168	3
Gray sand-water bearing	168	186	18
Gray silt	186	190	4
Blue sandy silt	190	206	16
Hard packed sand	206	227	21
Sandy silt	227	238	11
Coarse sand & gravel	238	244	6
Blue clay	244	252	8
Hard packed sand-some gravel	252	337	85
Sandy silt & gravel	337	342	5
Hard packed sand	342	372	30
Sandy clay	372	377	5
Hard packed sand & gravel	377	385	8
Sandy clay	385	392	7

State Well No. 14-3-236
County Walt.
Application No. GP-40

Owner: Reynolds ^{Metals} ~~Medals~~ Co. Owner's No. #10

[illegible]

STATE ENGINEER
Salem, Oregon

MULT Well Record
001325

STATE WELL NO. 1N/3-23G(5)
COUNTY Multnomah
APPLICATION NO. GR- 462

OWNER: Reynolds Metals Co.

MAILING ADDRESS: Sundial Rd.

LOCATION OF WELL: Owner's No. 11

CITY AND STATE: Trousdale, Oregon

SW $\frac{1}{4}$ NE $\frac{1}{4}$ Sec. 23 T. 1 N. R. 3 E. W.M.

Bearing and distance from section or subdivision


corner 3246' N. & 1474' W. from SE cor. sec. 23

Altitude at well 28.5'

TYPE OF WELL: Drilled Date Constructed 8/17/49

Depth drilled 592' Depth cased 541'

Section 23



CASING RECORD:

20 inch from 0 to 147 feet

12 inch from 0 to 541 feet

FINISH:

Perforated from 147 to 187 feet - shut off when well was redrilled to 592'
(2/16/55)

AQUIFERS:

WATER LEVEL:

45 feet

PUMPING EQUIPMENT: Type Peerless, 3 stage turbine H.P. 60
Capacity 1180 G.P.M.

WELL TESTS:

Drawdown 77 ft. after _____ hours 1000 G.P.M.

Drawdown 93 ft. after _____ hours 1200 G.P.M.

USE OF WATER Industrial Temp. _____ °F. _____, 19.

SOURCE OF INFORMATION GR- 445

DRILLER or DIGGER _____

ADDITIONAL DATA:

Log X Water Level Measurements _____ Chemical Analysis _____ Aquifer Test _____

REMARKS:

STATE ENGINEER
Salem, Oregon

State Well No. 11/3-236
County Multnomah
Application No. CR-464

Well Log

Owner: Reynolds ^{metals} Metals Co. Owner's No. # 11

Driller: Date Drilled Aug. 17, 1949

CHARACTER OF MATERIAL	(Feet below land surface)		Thickness (feet)
	From	To	
Dredge sand from river	0	8	8
Sandy clay	8	14	6
Brown clay	14	32	18
Brown silt	32	68	36
Brown silt & very fine gray sand	68	143	75
Hard brown silty clay	143	152	9
Gray sand & small gravel water bearing	152	167	15
Gray sand Cemented gravel	167	171	4
Gray sand-water bearing	171	178	7
Cemented gravel	178	183	5
Gray silt	183	188	5
Blue "	188	202	14
Gravel sandy clay binder	202	207	5
Sandy clay	207	219	12
Hard packed sand	219	232	13
Sandy silt	232	239	7
Hard packed sand - small amount gravel	239	274	35
Sandy silt.	274	286	12
Hard packed sand-some gravel	286	307	21
Silty sand-some gravel	307	362	55
Black shale	362	365	3

STATE ENGINEER

Salem, Oregon

State Well No. W-326

11

Application No. *CP-322*

Well Log

Owner: Reynolds Metals Co.

Owner's No. 9571

Driller:

Date Drilled

[illegible]

STATE ENGINEER
Salem, Oregon

MULT Well Record
001319

STATE WELL NO. IN/3-23K
COUNTY MULTNOMAH
APPLICATION NO. 1014

OWNER: Reynolds Metals Co.

MAILING
ADDRESS: _____

LOCATION OF WELL: Owner's No. #12

CITY AND
STATE: _____

1/4 1/4 Sec. T. N. E.
S., R. W., W.M.

Bearing and distance from section or subdivision

corner _____

Altitude at well 28

TYPE OF WELL: Drilled Date Constructed _____

Depth drilled 615 Depth cased 590

Section _____

CASING RECORD:

20-12 inch

FINISH:

AQUIFERS: Sand, Gravel, Troutdale Formation, from 156 to 187
Sand, Troutdale Formation, from 230 to 234
Sand, Gravel, Troutdale Formation, from 507 to 577

WATER LEVEL: 23 feet below land surface, September, 1949

PUMPING EQUIPMENT: Type Turbine H.P. _____
Capacity 1,200 G.P.M.

WELL TESTS:

Drawdown _____ ft. after _____ hours _____ G.P.M.

Drawdown _____ ft. after _____ hours _____ G.P.M.

USE OF WATER Industrial Temp. _____ °F. _____, 19____

SOURCE OF INFORMATION USGS

DRILLER or DIGGER _____

ADDITIONAL DATA:

Log X Water Level Measurements _____ Chemical Analysis X Aquifer Test _____

REMARKS:

Perforated 512-518, 522-538, 544-555, and 563-578 feet.

STATE ENGINEER
Salem, Oregon

State Well No. AIN/3-23K1 ^{db}

County MULTNOMAH

Application No. _____

Well Log

Owner: Reynolds Metals Co.

Owner's No. PW12

Driller: R. J. Strasser Drilling Co.

Date Drilled 1949 and 1954

CHARACTER OF MATERIAL	(Feet below land surface)		Thickness (feet)
	From	To	
<u>Artificial fill and younger alluvium:</u>			
Fill and soil	0	24	24
<u>Younger alluvium:</u>			
Silt and clay	24	42	18
Sand, brown	42	54	12
Sand, fine, gray	54	143	89
Sand, coarse, gray, some clay	143	156	13
<u>Troutdale Formation:</u>			
Sand, coarse, some gravel, water-bearing	156	187	31
Sand and clay, gray	187	230	43
Sand, in part water-bearing	230	234	4
Sand and clay, blue	234	265	31
Shale, blue	265	281	16
Clay and sand	281	305	24
Sand, fine with scattered gravel	305	352	47
Sand and clay, gray	352	361	9
Shale and sand, black	361	384	23
Clay, brown	384	396	12
Sandstone	396	409	13
Sand and clay, with some gravel	409	420	11
Sand, hard-packed, with some clay	420	446	26
Clay and gravel	446	474	28
Clay, sandy	474	487	13
Sandstone	487	507	20

Driller: _____ Date Drilled _____

STATE ENGINEER
Salem, Oregon

MULT Well Record
001326

STATE WELL NO. 1N/3-23G(6)
COUNTY Multnomah
APPLICATION NO. GR-462

OWNER: Reynolds Metals Co.

MAILING ADDRESS: Sundial Rd.


LOCATION OF WELL: Owner's No. 12

CITY AND STATE: Troutdale, Oregon

SW 1/4 NE 1/4 Sec. 23 T. 1 N. R. 3 E. W.M.

Bearing and distance from section or subdivision

corner 2944' N. & 1719' W. from SE cor. sec. 23



Section 23

Altitude at well 28.5'

TYPE OF WELL: Drilled Date Constructed 9/13/49

Depth drilled 616' Depth cased 590'

CASING RECORD:

20 inch from 0 to 140 feet

16 inch from 80 to 392 feet

12 inch from 0 to 590 feet

FINISH:

Perforated from 147 to 187 feet - shut off when well was redrilled on 3/18/54 to 616 feet. Hole backfilled with gravel from 616 to 584 feet to seal off fine sand strata from 598 to 607 feet.

AQUIFERS:

WATER LEVEL:

39 feet

PUMPING EQUIPMENT: Type Peerless, 3 stage turbine H.P. 60
Capacity 1180 G.P.M.

WELL TESTS:

Drawdown 71 ft. after 1000 hours G.P.M.

Drawdown 80 ft. after 1200 hours G.P.M.

USE OF WATER Industrial Temp. °F. 19

SOURCE OF INFORMATION GR-445

DRILLER or DIGGER

ADDITIONAL DATA:

Log X Water Level Measurements Chemical Analysis Aquifer Test

REMARKS:

STATE ENGINEER
Salem, Oregon

State Well No. 412-25
County Clatsop
Application No. GR-462

Well Log

Owner: Reynolds ^{metals} Metals Co. Owner's No. 3712

Driller: Date Drilled Sept. 13, 49

CHARACTER OF MATERIAL	(Feet below land surface)		Thickness (feet)
	From	To	
Dredge sand from pier	0	5	5
Fine brown silt	5	19	14
Blue silt	19	26	7
Brown clay	26	37	11
Hard blue clay	37	42	5
Brown sand	42	54	12
Fine gray sand	54	143	89
Coarse gray sand, some binder	143	156	13
Coarse sand & small gravel - water bearing	156	187	31
Grey sand with gray clay binder	187	230	43
Sand - some water	230	234	4
Sand & blue clay	234	246	12
Fine gray sand	246	259	13
Blue clay & sand	259	265	6
Heavy blue shale	265	281	16
Blue clay & sand	281	305	24
Fine sand - scattered gravel	305	352	47
Gray sand & clay	352	361	9
Black shale & sand	361	384	23
Brown clay	384	396	12
Sand stone	396	409	13

State Well No. 1413200
County Mult.
Application No. CR 2

Owner: Reynolds ^{metals} Metals Co Owner's No. 412

Driller: _____ Date Drilled _____

[illegible]

STATE ENGINEER
Salem, Oregon

MULT Well Record
001327

STATE WELL NO. 1N/3-23G(7)
COUNTY Multnomah
APPLICATION NO. GR-162

OWNER: Reynolds Metals Co.

MAILING
ADDRESS: Sundial Rd.


LOCATION OF WELL: Owner's No. 13

CITY AND
STATE: Troutdale, Oregon

SW $\frac{1}{4}$ NE $\frac{1}{4}$ Sec. 23 T. 1 N. R. 3 E. W.M.

Bearing and distance from section or subdivision

corner 2839' N. & 1534' W. from SE cor. sec. 23



Altitude at well 28.5'

TYPE OF WELL: Drilled Date Constructed 9/9/47

Depth drilled 195' Depth cased 195'

Section 23

CASING RECORD:

20 inch from 0 to 140 feet

12 inch from 127 to 195 feet

FINISH:

AQUIFERS:

WATER LEVEL:

105 feet

PUMPING EQUIPMENT: Type Peerless turbine H.P. 40
Capacity 1200 G.P.M.

WELL TESTS:

Drawdown _____ ft. after _____ hours _____ G.P.M.

Drawdown _____ ft. after _____ hours _____ G.P.M.

USE OF WATER Industrial Temp. _____ °F. _____, 19____

SOURCE OF INFORMATION GR-445

DRILLER or DIGGER _____

ADDITIONAL DATA:

Log X Water Level Measurements _____ Chemical Analysis _____ Aquifer Test _____

REMARKS:

State Well No. 1N/3-2-3667
County Mult
Application No. GR-442

Owner: Reynolds ^{Metals} ~~Metals~~ Co. Owner's No. #13
Driller: — Date Drilled Sept. 9, '47

[illegible]

STATE ENGINEER
Salem, Oregon

MULT

Well Record

STATE WELL NO. 1N/3-23G(8)
COUNTY Multnomah
APPLICATION NO. GR-462

OWNER: Reynolds Metals Co.

MAILING
ADDRESS: Sundial Rd.

LOCATION OF WELL: Owner's No. 14

CITY AND
STATE: Troutdale, Oregon

SW $\frac{1}{4}$ NE $\frac{1}{4}$ Sec. 23 T. 1 N. 3 E. W., W.M.

Bearing and distance from section or subdivision

corner 2839' N. & 1334' W. from SE cor. sec. 23

Altitude at well 28.5'

TYPE OF WELL: Drilled Date Constructed 9/29/49

Depth drilled 644' Depth cased 644'

Section 23

CASING RECORD:

20 inch from 0 to 144 feet

12 inch from 0 to 644 feet

FINISH:

Perforated from 150 to 189 feet - shut off when well was redrilled to 644 feet.
(7/20/55)

AQUIFERS:

WATER LEVEL:

49 feet

PUMPING EQUIPMENT: Type Peerless turbine H.P. 60
Capacity 1180 G.P.M.

WELL TESTS:

Drawdown 100 ft. after hours 1050 G.P.M.

Drawdown ft. after hours G.P.M.

USE OF WATER Industrial Temp. °F. 19

SOURCE OF INFORMATION GR-445

DRILLER or DIGGER

ADDITIONAL DATA:

Log X Water Level Measurements Chemical Analysis Aquifer Test

REMARKS:

Well Log

Owner: Reynolds Metals Co. Owner's No. # 19
Driller: ✓ Date Drilled Sept. 29, 1929

CHARACTER OF MATERIAL	(Feet below land surface)		Thickness (feet)
	From	To	
Dredge sand from river	0	5	5
Brown silt	5	16	11
Brown clay	16	24	8
Runny blue silt	24	35	11
Sticky blue clay	35	42	7
Fine gray sand	42	96	54
Cemented sand & gravel, hard	96	118	22
Hard blue clay	118	124	6
Fine gray sand-gray clay binder	124	146	22
Coarse black sand	146	152	6
Coarse sand, fine gravel - water bearing formation	152	184	32
Fine sand-gray clay binder	184	191	7
Gray silt	191	194	3
Sandy silt	194	215	21
Packed sand	215	224	9
Silt	224	233	9
Sand & clay	233	239	6
Cemented gravel	239	247	8
Sand & gravel w/ some clay binder	247	287	40
Packed sand	287	307	20
Gravel & sandy clay	307	332	25

State Well No. 14/3-2366
County McIntosh
Application No. GP-462

Owner: Reynolds Metals Co. Owner's No. # 14

[illegible]

STATE ENGINEER
Salem, Oregon

MULT Well Record
001312

STATE WELL NO. 1N/3-23H(6)
COUNTY Multnomah
APPLICATION NO. GR-462

OWNER: Reynolds Metals Co.

MAILING ADDRESS: Sundial Rd.

LOCATION OF WELL: Owner's No. 15

CITY AND STATE: Troutdale, Oregon

SE 1/4 NE 1/4 Sec. 23 T. 1 N. R. 3 E. W.M.

Bearing and distance from section or subdivision
corner 2964' N. & 654' W. from SE cor. sec. 23

Altitude at well 28.5'

TYPE OF WELL: Drilled Date Constructed 4/30/53

Depth drilled 275' Depth cased 275'

Section 23

CASING RECORD:

20 inch from 0 to 242 feet
12 inch from 225 to 275 feet

FINISH:

AQUIFERS:

WATER LEVEL:

41 feet

PUMPING EQUIPMENT: Type F. M., Pamona turbine H.P. 75
Capacity 1200 G.P.M.

WELL TESTS:

Drawdown 51 ft. after 1350 hours G.P.M.

Drawdown ft. after hours G.P.M.

USE OF WATER Industrial Temp. °F. 19

SOURCE OF INFORMATION GR-445

DRILLER or DIGGER

ADDITIONAL DATA:

Log X Water Level Measurements Chemical Analysis Aquifer Test

REMARKS:

State Well No. 10/3-2314
County Mult.
Application No. 67-462

Owner: Reynolds Metals Co. Owner's No. #15

[illegible]

NOTICE TO WATER WELL CONTRACTOR:

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310

within 30 days from the date
of well completion.

NOV 29 1967

WATER WELL REPORT

MULT

STATE OF OREGON

ENGINEER

(Please type or print)

OREGON

(Do not write above this line)

001313

State Well No.

1N/3-23

State Permit No.

G-3453

G-3761

(1) OWNER:

Name REYNOLDS METALS Co
Address TROUTDALE, ORE. NO. 16

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☒ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒
12" Diam. from 0 ft. to 279 ft. Gage 330
16" Diam. from 0 ft. to 121 ft. Gage 315
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(5) SCREENS:

Well screen installed? ☒ Yes ☐ No

Manufacturer's Name JOHNSON
Type STAINLESS STEEL Model No. 15 SLOT
Diam. 12" Slot size 15" Set from 151 ft. to 192 ft.
Diam. 12" Slot size 15" Set from 256 ft. to 269 ft.

(8) WATER LEVEL: Completed well.

Static level 16 ft. below land surface Date 10/27/67

Artesian pressure lbs. per square inch Date

(9) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? STRASSER
545 gal./min. with 11 ft. drawdown after 1 hrs.
870 " 16 " 1 "
1080 " 21 " 12 "

Ball test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m. Date

Temperature of water 54° Was a chemical analysis made? ☐ Yes ☒ No

10) CONSTRUCTION:

Well seal—Material used CEMENT GROUT
Depth of seal 56 ft.
Diameter of well bore to bottom of seal 20 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth
drive shoe used? ☒ Yes ☐ No
Do any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.

(11) LOCATION OF WELL:

County MULT. Driller's well number 4260
SE 1/4 SE 1/4 Section 23 T. 1N R. 3E W.M.
Bearing and distance from section or subdivision corner

(12) WELL LOG:

Diameter of well below casing 279

Depth drilled 303 ft. Depth of completed well 279 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
TOP SOIL	0	2	
GREY SAND	2	6	
BROWN SAND	6	13	
BLUE SILT	13	17	
GREY SILT	17	52	
MUDDY SAND	52	79	
PACKED SAND	79	102	
GREY SAND SOME GRAVEL	102	147	
WATER BEARING SAND	147	191	
(SOME GRAVEL)			
FINE SAND AND SILT	191	253	
SAND, SILT AND GRAVEL	253	269	
SILTY CLAY	269	278	
SAND AND SILT	278	280	
SAND, SILT, SOME GRAVEL	280	303	

Work started SEPT 5 1967 Completed NOV 2 1967

Date well drilling machine moved off of well NOV 3 1967

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Sam DeJura Date Nov 28 1967
(Drilling Machine Operator)

Drilling Machine Operator's License No. 54

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME R. STRASSER DRILLING Co
(Person, firm or corporation) (Type or print)

Address 8110 SE SUNSET LANE, PORTLAND, ORE.

[Signed] Robert L. Strasser
(Water Well Contractor)

Contractor's License No. 10 Date NOV 28 1967

(USE ADDITIONAL SHEETS IF NECESSARY)

WELL LOG, WELL #16

Well Log: Backfilled to 279 ft. Depth drilled 303 ft. Depth
of completed well 279 ft.

<u>Material</u>	<u>From</u>	<u>To</u>
Top Soil	0	2
Grey Sand	2	6
Brown Sand	6	13
Blue Silt	13	17
Grey Silt	17	52
Muddy Sand	52	79
Packed Sand	79	102
Grey Sand, Some Gravel	102	147
Water Bearing Sand (some gravel)	147	191
Fine Sand and Silt	191	253
Sand, Silt and Gravel	253	269
Silty Clay	269	278
Sand and Silt	278	290
Sand, Silt, Some Gravel	290	303

Work started Sept. 5, 1967. Completed Nov. 2, 1967.
Date well drilling machine moved off of well, Nov. 3, 1967.

Johnson screens, stainless steel, 15 slot. 12" dia. 15 slots set
from 151' to 192'. 12" dia. 15 slots set from 256' to 269'.

JUN 24 1985

M

A-11161

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

MULT

001314

State Well No. 11/3-2500

State Permit No.

(1) OWNER:

Name REYNOLDS METALS CO
Address TROUTDALE, ORE. NO. 17

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☒ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒
20" Diam. from 0 ft. to 6.3 ft. Gage 375
12" Diam. from 0 ft. to 170 ft. Gage 330
11" Diam. from 207 ft. to 221 ft. Gage 250
10" Diam. from 238 ft. to 280 ft. Gage 250
9" Diam. from 300 ft. to 310 ft. Gage 250

PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☒ Yes ☐ No

Manufacturer's Name U.O.P. JOHNSON
Type STAINLESS STEEL Model No. 207
Diam. 12 Slot size 14 Set from 170 ft. to 207 ft.
Diam. 12 Slot size 16 Set from 221 ft. to 238 ft.
Diam. 12 Slot size 16 Set from 280 ft. to 300 ft.

(8) WATER LEVEL: Completed well.

Static level 20 ft. below land surface Date 8/26/69
sian pressure lbs. per square inch Date

(9) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? STRASSER
Yield: 1090 gal./min. with 25 ft. drawdown after 12 hrs.

Ballor test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m. Date

Temperature of water 54° Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION:

Well seal—Material used CEMENT GROUT
Depth of seal 64 ft.

Diameter of well bore to bottom of seal 20 in.

Were any loose strata cemented off? ☐ Yes ☒ No Depth

Was a drive shoe used? ☒ Yes ☐ No

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.

(11) LOCATION OF WELL:

County MULT Driller's well number 5321
NE 1/4 SW 1/4 Section 23 T. 1N R. 3E W.M.
Bearing and distance from section or subdivision corner

(12) WELL LOG:

Diameter of well below casing

Depth drilled 310 ft. Depth of completed well 310 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change
in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
BROWN SAND	0	22	
FINE BLUE AND GREY SAND	22	43	
LIGHT GREY SAND	43	61	
HARD PACKED GREY SAND	61	64	
GREY SAND AND CLAY	64	73	
HARD PACKED GREY SAND	73	94	
BLUE SAND	94	106	
PACKED GREY SAND	106	148	
GREY AND BROWN SAND	148	160	
WATER BEARING SAND	160	168	
WATER BEARING SAND			
AND FINE GRAVEL	168	231	
SAND, SOME GRAVEL	231	240	
SAND, SIFT, SOME GRAVEL	240	280	
WATER BEARING SAND,			
SMALL AMOUNT OF GRAVEL	280	310	

Work started JUNE 24 1969 Completed AUG 29 1969

Date well drilling machine moved off of well SEPT 3 1969

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Shawn Rudman Date 10/1, 1969
(Drilling Machine Operator)

Drilling Machine Operator's License No. 54

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME RJ STRASSER DRILLING CO
(Person, firm or corporation) (Type or print)

Address 8110 SE SUNSET LAKE PORTLAND OR

[Signed] Robert L. Strasser
(Water Well Contractor)

Contractor's License No. 10 Date SEPT 24 1969

WELL LOG, WELL #17

Well Log: Depth drilled 310 ft. Depth of completed well 310 ft.

<u>Material</u>	<u>From</u>	<u>To</u>
Brown Sand	0	22
Fine Blue and Grey Sand	22	43
Light Grey Sand	43	61
Hard Packed Grey Sand	61	64
Grey Sand and Clay	64	73
Hard Packed Grey Sand	73	94
Blue Sand	94	106
Packed Grey Sand	106	148
Grey and Brown Sand	148	160
Water Bearing Sand	160	168
Water Bearing Sand and Fine Gravel	168	231
Sand, Some Gravel	231	240
Sand, Silt, Some Gravel	240	280
Water Bearing Sand, Small amount of Gravel	280	310

Work started June 24, 1969. Completed Aug. 29, 1969. Date
well drilling machine moved off of well, Sept. 3, 1969.

Johnson screens, stainless steel. 12" dia., 14 slots set from 170' to 207'.
12" dia., 16 slots set from 221' to 238'.
12" dia., 16 slots set from 280' to 300'.

JUN 24 1985

A-11162

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310

within 30 days from the date
of well completion.

RECEIVED
JUN 26 1970
STATE ENGINEER
SALEM, OREGON

(Please type or print)

01315

State Well No.

IN/3-23 bd

State Permit No.

(WELL No 18)

(1) OWNER:

Name REYNOLDS METALS COAddress TROUTDALE, ORE

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐
Cable ☒
g ☐

Driven ☐
Jetted ☐
Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☒ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒
12" Diam. from 0 ft. to 146 ft. Gage 330
11" Diam. from 138 ft. to 148 ft. Gage 250
11" Diam. from 184 ft. to 224 ft. Gage 250
11" Diam. from 260 ft. to 270 ft. Gage 250

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations	in.	by	in.
perforations from		ft. to	ft.
perforations from		ft. to	ft.
perforations from		ft. to	ft.
perforations from		ft. to	ft.
perforations from		ft. to	ft.

SCREENS:

Well screen installed? ☒ Yes ☐ NoManufacturer's Name W.D.P. JOHNSONType STAINLESS STEEL Model No.

Diam. 12 Slot size 15 Set from 148 ft. to 189 ft.

Diam. 12 Slot size 15 Set from 229 ft. to 260 ft.

(8) WATER LEVEL: Completed well.

ic level 14 ft. below land surface Date 6/8/70

Artesian pressure lbs. per square inch Date

(9) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? STRASSER

1090 gal./min. with 35 ft. drawdown after 11 hrs.

800 " 26 " 1/2 "

545 " 17 " 1/2 "

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m. Date

Temperature of water 54° Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION:

Well seal—Material used 80% CEMENT GROUTDepth of seal 120 FT AND 20 FT ft.Diameter of well bore to bottom of seal 16 AND 20 in.Were any loose strata cemented off? ☐ Yes ☒ No Deptha drive shoe used? ☒ Yes ☐ Noany strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(11) LOCATION OF WELL:

County MULT Driller's well number 5245SE 1/4 NW 1/4 Section 23 T. 1N R. 3E W.M.

Bearing and distance from section or subdivision corner

(12) WELL LOG:

Diameter of well below casing BACKFILLEDDepth drilled 300 ft. Depth of completed well 270 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
BROWN SAND	0	8	
SAND AND SILT	8	100	
SAND SOME GRAVEL	100	150	
WATER BEARING SAND	150	180	
SAND SOME GRAVEL	180	190	
SAND AND SILT	190	230	
SAND AND GRAVEL	230	260	
PACKED SANDY SILT	260	300	

Work started APR 20 1970 Completed JUNE 11 1970Date well drilling machine moved off of well JUNE 11 1970

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Wm Johnson Date 6/25 1970
(Drilling Machine Operator)

Drilling Machine Operator's License No. 56

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME R.J. STRASSER DRILLING CO
(Person, firm or corporation) (Type or print)

Address 8110 SE SUNSET LANE PORTLAND ORE

[Signed] Robert L. Strasser
(Water Well Contractor)

Contractor's License No. 10 Date JUNE 25 1970

(USE ADDITIONAL SHEETS IF NECESSARY)

WELL LOG, WELL #18

Well Log: Depth drilled 300 ft. Depth of completed well 270 ft.

<u>Material</u>	<u>From</u>	<u>To</u>
Brown Sand	0	8
Sand and Silt	8	100
Sane, Some Gravel	100	150
Water Bearing Sand	150	180
Sand, Some Gravel	180	190
Sand and Silt	190	230
Sand and Gravel	230	260
Packed Sandy Silt	260	300

Work started April 20, 1970. Completed June 11, 1970.
Date well drilling machine moved off of well June 11, 1970.

Johnson Screens, stainless steel. 12" dia. 15 slots set from
148' to 189' and from 229' to 260'.

JUN 24 1985 M

Offsite Wells:
Fairview Farms
Sundial Marine
and
Gresham Sand and Gravel

STATE ENGINEER
Salem, OregonMULT Well Record
001306

GR- 1589

STATE WELL NO. 1N/3-22E
COUNTY Multnomah
APPLICATION NO. GR- 1443

OWNER: (b) (6)

MAILING
ADDRESS:

(b) (6)

LOCATION OF WELL: Owner's No. #6

CITY AND
STATE:

(b) (6)

SE 1/4 NE 1/4 Sec. 22 T. 1 N. E.
S. R. 3 W. W.M.

Bearing and distance from section or subdivision

corner For location see sketch on map

Altitude at well 26'


TYPE OF WELL: Drilled Date Constructed 1950

Depth drilled 200' Depth cased 200'

CASING RECORD:

18" from 0 to 140 ft.

12" from 119 to 200 ft.



Section 22

FINISH:

Perforated from 119 to 200 ft.

AQUIFERS:

WATER LEVEL:

17'

PUMPING EQUIPMENT: Type Peerless turbine

HP. 75

Capacity 1200 G.P.M.

WELL TESTS:

Drawdown 12 ft. after hours 1200 G.P.M.

Drawdown 14 ft. after hours 1500 G.P.M.

USE OF WATER Dom. Irrigation & Manuf. Temp. °F. 19

SOURCE OF INFORMATION GR Record

DRILLER or DIGGER

ADDITIONAL DATA:

Log Water Level Measurements Chemical Analysis Aquifer Test

REMARKS: Irrigation of 170 acres.

Log: Top soil & yellow clay

Yellow sand

Blue quicksand

Fine gray sand

Brown silt

Fine gray sand - gray clay binder

Coarse sand - small gravel - gray clay binder 136 to 158 ft.

Coarse sand - small gravel - water bearing 158 to 200 ft.

0 to 16 ft.

16 to 27 ft.

27 to 49 ft.

49 to 82 ft.

82 to 94 ft.

94 to 136 ft.

136 to 158 ft.

158 to 200 ft.

COLUMBIA
RIVER
SANDS
AQUIFER

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT
SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

MULT

001251

State Well No.

State Permit No.

(1) OWNER:

Name (b) (6)

Address

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Cable ☐ Dug ☐
Driven ☐ Jetted ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒
Diam. from 6 in. to 0 ft. to 227 ft. Gage 250
Diam. from 5 in. to 0 ft. to 227 ft. Gage 250
Diam. from 5 in. to 0 ft. to 227 ft. Gage 250

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.
perforations from 0 ft. to 227 ft.
perforations from 0 ft. to 227 ft.
perforations from 0 ft. to 227 ft.

(7) SCREENS:

Well screen installed? ☒ Yes ☐ No

Manufacturer's Name IOP Johnson

Type stainless Model No.

Diam. 6 Slot size 15 Set from 228 ft. to 233 ft.

Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

60 gal./min. with 0 ft. drawdown after hrs.

Ballot test 60 gal./min. with 0 ft. drawdown after 1 hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used cement

Well sealed from land surface to 20 ft.

Diameter of well bore to bottom of seal 10 in.

Diameter of well bore below seal 6 in.

Number of sacks of cement used in well seal 9 sacks

Was cement grout placed? pumped

Drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.Do strata contain unusable water? ☐ Yes ☒ No

Water? depth of strata

Method of sealing strata off

Well gravel packed? ☐ Yes ☒ No Size of gravel:

(10) LOCATION OF WELL:

County Multnomah Driller's well number
SW 1/4 SW 1/4 Section 34 T. 1N R. 3E W.M.

Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 30 ft.

Static level 25 ft. below land surface. Date 12-19-79

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6

Depth drilled 233 ft. Depth of completed well 233 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated.
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
mucky sand	0	16	
mucky sand & clay	16	30	
sand, water	30	85	
sand, wood, water	85	100	
sand	100	135	
sand, water	135	180	
sand & water some silt	180	222	25
sand & gravel water	222	233	

RECEIVED

DEC 19 1979

WATER RESOURCES DEPT

Work started 12-14 1979 Completed 12-19 1979

Date well drilling machine moved off of well 12-19- 1979

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Jim D. Hansen Date 12-20 1979

(Drilling Machine Operator)

Drilling Machine Operator's License No. 847

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Hansen Drilling Co., Inc.

(Person, firm or corporation) (Type or print)

Address 6711 NE 58th Ave. Vancouver, WA.

[Signed] Marvin Sample (Water Well Contractor)

State Well No. 1N/3-14
State Permit No. MULT
00125

[Signed] George H. Ryan

Appendix F
Quality Assurance Sampling Plan

OU1 Quality Assurance Sampling Plan for: Reynolds Metals Facility Troutdale, Oregon

1.0 Background

The Reynolds Metals Facility is a primary aluminum reduction plant that has operated on an 80-acre site outside Troutdale, Oregon since 1942. To address the complex nature of this site with multiple production processes, waste streams, and disposal practices, the site has been divided into operable units (OUs) based on media, waste source type, and site geographical location. OU 1 encompasses the south and east potliner disposal areas, the cryolite pond, the facility scrapyard, the wetlands area, the north industrial landfill, and the parking lot. The media of concern include surface soil, subsurface soil, surface water, sediment, and groundwater.

The types of activities at this site that contributed to the wastes of concern to the Environmental Protection Agency's (EPA's) on-scene coordinator (OSC) include: reduction of alumina to aluminum metal and associated production processes; onsite disposal of potliners (carbon-lined reduction cells, a listed hazardous waste with waste identification number K088) and other production waste streams; the alleged use of potliners as a fill material in the construction of the facility parking lot; the alleged storage/disposal of polychlorinated biphenyl (PCB)-contaminated debris in the potliner disposal area; the recovery of cryolite in the cryolite recovery pond; and the release of free elemental mercury and other potentially hazardous substances from facility equipment discarded at the onsite scrapyard.

The major soil contaminants identified in Reynolds Metals facility soil and summarized in the Site Inspection Prioritization (SIP) report (PRC 1993) are listed in Table 1. The concentrations are of concern because they are elevated above background sample levels and/or risk-based concentrations established by the State of Oregon and EPA (E & E 1994). PCBs are also a contaminant of concern based on extensive historical use of


electrical equipment that contains PCB oils. Although in a previous investigation different media were sampled for PCBs, all of the analytical data were rejected because of organic interferences, hence, there is no PCB information available for the site.

Table 1 Constituents and Concentrations of Concern in Soil	
Constituent	Concentration (mg/kg)
Total polynuclear aromatic hydrocarbons	4,071
Aluminum	322,000
Copper	8,770
Cyanide	57.6
Fluoride	137,000
Notes	
1. Data from the SIP Report (PRC 1993)	
2. mg/kg = milligrams per kilogram	

The site is located north of the City of Troutdale, in Multnomah County, Oregon (see Figure 1). The nearest residences are located 0.5 mile to the south. Significant environments in the proximity of the site include wetlands located directly adjacent to the south side of the facility and Company Lake with associated wetlands directly north of the facility. Other significant environments include the Sandy River 0.25 mile east of the facility and the Columbia River 0.75 mile to the north.

2.0 Project Objectives

As this site may pose an imminent and substantial threat to public health and/or the environment, time considerations are a significant factor in the design and execution of this plan. The objectives of the proposed field activities are to:



ecology and environment, inc.
International Specialists in the Environment
Seattle, Washington

REYNOLDS METALS COMPANY Troutdale, Oregon



BASE MAP REFERENCE:
1963 7.5 Quad, Canby, Washington 1978
Scale: 1:24,000

Figure 1
SITE LOCATION MAP

Drawn By	Date	TDO Job No.	Dwg. No.
AES	3-1-84	T10-9311-006	1841UN

1. Determine if potliners and other wastes are present in the south or east potliner disposal area, the cryolite pond, beneath the parking lot, in the north industrial landfill, or in the south wetlands.
2. If potliners are found, perform an extent of contamination (EOC) in the vertical and horizontal directions. If potliners are not found, perform a limited EOC survey of contaminated soil in the south and east potliner disposal areas, the cryolite pond, and in the parking lot.
3. Design and install a groundwater monitoring well network and sampling program to determine depth to groundwater, hydraulic gradient, and extent of shallow groundwater contamination, if present, attributable to past practices related to potliner disposal or other sources.
4. Conduct an EOC survey of contaminated surface and subsurface soil in the scrapyard area.
5. Conduct a reconnaissance of the floodplain area (between the Sandy and the Columbia Rivers) and other target areas. Document suspicious stains, ground surface features and disturbances and collect grab samples as needed.
6. Collect groundwater samples from existing onsite production wells for water quality analysis. Perform quality assurance (QA) level 3 analysis on Reynolds' production well number 18 (PW-18) to establish level of confidence in deep groundwater quality data.
7. Collect sediment samples from Company Lake near the refractory brick debris pile on the Corps of Engineers (COE) dike to check for indications that PCBs may have leaked from capacitors alleged to have been buried in

the dike. If feasible, conduct a surface geophysical survey in selected areas in an attempt to locate the site where capacitors were allegedly disposed.

8. Collect sediment/surface water samples from the Company Lake outflow to the Columbia River to determine if contaminants related to site operations are present.

The data will be screened against EPA Region 10 Supplemental Risk Assessment Guidance for Superfund Criteria; EPA Safe Drinking Water Act National Primary and Secondary Drinking Water Regulations; EPA Region 3 Risk-Based Concentration Table Values; Oregon Department of Environmental Quality (DEQ) Environmental Cleanup Rules; Guidelines for the Protection and Management of Aquatic Sediment Quality in Ontario; State of Wisconsin Guidelines for Maximum Allowable Concentrations of Contaminants in Great Lake Sediments; and EPA Federal Water Quality Criteria for Surface Waters; although these criteria ultimately may or may not be applicable or appropriate for setting cleanup criteria for affected media at this site.

3.0 Quality Assurance Objectives

In accordance with the objectives outlined in Section 2.0, and the QA levels defined by the EPA (EPA 1990c), the sampling and analyses performed under this sampling effort will conform to the use and QA criteria summarized in Table 2.

Table 2 Data Use and Quality Assurance Objectives			
Parameter	Matrix	Intended Data Use	QA Objectives
Cyanide	Soil, air, sediment, water	Assessment, EOC, risk determination	QA 2
TPAH	Soil, air, sediment, water	Assessment, EOC, risk determination	QA 2
Metals	same	same	QA 2
Fluoride	same	same	QA 2
PCBs	same	same	QA 2
Cyanide, metals	1 PW water	Bias, level of confidence in laboratory's performance	QA 3

4.0 Methodologies

4.1 Samples

All samples will be collected, identified, and handled, and all documentation and chain of custody procedures will be conducted in accordance with Region 10 Removal Program guidelines and protocols. The QA Level 2 and 3 QA Requirements and QA 2 Validation Requirements will be as mandated by EPA guidelines (EPA 1990c). Other operating procedures that will be used in this sampling effort are generally consistent with those described in Appendix B of the Technical Assistance Team's Sampling Plan for the Reynolds Metals Troutdale Facility (E&E 1994). These include:

Field Logbook	Geoprobe Large Bore Sampler SOP
Sample Equipment Decontamination	Sample Documentation
Soil Sampling	Waste Pile Sampling
Monitoring Well Installation	Surface Water Sampling
Well Development	Sediment Sampling
Water Level Measurement	General Air Sampling Guidelines
Groundwater Well Sampling	Immunoassay Field Screening QA/QC
Potable Water Sampling	GPS Draft SOP—under development

The equipment listed in Table 3 will be used to obtain samples during the course of this project.


Table 3 Sampling Equipment Description			
Matrix	Sampling Equipment	Fabrication	Dedicated
Soil	Geoprobe Large Bore Sampler	Steel	No
	with acetate liner	Plastic	Yes
	Split-spoon sampler	Steel	No
	Bowls and spoons	Stainless Steel	Yes
	Sample Containers	Glass	Yes
Sediment	Ekman Dredge (or equivalent)	Steel	No
	Bowls and Spoons	Stainless Steel	Yes
	Sample Containers	Glass	Yes
Groundwater	Teflon Bailers	Teflon plastic	No
	Submersible pump	Stainless Steel	No
	Sample Containers	Glass/Plastic	Yes
Surface water	Sample Containers	Glass/Plastic	Yes
Ambient air (as needed)	HIVOL Air Samplers	Aluminum	No
	PUFS filters	Polyurethane Foam	Yes
		Quartz Microfibre	Yes
	Filter Papers	Cellulose Acetate	Yes

4.2 Sampling Rationale

The anticipated assessment areas for OU 1 are outlined on Figure 2. Several additional areas have been identified through the initial reconnaissance that will be investigated in addition to the areas shown on Figure 2. These areas are

- The eastern potliner disposal area
- The south wetlands
- The industrial landfill
- The small cryolite ponds

The sampling and analysis strategy is based on the following rationale.



ecology and environment, inc.
 International Specialists in the Environment
 Seattle, Washington

REYNOLDS METAL COMPANY
 Trouldale, Oregon

800' 0 800' 800'
 Approximate Scale in Feet

Figure 2
OPERABLE UNIT ASSESSMENT AREA

Drawn By AES	Date 8-1-84	TDO/Job No. T10-8311-008	Dwg. No. 18713M
-----------------	----------------	-----------------------------	--------------------

General

This section describes the sampling and exploration areas for the Phase 2 soil sampling effort. Soil sampling with backhoe and hand auger will commence the week of July 17 with one crew. Soil exploration with geoprobe will commence the week of July 25. If potliners are identified and initial screening indicates that surface geophysical techniques may be helpful in mapping the extent any identified potliner, as discussed below, the geophysical survey will commence as soon as schedule permits, either the week of August 15 or August 22.

Geophysical methods will be considered for use in mapping the vertical and horizontal extent of the suspected potliner disposal areas. The method which would be used is electromagnetics, using the EM-61, which can detect contrasts in soil or medium conductivity at depths up to about 15 feet. Verification sampling would be performed using hand sampling and geoprobe sampling as discussed below.

Geophysical methods will also be considered for use in attempting to locate the allegedly buried capacitors. A magnetometer will be evaluated for use in scanning the dike adjacent to the COE dike, the north industrial landfill, the north parking lot, and the clearing in the woods near the plant outfall which was noted in aerial photographs. The method may not be effective when in the proximity of the BPA power lines.

In general, soil sampling will be performed either with stainless steel spoons, acetate lined Geoprobe sleeves or stainless steel hand auger. Spoons will be discarded after each sample is taken. A new (dedicated) sleeve will be used for each geoprobe sample, and the geoprobe probe, auger and backhoe bucket will be decontaminated between sampling events or test holes. Where possible, the backhoe bucket and/or auger flight will be decontaminated by pressure washing into the backhoe pit or auger excavation.

For the initial sampling effort, samples will be taken at the intervals discussed below for the various areas. Samples will be composited vertically, where indicated, and discrete samples will also be collected. Based on the initial sample results, additional testing of discrete samples will be conducted. The purpose of compositing the samples is to perform a broad survey to determine the horizontal distribution of the various constituents. If constituents of concern for the Reynolds Metals facility are found in specific areas, discrete samples may be tested to determine the vertical distribution of the constituents.

Test pits will be backfilled with the excavated soil after sampling is completed.

Approximately 10 percent of the screened samples (PCB and TPAH) will be tested by rigorous methods in the laboratory. A complete list of proposed laboratory tests including methods and numbers of tests will be developed as the project progresses.

This document is intended to be a planning tool, and as such, may be revised as the project progresses and as actual conditions are uncovered in the field. For example, if it is not possible to penetrate the potliner area with the geoprobe, it may be better to perform additional exploration with the backhoe. Similarly, if geophysics are not appropriate for exploration of the potliner disposal area, more backhoe pits may be employed to help determine the lateral and vertical EOC.

Potliner Disposal Area

The rationale for exploring and sampling in this area is to determine the lateral and vertical extent of any remnant potliner and any remnant contamination.

Initial exploration:

- Dig 11 test pits to native ground (if possible), or to 7.5 feet, or to the groundwater table.
- Sample at surface, 2.5 feet, 5 feet, and 7.5 feet.
- Identify potliner visually and confirm with limited laboratory analytical.
- Soil samples will be screened in the laboratory for TPAH, cyanide, and fluoride.
- Selected soil samples will be screened for 13 metals and PCBs.

If potliners are found:

- Screen potliner matrix and native soil for electrical resistivity using conventional hand-held soil resistivity gear.
- If contrast in resistance between potliner matrix and native soil is adequate, plan to determine lateral and vertical extent of contamination with geophysical methods (EM).
- Do confirmation borings with Geoprobe. Estimate four Geoprobe holes to a depth of 10 feet, or to the groundwater table. Sample continuously and test 0-2 foot interval, 2-4 foot interval, 4-6 foot, etc.

If potliners are not found:

- Do confirmation borings with Geoprobe. Do 8 probes to maximum depth of 10 feet, or to groundwater table. Sample continuously and test as above.

Cryolite Pond and Small Cryolite Ponds

The rationale for sampling in the cryolite pond area is to determine the lateral and vertical EOC and potential migration patterns. The following work will be conducted:

- Drill two test holes in the main cryolite pond using a power auger.
- Drill one test hole in each of two smaller ponds using a hand auger.
- Drill two test holes in native ground adjacent to the main cryolite pond using a hand auger.
- Take samples at the surface, 2.5-foot depth and the 5-foot depth.
- Perform laboratory screening on composite samples for TPAH, cyanide and PCB. Perform laboratory testing for fluoride and 13 metals from discrete samples from native soil (if encountered).
- Make visual estimate of the horizontal extent of cryolite and measure using survey techniques.

Parking Lot

The rationale for sampling in the parking lot is to investigate past allegations that potliners may have been used as fill for the parking lot. The following work will be conducted:

- Perform four test probes using the Geoprobe in the parking lot area to a maximum depth of 7 feet (or to groundwater).
- Take samples from the following depth intervals: 1-3 feet, 3-5 feet, and 5-7 feet.
- Perform laboratory screening tests on discrete samples for TPAH, cyanide, and fluoride.
- Based on the laboratory results, if potliners are indicated, plan additional Geoprobe holes to determine the horizontal and vertical EOC.

Scrapyard

The SIP sampling showed elevated concentrations of TPAH and metals. The rationale for the sampling will be to determine the vertical and horizontal extent of contamination.

- Perform up to 15 backhoe test pits in the scrapyard.
- Take samples from 0-2 foot interval and 2-4 foot.
- Perform laboratory screening on composite samples for TPAH, cyanide, fluoride and PCBs.

- Perform laboratory screening for 13 metals on selected samples, primarily in the area where mercury was cleaned up in 1993.

Eastern Potliner Area

During the groundwater investigations, suspected potliner was discovered at the eastern end of the site. The purpose of investigating in this area is to determine the lateral and vertical EOC.

- Excavate 8 test pits in the area to a depth of 4 feet or to the groundwater table.
- Take samples at surface, 2-, and 4-foot depths.
- Perform laboratory screening on composite soil samples for TPAH, cyanide and fluoride.
- Perform laboratory screening for PCBs and 13 metals on selected samples if the area appears to be a scrapyard.
- If buried potliner is discovered, geophysical methods will be considered similar to those discussed above to determine the lateral and vertical EOC.
- Based on the field investigations and laboratory analysis, plan additional Geoprobe holes or test pits to confirm lateral and vertical EOC.

South Wetlands

No samples were taken in the south wetlands area during the SIP. Early aerial photographs indicate that the wetlands area served as a process water discharge pond

during the early years of the plant operation. The rationale for sampling in the wetlands is to determine whether contamination is present (incidence of contamination, or IOC).

- Perform 5 hand auger borings to depth of 3 feet.
- Take samples at surface and at the 3-foot depth.
- Perform laboratory screening on composited samples for TPAH, PCB, cyanide, fluoride, 13 metals, TPH and pesticides.
- Based on the field investigations and laboratory analysis, plan additional field investigations to determine lateral and vertical EOC.

North Industrial Landfill

Sampling and analysis performed by CH2M HILL in June 1994 in the industrial landfill east of the road showed elevated levels of PAH and PCB, as well as some asbestos. The rationale for sampling west of the road is to determine the relative concentration of constituents in the landfill.

- Perform eight test pits up to 12 feet deep (to groundwater or to native ground).
- Take up to three samples per test pit.
- Perform laboratory screening on composite samples for TPAH, PCB, 13 metals, cyanide, fluoride, and asbestos (if indicated).
- Visually determine horizontal extent of landfill and measure using survey techniques.

Miscellaneous Sampling Areas

Several additional disturbed areas were noted during initial site reconnaissance activities and were sampled. These areas were:


- The stressed-vegetation area south and west of the south potliner area. Surface samples were taken from this area and tested for cyanide, fluoride, PCBs, 13 priority pollutant metals and TPAH.
- The sand preload area southwest of Potline 5 was sampled and tested for cyanide, fluoride, PCBs and TPAH.

Groundwater

Past Work. Detectable concentrations of cyanide and fluoride were detected in groundwater samples collected by PRC from the onsite deep production wells (PRC 1993). These onsite wells supply the facility with process and drinking water.

A total of eight shallow groundwater monitoring wells were installed by Reynolds Metals during the Phase 1 groundwater investigation using hollow stem auger drilling techniques. Monitoring well locations are shown on Figure 3. Monitoring wells were either two or four inches in diameter, depending on the potential for future use as extraction wells, should groundwater remediation be required. The locations of the shallow monitoring were mutually agreed to by Reynolds Metals and EPA on the basis of available information regarding past practices at the Troutdale facility.

A water level monitoring program was initiated soon after well installation by installing data loggers and transducers in the Columbia River and in MW-8, -6, and -5. This



network of continuous groundwater level monitoring will be supplemented by periodic manual measurements in other monitoring wells at the facility. To improve the understanding of groundwater hydraulics at the facility, the data logger network may be adjusted by moving the transducers and loggers to alternative wells.

Ongoing and Future Work. The eight shallow monitoring wells were sampled and samples analyzed during the week of July 18, 1994. After the data from this sampling round has been evaluated, Reynolds Metals will meet with EPA to discuss the results of the sampling event and the results of the water level monitoring program. The need for and location of any additional monitoring wells will be established at that time. If indicated by the data collected during Phase 1 or other information regarding past practices at the Troutdale facility, additional monitoring wells will be installed using similar techniques as used for Phase 1 monitoring wells. After their installation, Phase 2 monitoring wells, selected Phase 1 monitoring wells, and selected production wells will be sampled and the samples analyzed for a list of constituents agreed upon by Reynolds Metals and EPA.

The scope of any ongoing, periodic groundwater monitoring program for the facility will be determined as indicated on the basis of the results of sampling and analysis conducted during the Phase 1 and Phase 2 monitoring well installation programs.

Sample Analysis. Groundwater samples collected by CH2M HILL for Reynolds Metals will be analyzed in the laboratory for total petroleum hydrocarbons (TPH), volatile organic compounds (VOC), semivolatile organic compounds, plus polynuclear aromatic hydrocarbons (PAH), PCBs, pesticides, total cyanide (supplemented by a free cyanide analysis if total cyanide analysis yields detectable concentrations of cyanide), fluoride, and EPA's toxic analyte list of 23 metals. Groundwater samples will be analyzed in the field for temperature, pH, and electrical conductivity.

Surface Water and Sediments

Reynolds Metals proposes to collect surface water samples at the following locations:

- From the outflow from Company Lake before it empties into the Columbia River to assess the quality of water flowing into the river from Company Lake.
- From the Columbia River near the Company Lake outfall to assess the water quality in the Columbia River downstream of the Company Lake discharge.
- From the Columbia River upstream of the Sandy River confluence to provide background river water quality data.
- From the eastern part of Company Lake to assess water quality away from the main inflow/outflow pattern in Company Lake.
- From Salmon Creek just downstream of the reported connection between the creek and the plant waste water collection ditch to assess possible impacts to the creek water quality.

Sediment samples will be collected from the following locations:

- From the Company Lake drainage ditch before it empties into the Columbia River to assess concentrations of sediments potentially entering the river.
- Two samples from the Columbia River, one east and one west of where the Company Lake discharge ditch enters the river, to assess sediment

concentrations near the Company Lake discharge. Two samples will be collected because of observed backwater flow patterns in the Columbia River at the Company Lake discharge.

- Two samples from the Columbia River upstream of the Sandy River confluence to provide background sediment quality data.
- Five samples from Company Lake, three in the eastern part of the lake to assess possible effects of the debris pile, one in the middle part of the lake, and one in the western part of the lake.
- Two samples from Salmon Creek, one just downstream of the possible connection with the plant waste water collection ditch and one near Reynolds Metals' property boundary.

In the SIP effort, all sample results for PCB analyses were qualified as rejected because of organic interferences. In this investigation, the samples will undergo a modified cleanup step in the laboratory in an attempt to obtain acceptable data.

Reconnaissance

Visual reconnaissance on foot and bicycle will be performed in accessible areas of the wooded floodplain area between the Columbia and Sandy Rivers. Stained and disturbed soil locations and unusual ground surface features will be documented. A minimum of one surface soil or product grab sample will be collected at each suspicious location.

Reconnaissance will be performed on the south and west boundaries of the south wetlands area with the intent of noting any cross drainages and/or any unmapped influent pipes, gates, overflows or structures. Any unusual features and/or sample locations which are noted during the reconnaissance will be marked and subsequently surveyed in.

In March 1994, 650 tons of soil containing Bunker-C fuel oil was excavated from the area northeast of the fuel tanks and disposed at the Waste Management facility in Arlington, Oregon. Diesel contamination was discovered below the excavated oil. Soil samples were collected and analyzed for TPH, PCBs, Volatile Organic Compounds and the toxicity characteristic leaching procedure for 8 metals. The oil contamination below the excavated soil was found to be diesel and heavy oil; no PCBs, VOCs or metals were detected.

Onsite Production Wells

The five production wells sampled during the EPA's site investigation will be resampled and analyzed for the same constituents as monitoring wells. Production well sampling will occur during the same sampling effort as the Phase 2 monitoring wells.

Surveying and Geographic Information System

Sample locations and elevations will be determined using standard survey techniques. Monitoring well elevations will be determined by differential levelling techniques using the WILD NA2 optical level. Vertical elevations will be referenced to National Geodetic Vertical Datum (NGVD) and will be accurate to 0.01 foot. A first-order control point has been identified near the site and the elevation datum has been transferred to the site.

All well locations and soil sample locations and elevations will be surveyed using either a WILD T1600 total station theodolite with a DI2000 EDM or a Trimble 4000 GPS system. Horizontal control has been established using the Trimble 4000 GPS system. Because it is not possible to survey all locations using GPS because of the tree cover north of the dike, some locations will require survey by manual techniques. Horizontal control will be referenced to State-Plane coordinates.

All horizontal and vertical coordinates for all wells and sampling locations will be stored in an electronic data package which is compatible with the existing GIS mapping for the Reynolds Metals Troutdale facility.

Air Sampling

As part of the site-specific health and safety plan, the following air monitoring equipment will be used during site activities:

- Flame ionization or photoionization organic vapor detector
- Hydrogen cyanide meter
- Combustible gas meter (invasive activities only)
- Oxygen meter (invasive activities only).

Fugitive dust emissions are not anticipated to be generated during site investigation activities, with the exception of test pits being excavated by backhoe. Each test pit and spoils pile will be sprayed with water periodically during excavation if dust is observed. In the unlikely event it will not be possible to prevent dust migration offsite during test pit excavation activities because of a combination of dry soil conditions and high wind velocities, perimeter air monitoring will be instituted.

4.3 Sample Types and Quantities

The proposed OU 1 assessment areas, other reconnaissance/assessment areas, the sample collection activities, the estimated number of samples, and the required QA/QC samples for each activity are listed in Table 4.

Table 4
Sample Locations and Quantities

Area	Activity	No. Composite Samples	Laboratory Composite Analysis	No. Discrete Samples	Laboratory Discrete Analysis	Comments
Soil Sampling						
Eastern Potliner	8 test pits	9	TPAH, PCB, CN	27	TBD	
Southern Potliner	11 test pits	13	TPAH, PCB, F, CN	34	TBD	11 composites analyzed for 13 metals
North Landfill SHN	4 test pits	4	TPAH, PCB, F, CN	10	TBD	3 composites analyzed for 13 metals
North Landfill EHW	3 test pits	3	TPAH, PCB, F, CN	9	TBD	2 composites analyzed for 13 metals
Scrap Yard	15 test pits	13	TPAH	40	TBD	3 composites analyzed for 13 metals
Parking Lot	4 geoprobe holes			12	TPAH, CN, PCB	
Cryolite Pond	6 hand auger holes	4	TPAH, PCB, CN	15	TBD	2 composites analyzed for fluoride
South Wetlands	5 hand auger holes	5	TPAH, PCB, CN, F, pesticides, TPH	10	TBD	
Stressed Veg.	2 hand auger holes	2	TPAH, PCB, CN, F, pesticides, 13 priority pollutant metals	4	TBD	
Reconnaissance Activities						
Soil/Product	Estimate 10	0	0	10	TBD	
Surface Water/Sediment						
Water	Company Lake, Columbia River, Salmon Creek	0	0	5	PAH, PCB, cyanide, fluoride, TAL metals	

Sediment	Company Lake, Columbia River, Salmon Creek	0	0	12	PAH, PCB, cyanide, fluoride, TAL metals	
Monitoring Well Installation and Sampling						
Soil	12 boreholes, 3 soil samples per borehole	0	0	36	PAH, PCB, TPH, cyanide, fluoride, TAL metals	Samples screened in laboratory for TPH, PCB, PAH. Fluoride, metals and cyanide are standard laboratory analysis. 10 percent of soil samples will be analyzed for TPH, PCB, and PAH to confirm data.
Water	12 wells	0	0	12	VOC, SVOC plus PAH, PCB, TPH, pesticides, cyanide, fluoride, TAL metals	
Production Wells						
Water	5 wells	0	0	5	VOC, SVOC plus PAH, PCB, TPH, pesticides, cyanide, fluoride, TAL metals	
TBD = To be determined						

4.4 Equipment Decontamination

Decontamination procedures will be generally consistent with those described in Appendix B of the Technical Assistance Team's Sampling Plan for the Reynolds Metals Troutdale Facility (E&E 1994). Geoprobe rods and drilling auger flights will be decontaminated with a pressure washer or steam cleaner and then air dried.

4.5 Investigation-Derived Wastes (IDW)

Disposable personnel protective equipment and sampling equipment will be bagged, drummed, labeled, and left onsite. Purge and decontamination water and drill cuttings will be drummed and left onsite. Field screening and laboratory waste will be segregated according to waste stream, drummed, and stored onsite. All IDW remaining onsite will be placed in a secure location until appropriate disposal is arranged.

4.6 Schedule of Activities

The proposed schedule of work is as follows:

Activity	Anticipated Level of Effort
Pre-mobilization, analytical setup	1 week
Site assessment activities	3 weeks
Analytical reporting	4 weeks
Data validation	4 weeks
Report generation	4 weeks

5.0 Quality Assurance/Quality Control Requirements

5.1 Analytical Parameters

The types of analyses required for the satisfactory completion of this project have been determined by the OSC. Analytical parameters are summarized by sample types and quantities in Table 5.

5.2 Quality Control Measures

Quality control checks for sample collection will be accomplished by a combination of collocated/replicate samples; background samples; rinsate blank samples; chain-of-custody protocols; and laboratory quality assurance.

Quality control measures for laboratory screening will include: collect and field analyze uncontaminated sample from site matrix to document matrix effect; for each batch of 20 samples, one blind duplicate will be analyzed to document method repeatability; on a daily basis, one extract spike on a sample previously determined to be below the lowest test level will be performed and analyzed; on a daily basis, a performance evaluation sample will be analyzed to document method/operator performance.

At least 10 percent of all of the samples analyzed by laboratory screening methods onsite will be submitted to the analytical laboratory for confirmatory analysis of the field screened analytes by an EPA-approved laboratory method. Samples submitted for confirmatory analyses will be selected to represent the response range of the field analyses (samples that tested below the lowest level, above the upper test level, and if applicable, between two test levels).

To assess the effectiveness of the decontamination procedures on the Geoprobe large bore sampler and the drill rig split spoon sampler, a final rinsate blank sample will be

Table 5
QA/QC Analysis and Objective Summary

Matrix *	Analytical Parameter	Analytical Method (ref)	Spikes		QA/QC	
			Matrix ¹	Surrogate ²	Detect Limits ³	DQO ⁴
S SD	TPAH	CL-EPA 8270 SIM	10 ES 4/4	10 PE 34	10 ppm 1 ppm	QA-2
S SD	PCBs	CL-EPA 8080	10 ES 3/3	10 PE 24	1 ppm 0.5 ppm	QA-2
S SD	Cyanide	CL-EPA 335.2	17 4/4	10 PE NA	0.5 ppm 0.5 ppm	QA-2
S SD	Metals	CL-EPA 6010 CL-EPA 7470	37/37	NA	1 ppm 0.2 ppm	QA-2
S SD	Fluoride	CL-EPA 340.2	NA	NA	1 ppm	QA-2
W	SOC + all PAHs	CL-EPA 8270 SIM	3/3	25	same	QA-2
W	Cyanide	CL-EPA 335.2 CI-335.1	3/3	NA	same	QA-2 QA-3
A	Inorganics PAHs, PCBs TSP	CL-EPA 6010A/7000 CL-EPA 8270A, 8310, 8080 FS-field method	3/3 3/3 NA	NA 140 NA	low conc.	QA-2

Notes:

*=Matrix: S = soil; W = water; O = oil; DS = drummed solids; DL = drummed liquids; TS = tank solids; TL = tank liquids; A = air; SD = sediments; X = other

1=Matrix Spike/Matrix Spike Duplicate: at a rate of 1 per 10 samples for QA 2 and 1 per 5 samples for QA 3. For laboratory screening the extract will be spiked.

2=1 for each sample for QA 2 and QA 3 (otherwise specify NA). PE = Performance Evaluation Sample-No surrogate required in screening analysis.

3=To be determined at the time that laboratory selection is made.

4=Data Quality Objective for analysis (enter QA 1, QA 2, or QA 3).

FS=Field Screening; ES = Extract Spike; CL = Commercial Laboratory; SOC = Synthetic Organic Compounds; IOC = Inorganic Compounds; SD = Sediment.

collected from each piece of equipment listed above at least once each day that sampling is being conducted.

5.3 Data Quality Assurance Review

The data validation review of data packages will include an evaluation of: the information provided on the analytical data sheets and required support documentation for all sample analyses; the supporting sample collection documentation, including chain-of-custody; and field instrument calibration and/or performance check documentation (if required by method). The QA review will also examine adherence to the procedures as described in the cited SOPs and the requested analytical methods.

6.0 Deliverables

Laboratory deliverables will be as specified in the Quality Assurance Objectives Section (Section 3.0), in ARC/INFO format.

Reynolds Metals' Project Manager will provide an interim update to the OSC within 2 weeks after the completion of the field work that will include preliminary data tables, a site map, and a verbal debriefing.

The Reynolds Metals Project Manager will provide a site assessment report within 12 weeks of project completion.

7.0 Data Validation

The data validation requirements for each DQO specified in Table 5 are included in the Interim Final Guidance for the Quality Assurance/Quality Control for Removal Activities (EPA, 1990c).